

# B-FB4 - WAHLBURGERS

## SARASOTA BRADENTON INTERNATIONAL


6000 AIRPORT CIRCLE, SARASOTA, FL 34243

ISSUED FOR PERMIT  
08/16/2024

**ENV**  
ARCHITECTURE + DESIGN  
180 SYLVAN AVENUE, SUITE 3  
ENGLEWOOD CLIFFS, NJ 07632  
TEL 201 | 894 | 1000  
ENV-team.com  
ENVIRONETICS GROUP ARCHITECTS, P.C.  
COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED

CLIENT:  
**SSP AMERICA**  
20408 BASHAN DRIVE  
SUITE 300  
ASHBURN, VA 20147

PROJECT TEAM:  
ARCHITECT:  
ENVIRONETICS GROUP ARCHITECTS  
180 SYLVAN AVE.  
ENGLEWOOD CLIFFS, NJ 07632  
MEP ENGINEER  
GUTH DECONZO CONSULTING  
ENGINEERS, PC  
520 8TH AVENUE, SUITE 2201  
NEW YORK, NY 10001



### SITE LOCATION



SARASOTA AIRPORT

### PROJECT TEAM

**CLIENT**  
SSP AMERICA  
20408 BASHAN DRIVE  
SUITE 300  
ASHBURN, VA 20147

**ARCHITECT**  
ENVIRONETICS GROUP ARCHITECTS  
180 SYLVAN AVE.  
SUITE 3  
ENGLEWOOD CLIFFS, NJ 07632  
201-894-1000

**ARCHITECT OF RECORD**  
HANS ERDENBERGER  
201-894-1000  
HANS@ENV-NJ.COM

**PROJECT MANAGER**  
DEASY CAMPIONE  
201-894-1000  
DCAMPIONE@ENV-NJ.COM

**MEP ENGINEER**  
GUTH DECONZO CONSULTING  
ENGINEERS, PC  
520 8TH AVENUE, SUITE 2201  
NEW YORK, NEW YORK 10001

**ENGINEER OF RECORD**  
JOHN GUTH  
212 967 4306  
JGUTH@GUTHDECONZO.COM

**PROJECT MANAGER**  
HASSAN AMMAR  
212 967 4306  
HAMMAR@GUTHDECONZO.COM


**FOOD SERVICE CONSULTANT**  
IKITCHEN CONCEPTS  
PROJECT MANAGER  
EDWARDS GONZALES  
817-300-8762  
EDWARD@IKITCHENCONCEPTS.COM

### RENDERING

NOTE: IMAGES ARE FOR CONCEPT ONLY, REFER TO ARCHITECTURAL SHEETS FOR ELEVATIONS AND FINISH DETAILS



### KEY PLAN



### APPLICABLE CODES

BUILDING SHALL BE CONSTRUCTED TO BE IN COMPLIANCE WITH THE LISTED CODES, AND THE MOST CURRENT VERSION OF THE AIRPORT TENANT CONSTRUCTION REVIEW MANUAL:

- 2023 FLORIDA BUILDING CODE, 8TH EDITION
- 2023 FLORIDA MECHANICAL CODE, 8TH EDITION
- 2020 FLORIDA ELECTRICAL CODE
- 2023 FLORIDA FIRE PREVENTION CODE
- 2023 FLORIDA PLUMBING CODE, 8TH EDITION
- 2023 FBC ENERGY CONSERVATION CODE, 8TH EDITION
- 2020 NFPA FIRE PREVENTION
- 2016 ADA STANDARDS FOR TRANSPORTATION FACILITIES
- 2010 ADA STANDARDS FOR ACCESSIBILITY
- 2009 ICC A117.1- 2009 BARRIER FREE CODE

### SCOPE OF WORK

THIS IS A RENOVATION PROJECT TO THE EXISTING SPACE B-FB4 GULF BREEZE. THE NEW CONCEPTS WILL BE CALLED WAHLBURGERS, WHICH IS A FULL RESTAURANT AND BAR WITH A KITCHEN. THIS RENOVATION WILL INCLUDE DEMOLITION OF THE EXISTING AND A FULL CONSTRUCTION OF THE SPACE, INCLUDING MECHANICAL, ELECTRICAL, PLUMBING, SPRINKLER, AND FIRE ALARM.

**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA

| REV                 | DATE              | DESCRIPTION |
|---------------------|-------------------|-------------|
| DESIGN DELIVERABLE: | ISSUED FOR PERMIT |             |
| ISSUE DATE:         | 08/16/2024        |             |

|                 |        |
|-----------------|--------|
| PROJECT NUMBER: | 24017G |
| DRAWN BY:       | MK, JP |
| CHECKED BY:     | DC     |

Copyright (c) by Environetico, Inc. All Rights Reserved.

SHEET TITLE:  
**TITLE SHEET**


SHEET NUMBER:  
**T-100**

REVIT 2023

**ENV**  
**ARCHITECTURE + DESIGN**  
 180 SYLVAN AVENUE, SUITE 3  
 ENGLEWOOD CLIFFS, NJ 07632  
 TEL 201 | 894 | 1000  
**ENV-team.com**  
 ENVIRONETICS GROUP ARCHITECTS, P.C.  
COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED

CLIENT:  
**SSP AMERICA**  
 20408 BASHAN DRIVE  
 SUITE 300  
 ASHBURN, VA 20147

PROJECT TEAM:  
 ARCHITECT:  
 ENVIRONETICS GROUP ARCHITECTS  
 180 SYLVAN AVE.  
 ENGLEWOOD CLIFFS, NJ 07632  
 MEP ENGINEER  
 GUTH DECONZO CONSULTING  
 ENGINEERS, PC  
 520 8TH AVENUE, SUITE 2201  
 NEW YORK, NY 10001



**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA

| SHEET #       | SHEET NAME   | 30% DESIGN SUBMISSION 05.09.2024 | ISSUE FOR 90% REVIEW 07.26.2024 | ISSUE FOR PERMIT 08.16.2024 |
|---------------|--|----------------------------------|---------------------------------|-----------------------------|
| GENERAL       |  |                                  |                                 |                             |
| T-100         | TITLE SHEET  | •                                | •                               | •                           |
| T-101         | DRAWING INDEX  | •                                | •                               | •                           |
| GN-100        | GENERAL NOTES  | •                                | •                               | •                           |
| GN-101        | SYMBOLS AND ABBREVIATIONS                                      | •                                | •                               | •                           |
| GN-102        | ADA SHEET  | •                                | •                               | •                           |
| GN-103        | RESPONSIBILITY MATRIX  | •                                | •                               | •                           |
| ARCHITECTURAL |  |                                  |                                 |                             |
| EG-101        | EGRESS PLAN  | •                                | •                               | •                           |
| AD-101        | BARRICADE AND DEMOLITION PLAN                                  | •                                | •                               | •                           |
| AD-102        | CORING PLAN  | •                                | •                               | •                           |
| AD-110        | DEMOLITION REFLECTED CEILING PLAN                              | •                                | •                               | •                           |
| AD-401        | CORING AND BARRICADE DETAILS                                   | •                                | •                               | •                           |
| A-001         | PARTITION TYPES  | •                                | •                               | •                           |
| A-002         | PARTITION DETAILS  | •                                | •                               | •                           |
| A-003         | DOOR SCHEDULES   | •                                | •                               | •                           |
| A-101         | CONSTRUCTION PLAN  | •                                | •                               | •                           |
| A-110         | REFLECTED CEILING PLAN   | •                                | •                               | •                           |
| A-112         | TYPICAL CEILING DETAILS  | •                                | •                               | •                           |
| A-113         | CEILING SECTION DETAILS  | •                                | •                               | •                           |
| A-120         | FINISH PLAN  | •                                | •                               | •                           |
| A-121         | FINISH SCHEDULE AND TYPICAL FINISH DETAILS                     | •                                | •                               | •                           |
| A-130         | MILLWORK PLAN  | •                                | •                               | •                           |
| A-131         | MILLWORK ENLARGED PLANS, ELEVATIONS, AND DETAILS               | •                                | •                               | •                           |
| A-132         | MILLWORK ENLARGED PLANS, ELEVATIONS, AND DETAILS               | •                                | •                               | •                           |
| A-140         | FURNITURE & EQUIPMENT PLAN                                     | •                                | •                               | •                           |
| A-150         | POWER & DATA PLAN  | •                                | •                               | •                           |
| A-200         | ELEVATIONS   | •                                | •                               | •                           |
| A-201         | SIGNAGE DETAILS  | •                                | •                               | •                           |
| A-451         | TYPICAL FIRESTOPPING DETAILS                                   | •                                | •                               | •                           |
| A-452         | TYPICAL FIRESTOPPING DETAILS                                   | •                                | •                               | •                           |
| A-453         | TYPICAL FIRESTOPPING DETAILS                                   | •                                | •                               | •                           |
| A-454         | TYPICAL FIRESTOPPING DETAILS                                   | •                                | •                               | •                           |
| A-461         | TYP. SEISMIC DETAILS & NOTES                                   | •                                | •                               | •                           |
| FOOD SERVICE  |  |                                  |                                 |                             |
| K1            | FOODSERVICE EQUIPMENT PLAN                                     | •                                | •                               | •                           |
| K2            | FOODSERVICE EQUIPMENT DRAIN PLAN                               | •                                | •                               | •                           |
| K3            | FOODSERVICE EQUIPMENT WATER & GAS PLAN                         | •                                | •                               | •                           |
| K4            | FOODSERVICE EQUIPMENT ELECTRICAL PLAN                          | •                                | •                               | •                           |
| K5            | FOODSERVICE EQUIPMENT WALL BLOCKING & BUILDING CONDITIONS PLAN | •                                | •                               | •                           |
| K6            | FOODSERVICE EQUIPMENT ELEVATIONS AND SECTIONS                  | •                                | •                               | •                           |
| K7            | FOODSERVICE EQUIPMENT ELEVATIONS AND SECTIONS                  | •                                | •                               | •                           |
| MECHANICAL    |  |                                  |                                 |                             |
| M-001         | MECHANICAL NOTES, SYMBOLS AND DRAWING LIST                     | •                                | •                               | •                           |
| M-011         | MECHANICAL DEMOLITION PLAN                                     | •                                | •                               | •                           |
| M-101         | MECHANICAL PLAN  | •                                | •                               | •                           |
| M-401         | MECHANICAL DETAILS (SHEET 1 OF 2)                              | •                                | •                               | •                           |
| M-402         | MECHANICAL DETAILS (SHEET 2 OF 2)                              | •                                | •                               | •                           |
| M-501         | MECHANICAL HOOD DRAWINGS (SHEET 1 OF 4)                        | •                                | •                               | •                           |
| M-502         | MECHANICAL HOOD DRAWINGS (SHEET 2 OF 4)                        | •                                | •                               | •                           |
| M-503         | MECHANICAL HOOD DRAWINGS (SHEET 3 OF 4)                        | •                                | •                               | •                           |
| M-504         | MECHANICAL HOOD DRAWINGS (SHEET 4 OF 4)                        | •                                | •                               | •                           |
| M-601         | MECHANICAL SPECIFICATIONS (SHEET 1 OF 3)                       | •                                | •                               | •                           |
| M-602         | MECHANICAL SPECIFICATIONS (SHEET 2 OF 3)                       | •                                | •                               | •                           |
| M-603         | MECHANICAL SPECIFICATIONS (SHEET 3 OF 3)                       | •                                | •                               | •                           |
| ELECTRICAL    |  |                                  |                                 |                             |
| E-001         | ELECTRICAL NOTES, SYMBOLS AND DRAWING LIST                     | •                                | •                               | •                           |
| E-101         | ELECTRICAL POWER PLAN  | •                                | •                               | •                           |
| E-102         | ELECTRICAL COMMUNICATION PLAN                                  | •                                | •                               | •                           |
| E-201         | ELECTRICAL LIGHTING PLAN                                       | •                                | •                               | •                           |
| E-301         | ELECTRICAL RISER   | •                                | •                               | •                           |
| E-401         | ELECTRICAL DETAILS   | •                                | •                               | •                           |
| E-501         | ELECTRICAL SCHEDULES   | •                                | •                               | •                           |
| E-601         | ELECTRICAL SPECIFICATIONS                                      | •                                | •                               | •                           |
| E-602         | ELECTRICAL SPECIFICATIONS-2                                    | •                                | •                               | •                           |
| PLUMBING      |  |                                  |                                 |                             |
| P-001         | PLUMBING NOTES, SYMBOLS AND DRAWINGS LIST                      | •                                | •                               | •                           |
| P-011         | PLUMBING PLAN - LEVEL 1  | •                                | •                               | •                           |
| P-101         | PLUMBING PLAN - LEVEL 2  | •                                | •                               | •                           |
| P-301         | PLUMBING RISER   | •                                | •                               | •                           |
| P-401         | PLUMBING DETAILS   | •                                | •                               | •                           |
| P-402         | PLUMBING DETAILS   | •                                | •                               | •                           |
| P-501         | PLUMBING SCHEDULE  | •                                | •                               | •                           |
| P-601         | PLUMBING SPECIFICATIONS  | •                                | •                               | •                           |
| SPRINKLER     |  |                                  |                                 |                             |
| SP-001        | SPRINKLER NOTES, SYMBOLS AND DRAWING                           | •                                | •                               | •                           |
| SP-101        | SPRINKLER PLAN   | •                                | •                               | •                           |
| SP-401        | SPRINKLER DETAILS  | •                                | •                               | •                           |
| SP-402        | SPRINKLER DETAILS  | •                                | •                               | •                           |
| SP-601        | SPINKLER SPECIFICATIONS  | •                                | •                               | •                           |
| FIRE ALARM    |  |                                  |                                 |                             |
| FA-001        | FIRE ALARM NOTES, SYMBOLS AND DRAWING LIST                     | •                                | •                               | •                           |
| FA-101        | FIRE ALARM PLAN  | •                                | •                               | •                           |

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |


DESIGN DELIVERABLE: ISSUED FOR PERMIT  
 ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G  
 DRAWN BY: MK, JP  
 CHECKED BY: DC

Copyright (c) by Environetia, Inc. All Rights Reserved.

SHEET TITLE:  
**DRAWING INDEX**


SHEET NUMBER:  
**T-101**



CLIENT:  
**SSP AMERICA**  
20408 BASHAN DRIVE  
SUITE 300  
ASHBURN, VA 20147

PROJECT TEAM:  
ARCHITECT:  
ENVIRONETICS GROUP ARCHITECTS  
180 SYLVAN AVE.  
ENGLEWOOD CLIFFS, NJ 07632

MEP ENGINEER  
GUTH DECONZO CONSULTING  
ENGINEERS, PC  
520 8TH AVENUE, SUITE 2201  
NEW YORK, NY 10011



**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA

**GENERAL NOTES**

1. THIS IS STANDARD LEGEND AND NOTES COLUMN. SOME OF THE ITEMS AND/OR NOTES MAY NOT BE APPLICABLE TO THIS SPACE. COORDINATE WITH MECHANICAL, ELECTRICAL AND HVAC DRAWINGS AND REQUIREMENTS WITH CONDITIONS SHOWN ON THE ARCHITECTURAL DRAWING. VERIFY AND COORDINATE BETWEEN THE RESPECTIVE TRADES PRIOR TO THE START OF CONSTRUCTION. NOTIFY THE ARCHITECT OF ANY DISCREPANCIES PRIOR TO PROCEEDING WITH THE WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING WITH THE CM THOSE ITEMS LISTED HEREIN WHICH ARE NOT APPLICABLE TO A PARTICULAR PROJECT.
2. THE CONTRACTOR SHALL FULLY ACQUAINT HIMSELF WITH THE EXISTING CONDITIONS AND SHALL HAVE VISITED AND INSPECTED THE JOB SITE AND BE FULLY INFORMED AS TO THE NATURE OF EQUIPMENT AND FACILITIES NEEDED FOR THE PROPER EXECUTION OF THE WORK. STARTING OF DEMOLITION AND REMOVAL OPERATIONS WILL BE CONSTRUED AS EVIDENCE THAT THE CONTRACTOR HAS COMPLIED WITH THESE REQUIREMENTS. ANY LATER CLAIMS FOR DIFFICULTIES ENCOUNTERED, WHICH COULD HAVE BEEN FORESEEN, WILL NOT BE RECOGNIZED.
3. VERIFY ALL EXISTING ELEVATIONS, CONDITIONS AND DIMENSIONS AT THE SITE, AGAINST THE DRAWINGS, AND INFORM THE CM OF ANY DISCREPANCIES PRIOR TO COMMENCING WORK AND SUBMISSION OF ANY SHOP DRAWINGS.
4. ALL WORK, WHETHER SHOWN OR IMPLIED, UNLESS SPECIFICALLY QUESTIONED, SHALL BE CONSIDERED FULLY UNDERSTOOD IN ALL RESPECTS BY THE CONTRACTOR. THE CONTRACTOR WILL BE HELD RESPONSIBLE FOR ANY MISINTERPRETATIONS AND/OR CONSEQUENCES THEREOF, FOR ALL WORK ON ALL DRAWINGS.
5. CONTRACTOR SHALL FOLLOW ACCEPTED TRADE PROCEDURES AND MANUFACTURER'S STANDARDS AND SHALL PRODUCE THE PROJECT IN A GOOD AND WORKMANLIKE MANNER. ALL MATERIALS ARE TO BE NEW, UNLESS OTHERWISE NOTED IN THE DRAWINGS AND CONTRACTOR SHALL NOT SUBSTITUTE ANY STRUCTURAL GRADE MATERIALS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT.
6. CONTRACTOR SHALL SCHEDULE ALL WORK TO CONFORM TO THE GENERAL CONSTRUCTION SCHEDULE AND SHALL COOPERATE AND NOT CONFLICT WITH THE DAY TO DAY OPERATIONS OF THE BUILDING AND OWNER.
7. THE CONTRACTOR AND ALL RESPECTIVE TRADES SHALL GIVE THEIR PERSONAL SUPERINTENDENCE TO THE WORK AND SHALL FURNISH ALL LABOR, MATERIALS, TRANSPORTATION, APPARATUS AND EQUIPMENT REQUIRED FOR A COMPLETE INSTALLATION. THE CONTRACTORS SHALL INSTALL ALL MATERIALS IN A MANNER SUBJECT TO APPROVAL OF THE OWNER AND THE ARCHITECT.
8. THE CONTRACTOR SHALL LEAVE THE PREMISES IN A NEAT, CLEAN AND SAFE CONDITION AT THE COMPLETION OF WORK EACH DAY.
9. THE CONTRACTOR SHALL CONFORM TO ALL APPLICABLE PROVISIONS OF THE NATIONAL AND STATE BUILDING CODES AND LOCAL REQUIREMENTS OF THE AIRPORT AND AHJ.
10. ALL CONDITIONS WHICH OCCUR AND WHICH ARE NOT IN CONFORMANCE WITH THESE SPECIFICATIONS AND DRAWINGS SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE ARCHITECT FOR PROMPT RESOLUTION. FAILURE TO DO SUCH SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
11. NO MATERIAL SUBSTITUTIONS SHALL BE MADE. THE ARCHITECT WILL CONSIDER MATERIAL CHANGE REQUESTS ON AN INDIVIDUAL BASIS. SUB-CONTRACTOR SHALL SUBMIT SAMPLES AND CUTS FOR WRITTEN APPROVAL BY THE ARCHITECT PRIOR TO THE START OF ANY WORK.
12. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATION OF WORK AND ESTABLISHING SCHEDULES FOR ALL TRADES. HE SHALL AFFORD OTHER SUB-CONTRACTORS REASONABLE OPPORTUNITY FOR THE INTRODUCTION AND STORAGE OF THEIR MATERIALS AND EQUIPMENT AND THE EXECUTION OF THEIR WORK.
13. ALL MANUFACTURED ARTICLES, MATERIALS AND EQUIPMENT SHALL BE SUPPLIED, INSTALLED, CONNECTED, ERECTED, USED, CLEANED AND CONDITIONED AS DIRECTED BY THE MANUFACTURER, UNLESS OTHERWISE SPECIFIED ON THE DRAWINGS.
14. EACH SUBTRADE WILL BE RESPONSIBLE FOR REVIEWING THE ENTIRE SET OF DRAWINGS AND NOTING HIS WORK AS APPLICABLE. WORK INDICATED OR INFERRED ON THE DRAWINGS WILL BE DEEMED AND INCLUDED IN SUB-CONTRACTOR'S COSTS.
15. THE CONTRACTOR SHALL SUBMIT, IN WRITING, ALL PROPOSALS FOR ADDITIONAL WORK TO THE ARCHITECT'S OFFICE FOR REVIEW AND APPROVAL. NO WORK IS TO PROCEED UNTIL A SIGNED PROPOSAL IS RETURNED TO THE GENERAL CONTRACTOR.
16. PERMITS: THE CONTRACTOR WILL SECURE REQUIRED BUILDING PERMITS PRIOR TO START OF WORK. INDIVIDUAL SUBCONTRACTORS TO SECURE NECESSARY PERMITS PRIOR TO START OF THEIR RESPECTIVE WORK.
17. UPON COMPLETION OF THE JOB, THE CONTRACTOR SHALL SUBMIT CERTIFICATES ON INSPECTION AND A CERTIFICATE OF SUBSTANTIAL COMPLETION (A.I.A. DOCUMENT G-704).
18. TEMPORARY PROTECTION: PARTICULAR ATTENTION SHALL BE GIVEN TO THE PROTECTION OF EXISTING STRUCTURE AND FINISHES SO AS TO PREVENT ANY DAMAGE OF EXISTING FINISHES NOT DESIGNATED FOR DEMOLITION. PROVIDE ALL NECESSARY TEMPORARY CONSTRUCTION AND DUST-PROOF PROTECTION. PROTECTIONS SHALL BE IN COMPLIANCE WITH BUILDING STANDARDS. TYPE AND LOCATION OF PROTECTION SHALL BE REVIEWED WITH OWNER'S CONSTRUCTION REPRESENTATIVE PRIOR TO COMMENCING WORK. SUB-CONTRACTOR SHALL FULLY BRACE AND OTHERWISE PROTECT ALL WORK IN PROGRESS UNTIL THE BUILDING IS COMPLETED.
19. PROVIDE FULL AND COMPLETE PROTECTION REQUIRED FOR ALL AREAS REMAINING OPERATIONAL DURING ALL PHASES OF THIS PROJECT. CONTRACTOR TO TAKE ALL NECESSARY MEASURES TO PREVENT DAMAGE TO ANY ADJACENT PROPERTY AND/OR PERSONS. THE CONTRACTOR SHALL REPAIR AND PATCH ANY AREAS THAT ARE ALTERED OR DAMAGED DURING PROCESS OF ALTERATION.
20. ANY EXISTING WORK DAMAGED BY THE CONTRACTOR OR SUBCONTRACTORS SHALL BE RETURNED TO ITS ORIGINAL CONDITION AT THE CONCLUSION OF THE PROJECT AT NO ADDITIONAL COST TO THE OWNER.
21. IT IS THE RESPONSIBILITY OF THE CONTRACTOR AND ITS SUB-CONTRACTORS TO KEEP THE BUILDING WEATHERTIGHT AND MAINTAIN ALL BARRICADES, SHORING, BRACING AND OTHER SAFETY MEASURES REQUIRED TO PROTECT THE BUILDING, WORKMEN AND THE PUBLIC.
22. CLEAN-UP: ALL MATERIALS DEMOLISHED, EXCEPT AS INDICATED ON THE DRAWINGS TO BE SALVAGED, SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE REMOVED AND DISPOSED OF OFF THE SITE WITH SUCH DILIGENCE AS TO CAUSE NO INTERFERENCE WITH SUBSEQUENT BUILDING OPERATIONS, USE OF BUILDING BY OCCUPANTS OR ANY UNSIGHTLY ACCUMULATION OF DEBRIS. CONSTRUCTION DEBRIS SHALL BE REMOVED
23. UPON COMPLETION OF ALL DEMOLITION AND REMOVAL WORK. REMOVE ALL TOOLS AND APPARATUS FROM THE PREMISES. REMOVE FROM THE AREA OF WORK ALL DEMOLISHED MATERIAL NOT DESIGNATED FOR RE-USE. REMOVE ALL TEMPORARY SHORING, BRACING, LINTELS PROTECTION, ETC., AS DIRECTED. LEAVE THE AREA OF WORK, BROOM-CLEAN, NEAT AND ORDERLY, TO THE SATISFACTION OF THE OWNER. STORAGE OF MATERIALS SHALL NOT INTERFERE WITH THE MEANS OF EGRESS OF THE EXISTING CORRIDOR SPACES.
24. THE CONTRACTOR SHALL OBTAIN AND PAY FOR COMPREHENSIVE LIABILITY INSURANCE COVERING THE ENTIRE WORK AND COMPENSATION INSURANCE, IN ACCORDANCE WITH APPLICABLE CURRENT LAWS, PRIOR TO THE COMMENCEMENT OF THE WORK. THE SUB-CONTRACTOR SHALL SUBMIT TO THE CONTRACTOR COPIES OF ALL REQUIRED, CERTIFICATES OF INSURANCE.

25. SHOP DRAWINGS: THE CONTRACTOR SHALL CHECK AND VERIFY ALL FIELD MEASUREMENTS AND SUBMIT, WITH PROMPTNESS, SHOP DRAWINGS, SAMPLES, MANUALS AND SCHEDULES REQUIRED FOR APPROVAL. THE ARCHITECT'S APPROVAL SHALL NOT RELIEVE THE CONTRACTOR FROM RESPONSIBILITY FOR DEVIATIONS AT THE TIME OF SUBMISSION, NOR SHALL IT RELIEVE HIM FROM RESPONSIBILITY FOR ERRORS IN SHOP DRAWINGS. THIS SHALL BE DONE PRIOR TO FABRICATION AND REVIEWED BY THE ARCHITECT.
26. LL SUBCONTRACTOR'S SHOP DRAWINGS SHALL BE SUBMITTED TO ARCHITECT FOR APPROVAL, THROUGH THE CM, PRIOR TO WORK BEING PERFORMED, UNLESS OTHERWISE NOTED. THE SHOP DRAWINGS SHALL BE REVIEWED BY THE CM AND VISIBLY INDICATED AS SUCH ON THE DRAWINGS, PRIOR TO SUBMISSION FOR THE ARCHITECT'S REVIEW.
27. HARDWARE AND DOOR SCHEDULES TO BE SUBMITTED TO AND APPROVED BY ARCHITECT PRIOR TO FABRICATION. WHERE CONTENTS OF MANUALS INCLUDE MANUFACTURERS' CATALOG PAGES, CLEARLY INDICATED THE PRECISE ITEMS INCLUDED IN THIS INSTALLATION AND DELETE, OR OTHERWISE CLEARLY INDICATE ALL MANUFACTURER'S DATA, WITH WHICH THIS INSTALLATION IS NOT CONCERNED UNLESS OTHERWISE SPECIFICALLY DIRECTED BY THE ARCHITECT, DELIVER SIX (6) COPIES OF THE MANUFACTURER'S MANUAL TO THE ARCHITECT AND ONE (1) COPY TO THE OWNER.
28. APPROVALS: THE ARCHITECT WILL REVIEW SUBMITTAL WITH REASONABLE PROMPTNESS, SO AS TO CAUSE NO DELAY, BUT ONLY FOR CONFORMANCE WITH THE DESIGN CONCEPT OF THE PROJECT AND WITH THE INFORMATION GIVEN IN THE CONTRACT DOCUMENTS.
29. NO PORTION OF THE WORK REQUIRING A SUBMISSION SHALL BE COMMENCED BY THE CONTRACTOR, UNTIL THE SUBMISSION HAS BEEN REVIEWED AND NOTED BY THE ARCHITECT IN WRITING. ALL SUCH PORTIONS OF THE WORK SHALL BE IN ACCORDANCE WITH APPROVED SUBMITTAL, AND IF COMMENCED, ARE AT THE CONTRACTOR'S OWN RISK.
30. ALL COLOR SELECTIONS SHALL BE MADE AND COORDINATED THROUGH THE OFFICE OF THE ARCHITECT, EXCEPT AS OTHERWISE DIRECTED BY THE OWNER. COLORS UNLESS THE PRECISE COLOR AND PATTERN IS SPECIFICALLY DESCRIBED IN THE CONTRACT DOCUMENTS, WHENEVER A CHOICE OF COLOR OR PATTERN IS AVAILABLE IN A SPECIFIED PRODUCT, SUBMIT ACCURATE COLOR CHARTS AND PATTERN CHARTS TO THE ARCHITECT FOR HIS REVIEW AND SELECTION.
31. THE GENERAL CONTRACTOR SHALL SUBMIT FINAL "AS BUILT" DRAWINGS IN PDF FORMAT AS PART OF THE CONTRACT.
32. THE CONTRACTOR SHALL SUBMIT THE SAMPLES IN SUFFICIENT TIME TO PERMIT CHECKING, RESUBMISSION, RECHECKING, APPROVAL FABRICATION AND DELIVERY. FAILURE TO DO SO WILL NOT JUSTIFY A DELAY IN THE TIME OF COMPLETION OF WORK.
33. DETAILS SHOWN IN ANY SECTION APPLY TO ALL SIMILAR SECTIONS UNLESS OTHERWISE NOTED.
34. WHEN CERTAIN ITEMS OF EQUIPMENT AND OTHER WORK ARE INDICATED AS "NIC" (NOT IN CONTRACT) OR TO BE FURNISHED AND INSTALLED UNDER OTHER CONTRACTS, ANY REQUIREMENTS FOR PREPARATION OF OPENINGS, PROVISION OF BACKING, ETC., FOR RECEIPT OF SUCH "NIC" WORK, SHALL BE PROVIDED TO THE GENERAL CONTRACTOR, WHO SHALL PROPERLY FORM AND OTHERWISE PREPARE HIS WORK IN A SATISFACTORY MANNER TO RECEIVE SUCH "NIC" WORK.
35. UPON WRITTEN REQUEST OF CONTRACTOR, THE OWNER WILL FURNISH TO THE GENERAL CONTRACTOR A SCHEDULE INDICATING DELIVERY DATES AND INSTALLATION REQUIREMENTS OF EQUIPMENT TO BE FURNISHED AND INSTALLED UNDER SEPARATE CONTRACTS.
36. IT WILL BE THE GENERAL CONTRACTOR'S RESPONSIBILITY TO SEE THAT THE BUILDING AREAS ARE MADE READY TO RECEIVE AND INSTALL THE OWNER'S EQUIPMENT, IN ACCORDANCE WITH THE DELIVERY SCHEDULE AND SPECIFIC REQUIREMENTS FURNISHED. FAILURE TO MEET THE SCHEDULE ON ITEMS OF THE OWNER-FURNISHED EQUIPMENT WILL BE CONSIDERED AS IMPORTANT TO THE COMPLETION SCHEDULE AS ANY OTHER PART OF THE WORK.
37. CONTRACTOR SHALL FULLY BRACE AND OTHERWISE PROTECT ALL WORK IN PROGRESS UNTIL THE BUILDING IS COMPLETED.
38. ALL FILL IS TO BE CLEAN AND COMPACTED PRIOR TO THE POURING OF ANY FLOOR SLAB OR FOOTING.
39. ALL OPENINGS IN PARTITIONS OR BLOCK WALLS INCLUDING, BUT NOT LIMITED TO, DUCTWORK, PENETRATIONS, DOOR OPENINGS, ETC. SHALL BE SUPPORTED BY STEEL LINTEL UNLESS OTHERWISE INDICATED. SUB-CONTRACTOR IS TO FURNISH AND INSTALL ALL ANGLES, STRUTS, BRACKETS, TOGGLES, EYE BOLTS, ETC. WHEREVER NECESSARY TO PROPERLY SUPPORT, BRACE OR REINFORCE ALL FINISHES, FRAMES, EQUIPMENT, ETC.
40. SEE PLANS FOR LOCATIONS OF ALL EXPANSION AND CONTROL JOINTS. PROVIDE EXPANSION JOINT COVERS (RECESSED) AT ALL FLOOR, WALL AND CEILING CONNECTIONS TO EXISTING CONSTRUCTION TO CONTROL JOINTS/FINISH CRACKING PROVIDE CONTINUOUS EXPANSION CONTROL AT STRUCTURE AND BUILDING FINISHES. SEE PLANS FOR WIDTH/TYPE.
41. ALL BLOCK AND ADJACENT RATED WALL CONSTRUCTION SHALL MEET THE FIRE RESISTIVE RATINGS AND OTHER REQUIREMENTS OF BUILDING CODE AND REGULATIONS, LOCAL LAWS, ORDINANCES, REGULATIONS AND AUTHORITIES HAVING JURISDICTION.
42. ALL CUTTING AND PATCHING OF OPENINGS SHALL BE POINTED UP, AND SURFACE REPAIRED FOR AN AIRTIGHT SEAL.
43. ALL EXISTING WALL FINISHES OR EQUIPMENT, ETC. WHICH ARE DISTURBED DURING CONSTRUCTION AND PROVE NOT TO BE NECESSARY AND NOT BE SPECIFICALLY INDICATED "TO REMAIN", SHALL BE REMOVED, PATCHED, REPAIRED OR COVERED, EITHER AS INDICATED ON THE PLANS OR TO CREATE A FLUSH, UNIFORM SURFACE HAVING THE INTEGRITY OF SUCH.
44. ALL WALLS AND/OR PARTITIONS, INCLUDING COLUMN AND RATED WALL CONSTRUCTION, SHALL EXTEND FROM FLOOR SLAB TO UNDERSIDE OF DECK CONSTRUCTION ABOVE, UNLESS OTHERWISE NOTED.
45. ALL OUTSIDE CORNERS AT MASONRY AND DRYWALL PARTITIONS SHALL HAVE METAL CORNER BEADS. TAPE AND SPACKLE SMOOTH WHERE REQUIRED.
46. ALIGNMENT OF NEW CONSTRUCTION TO EXISTING WALLS AND COLUMNS SHALL BE DONE IN A MANNER AS TO VISIBLY ELIMINATE THE POINT OF CONTACT OR JOINT OF NEW AND EXISTING MATERIALS. NEW CONSTRUCTION SHALL BE FLUSHED WITH EXISTING.
47. ALL WOOD PRODUCTS, FURRING STRIPS, BLOCKING ETC., SHALL BE FIRE RATED, IN ACCORDANCE WITH APPLICABLE STATE, CITY AND LOCAL BUILDING CODES.
48. PLASTIC LAMINATE COUNTERS, WALL HUNG SHELVES, CLOSET SHELVES AND COAT BARS, AND DIVIDERS IN CLOSETS BY GENERAL CONTRACTOR, UNLESS OTHERWISE NOTED.

49. PARTITIONS SHALL BE CONTINUOUS OVER ALL BUILT-IN EQUIPMENT, WHERE SHOWN ON PLANS AND DETAILS. FURNISH NECESSARY ANGLES, HANGERS, ETC. TO CARRY THESE PARTITIONS AND PROVIDE NECESSARY CLOSURE STRIPS AND TRIM AS REQUIRED.
50. PATCH ALL FLOOR AND WALL CRACKS AND SURFACE IRREGULARITIES AS REQUIRED. PRIOR TO FINISH INSTALLATION SHOWN. FLASH PATCH AREAS AS REQUIRED TO PROVIDE A SMOOTH FLUSH SURFACE FOR SAME.
51. ALL NEW PIPING, DUCTWORK, AND ELECTRICAL CONDUITS SHALL BE CONCEALED WITHIN NEW PARTITIONS; OR THE GENERAL CONTRACTOR IS TO PROVIDE FURRING, SOFFITS, CHASES, ETC., FOR ALL DUCTWORK, PIPING, CONDUIT, ETC., UNLESS INDICATED TO BE EXPOSED.
52. ALL INFILL PATCHING SHALL BE FURRED OUT AS REQUIRED AND FINISHED FLUSH WITH EXISTING.
53. THE GENERAL CONTRACTOR SHALL PATCH ALL CUTTING BY MECHANICAL AND ELECTRICAL TRADES AND ALL ADDITIONAL CUTTING BY OTHERS. COORDINATE THE WORK PRIOR TO THESE TRADES PROCEEDING. NO EXTRAS WILL BE ALLOWED DUE TO FAILURE TO COORDINATE SUCH, OR PROCEEDING WITH WORK THAT COULD HAVE BEEN AVOID WITH SUCH/PROPER PLANNING.
54. ALL PIPE SPACES AND DUCT SPACES SHALL BE ENCLOSED AND FIRE STOPPED BY A PARTITION OF THE REQUIRED RATING.
55. ANY STEEL AND COLUMN FIREPROOFING WHICH IS DAMAGED, LOOSE OR HAS CHIPPED-OFF, SHALL BE REPLACED PRIOR TO THE ENCLOSURE OF ANY COLUMNS TO MAINTAIN THE FIRE INTEGRITY OF SUCH.
56. FIRE ALARM TO BE PROVIDED WHERE SHOWN AND INSTALLED IN STRICT ACCORDANCE WITH MANUFACTURER'S ACTUAL INSTRUCTIONS AND NFPA 72.
57. EXIT SIGNS AND EMERGENCY LIGHTING ARE TO BE PROVIDED, MEETING ALL CODE REQUIREMENTS. ALL EXIT AREAS SHALL BE PROPERLY IDENTIFIED AND SUPPLIED WITH EMERGENCY EXIT LIGHTING TO MAINTAIN A MINIMUM OF ONE (1) FOOTCANDLE IN ACCORDANCE WITH IBC.
58. SUB-CONTRACTOR IS TO LOCATE AND COORDINATE EGRESS DOOR HARDWARE WITH ALARM SYSTEM AND MAKE ALL NECESSARY CONNECTIONS/REWIRE AS REQUIRED.
59. ALL "B" LABEL DOORS ARE TO BE EQUIPPED WITH AN AUTOMATIC SELF-CLOSER AND BE UL LABELED.
60. THE ELECTRICAL, OUTLETS AND PLUMBING SHOWN ON THE ARCHITECTURAL DRAWING ARE ONLY THOSE WHICH HELP TO CLARIFY THE SUGGESTED FUNCTIONAL PATTERNS OF THE ROOMS. IN ALL CASES THE SUB-CONTRACTOR SHALL REFER TO THE MECHANICAL AND ELECTRICAL DRAWINGS FOR THE COMPLETE LAYOUT OF EACH RESPECTIVE SERVICE. IN ALL CASES, OR IN THE EVENT OF A CONFLICT, THE ARCHITECTURAL DRAWINGS SHALL TAKE PRECEDENCE.
61. PROVIDE NEW ELECTRICAL WIRING/LIGHTING AS CLOSE AS POSSIBLE TO LAYOUTS SHOWN ON PLANS, UNLESS OTHERWISE DIRECTED BY CM. ELECTRICAL WIRING AND DEVICES TO MEET ALL CODE REQUIREMENTS. SUB-CONTRACTOR TO PROVIDE ALL HOOKUPS TO EXISTING, AS REQUIRED AFTER VERIFYING IF MAIN SERVICE IS SUFFICIENT TO CARRY INCREASED LOAD. REPLACE AS REQUIRED AND/OR UPGRADE IF NOT ADEQUATE.
62. COORDINATE NEW CONSTRUCTION WITH ALL REQUIRED MECHANICAL DUCTWORK AND PIPE PENETRATIONS. PROVIDE THROUGH WALL SLEEVES AS REQUIRED, TYPICAL. ALL LOCATIONS. PENETRATING SUB-CONTRACTOR TO PROVIDE SHEET METAL SLEEVE WITH THERMO FIBER AND FIRE RATED CAULK SYSTEM.
63. ALL HVAC, ELECTRICAL AND PLUMBING EQUIPMENT UNCOVERED DURING DEMOLITION THAT IS NOT SHOWN TIED INTO NEW CONSTRUCTION OR TO RELOCATED UNITS, IS TO BE "CAPPED OFF". COVERED AND LOCATION NOTED FOR FUTURE USE, OR REMOVED WHERE NO FUTURE USE IS INTENDED.
64. CEILING SUB-CONTRACTOR SHALL SUBMIT REFLECTED CEILING PLANS FOR ALL AREAS. PLANS SHALL INDICATE CEILING TILE GRID, CEILING DIFFUSERS, ELECTRICAL LIGHTING FIXTURES, STARTING POINTS, ETC. CAULK JOINTS AT VERTICAL INTERSECTIONS TO ALLOW FOR A CLEAN SHARP APPEARANCE.
65. ELECTRICAL SUBCONTRACTOR SHALL SUBMIT CATALOG CUTS OF ALL FIXTURES TO CM FOR APPROVAL OF COLOR AND STYLE.
66. PROVIDE ACCESS TO EXISTING ELECTRICAL AND TELEPHONE PANELS WHERE REQUIRED.
67. PHONE JACKS BY TELEPHONE SUB-CONTRACTOR. CM IS TO COORDINATE WITH ALL TRADES. INCOMING SERVICE TO BE BY THE REGIONAL TELEPHONE UTILITY COMPANY.
68. NEW WORK IS TO MEET OR EXCEED THE ENERGY CODE, NATIONAL ELECTRIC CODE NEC, NATIONAL STANDARD PLUMBING CODE (NSP), MECHANICAL CODES, OSHA (WHERE APPLICABLE), ALL UL REQUIREMENTS, AND ICC CODES. THE MOST RECENT PUBLICATION DATE OF ALL AFOREMENTIONED CODES SHALL APPLY.
69. HANDICAP NOTE: THE REQUIREMENTS OF THE "BARRIER-FREE SUBCODE" SHALL BE STRICTLY ADHERED TO.
70. GUARANTEES: ALL MATERIALS AND WORKMANSHIP SHALL BE GUARANTEED FOR A PERIOD OF ONE (1) YEAR FROM THE DATE OF FINAL ACCEPTANCE, UNLESS SPECIFIED OTHERWISE FOR A LONGER PERIOD OF TIME FOR SPECIFIC ITEMS. EACH SUB-CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS INCIDENTAL THERETO, INCLUDING DAMAGE TO OTHER WORK, FURNISHINGS OR EQUIPMENT, IF THE SUB-CONTRACTOR, AFTER NOTICE IN WRITING FROM THE CM AND ARCHITECT, FAILS TO PROCEED PROMPTLY TO COMPLY WITH THE TERMS OF THE GUARANTEE. THE CM MAY HAVE THE DEFECTS CORRECTED AND THE SUB-CONTRACTOR WILL BE RESPONSIBLE FOR ALL EXPENSES INCURRED.
71. ACCEPTANCE OF BID WILL BE CONSTRUED AS EVIDENCE THAT THE SUB-CONTRACTOR HAS COMPLIED WITH ALL REQUIREMENTS STATED ABOVE.
72. THESE DRAWINGS ARE FOR COORDINATION PURPOSES AND ARE TO BE USED IN CONJUNCTION WITH THE STRUCTURAL PLANS AND BUILDING SYSTEMS MANUFACTURERS' DETAILS/SHOP DRAWINGS. COORDINATE THESE SYSTEMS PRIOR TO COMMENCEMENT OF ANY WORK.
73. ARCHITECT'S RESPONSIBILITIES DURING CONSTRUCTION PHASE OF THE WORK SHALL BE TO ANSWER QUESTIONS REGARDING THE INTENT OF THE DRAWINGS, ALL REVISIONS, CONFLICTS AND SUBSTITUTIONS DURING CONSTRUCTION SHALL BE SUBMITTED TO THE CM.
74. AT INTERSECTIONS OF MASONRY AND GYPSUM BOARD FINISHES CONTRACTOR SHALL PROVIDE A CONTINUOUS 1/4" Z" REVEAL EXPANSION JOINT AND PAINT TO MATCH EXISTING.
75. GC IS TO PROVIDE ADEQUATE WALL BLOCKING BEHIND FINISH SURFACES FOR ALL KITCHEN EQUIPMENT (TYP.).

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: PERMIT  
ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G  
DRAWN BY: JP  
CHECKED BY: DC

Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE:  
**GENERAL NOTES**

SHEET NUMBER:  
**GN-100**

ABBREVIATIONS LEGEND

ABBREVIATIONS WHEN USED IN COMPOSITION MAY INCLUDE PERIODS FOR CLARIFICATION

Table with columns for Abbreviations and Full Names, covering categories like Anchor Bolt, Air Conditioning, Acoustic Panel, etc., up to YARD.

MATERIALS

Table listing various materials with their corresponding hatching patterns, such as COMPACTED SOIL, UNDISTURBED SOIL, COURSE POROUS FILL, SAND, CONCRETE, TERRAZZO, CUT STONE, BRICK MASONRY, etc.

SYMBOLS LEGEND


Diagrammatic section explaining various symbols used in the drawings, including COLUMN SYMBOLS & CENTER LINES, PARTITION TYPE, BUILDING SECTION CALLOUT, DETAIL/WALL SECTION CALLOUT, PARTIAL PLAN AND DETAIL CALLOUT, EXTERIOR ELEVATION CALLOUT, EGRESS PATH, MISC. TAG, and CONSTRUCTION LEGEND.

EN|V ARCHITECTURE + DESIGN logo and address information: 180 SYLVAN AVENUE, SUITE 3, ENGLEWOOD CLIFFS, NJ 07632.

CLIENT: SSP AMERICA, 20408 BASHAN DRIVE, SUITE 300, ASHBURN, VA 20147

PROJECT TEAM: ARCHITECT: ENVIRONETICS GROUP ARCHITECTS, 180 SYLVAN AVE, ENGLEWOOD CLIFFS, NJ 07632

MEP ENGINEER: GUTH DECONZO CONSULTING ENGINEERS, PC, 520 8TH AVENUE, SUITE 2201, NEW YORK, NY 10011




B-FB4 - WAHLBURGERS SARASOTA BRADENTON INTERNATIONAL, 6000 AIRPORT CIRCLE, SARASOTA, FL 34243, CLIENT: SSP AMERICA

Revision table with columns: REV, DATE, DESCRIPTION. Shows one revision: DESIGN DELIVERABLE: PERMIT ISSUE DATE: 08/16/2024.


PROJECT NUMBER: 24017G, DRAWN BY: JP, CHECKED BY: DC

Copyright (c) by Environetics, Inc. All Rights Reserved. SHEET TITLE: SYMBOLS AND ABBREVIATIONS


SHEET NUMBER: GN-101




403.5.1 CLEAR WIDTH FIGURE 403.5.1  
 304.3.1.1 NEW BUILDINGS AND FACILITIES TURNING SPACE  
 304.3.1.2 EXISTING BUILDINGS AND FACILITIES TURNING SPACE  
 304.3.2.1(A) T-SHAPED TURNING SPACE IN NEW BUILDINGS - OPTION 1  
 304.3.2.1(B) T-SHAPED TURNING SPACE IN NEW BUILDINGS - OPTION 2  
 304.3.2.1(C) T-SHAPED TURNING SPACE IN NEW BUILDINGS - OPTION 3




305.3.1 CLEAR FLOOR SPACE - NEW BUILDINGS AND FACILITIES  
 305.3.2 CLEAR FLOOR SPACE - EXISTING BUILDINGS AND FACILITIES  
 305.5(A) CLEAR FLOOR SPACE FORWARD APPROACH  
 305.5(B) CLEAR FLOOR SPACE PARALLEL APPROACH  
 305.7(A) MANEUVERING IN AN ALCOVE FORWARD APPROACH WHERE DEPTH IS GREATER THAN 24"  
 305.7.1 MANEUVERING IN AN ALCOVE PARALLEL APPROACH WHERE DEPTH EXCEEDS 15"



307.2 LIMITS OF PROTRUDING OBJECTS  
 308.2.1 UNOBSTRUCTED FORWARD REACH  
 308.2.2 OBSTRUCTED HIGH FORWARD REACH  
 308.3.1 UNOBSTRUCTED SIDE REACH  
 308.3.2(A) OBSTRUCTED SIDE REACH  
 308.3.2(B) OBSTRUCTED HIGH SIDE REACH



404.2.3.2(A) FRONT APPROACH-PULL SIDE  
 404.2.3.2(B) FRONT APPROACH-PUSH SIDE  
 404.2.3.2(C & D) HINGE APPROACH-PULL SIDE  
 404.2.3.2(E) HINGE APPROACH-PUSH SIDE  
 404.2.3.2(F) LATCH APPROACH-PULL SIDE  
 404.2.3.2(G) LATCH APPROACH-PUSH SIDE



404.2.2(A) HINGED DOOR CLEAR WIDTH OF DOORWAYS  
 404.2.5(C) TWO DOORS IN A SERIES  
 404.2.5(B) TWO DOORS IN A SERIES  
 404.2.5(A) TWO DOORS IN A SERIES

**GENERAL ADA NOTES:**

THE PROPOSED DESIGN COMPLIES WITH THE REQUIREMENTS OF THE AMERICAN WITH DISABILITIES ACT (ADA) AND PANYNJ'S SUPPLEMENTAL ACCESSIBILITY REQUIREMENTS  
 MIN. CLEARANCES OR GUIDELINES FROM THE ADA AND ANSI A117.1 REQUIREMENTS ARE REVISED PER PANYNJ'S SUPPLEMENTAL ACCESSIBILITY REQUIREMENTS  
 ALL ASPECTS OF THE MOST RECENT ADA/ADAAG DESIGN AND CONSTRUCTION CODES AND REGULATIONS HAS BEEN MET.

CLEAR FLOOR OR GROUND SPACE AT LEAST 30"X52" (PER PANYNJ'S SAR) THAT ALLOWS EITHER A FORWARD OR PARALLEL APPROACH BY A PERSON USING A WHEELCHAIR SHALL BE PROVIDED.  
 THE MINIMUM CLEAR FLOOR GROUND SPACE REQUIRED TO ACCOMMODATE A SINGLE STATIONARY WHEELCHAIR AND OCCUPANT IS 30" BY 52". THE MINIMUM CLEAR FLOOR OR GROUND SPACE FOR WHEELCHAIRS MAY BE POSITIONED FOR FORWARD OR PARALLEL APPROACH TO AN OBJECT. CLEAR FLOOR OR GROUND SPACE MAY BE PART OF THE KNEE SPACE REQUIRED UNDER SOME OBJECTS. (305.3 - 305.5)

ONE FULL UNOBSTRUCTED SIDE OF THE CLEAR FLOOR OR GROUND SPACE FOR A WHEELCHAIR SHALL ADJOIN ANOTHER WHEELCHAIR CLEAR FLOOR SPACE. IF A CLEAR FLOOR SPACE IS LOCATED IN AN ALCOVE OR OTHERWISE CONFINED ON ALL OR PART OF THREE SIDES, ADDITIONAL MANEUVERING CLEARANCES SHALL BE PROVIDED. (305.6 - 305.7)

FLOOR SURFACES OF WHEELCHAIR SPACES SHALL BE SLIP-RESISTANT. (302)  
 FAUCET CONTROLS AND OPERATING MECHANISMS SHALL BE OPERABLE WITH ONE HAND AND SHALL NOT REQUIRE TIGHT GRASPING, PINCHING OR TWISTING OF THE WRIST. THE FORCE REQUIRED TO ACTIVATE CONTROLS SHALL BE NO GREATER THAN 5 LBS. SELF-CLOSING VALVES ARE ALLOWED IF THE FAUCET REMAINS OPEN FOR AT LEAST 10 SECONDS. (309.4)

FEDERAL LAW: 2010 ADA STANDARDS FOR ACCESSIBLE DESIGN  
 REFERENCE ICC ANS A117.1 - 2017 ACCESSIBLE AND USABLE BUILDINGS AND FACILITIES FOR ADDITIONAL INFORMATION

**ENV**  
 ARCHITECTURE + DESIGN  
 180 SYLVAN AVENUE, SUITE 3  
 ENGLEWOOD CLIFFS, NJ 07632  
 TEL 201 | 894 | 1000  
 ENV-team.com

ENVIRONETICS GROUP ARCHITECTS, P.C.  
 CLIENT:  
**SSP AMERICA**  
 20408 BASHAN DRIVE  
 SUITE 300  
 ASHBURN, VA 20147

PROJECT TEAM:  
 ARCHITECT:  
 ENVIRONETICS GROUP ARCHITECTS  
 180 SYLVAN AVE.  
 ENGLEWOOD CLIFFS, NJ 07632  
 MEP ENGINEER  
 GUTH DECONZO CONSULTING  
 ENGINEERS, PC  
 520 8TH AVENUE, SUITE 2201  
 NEW YORK, NY 10011

DocuSigned by:  
  
 PETER ERDEMIR  
 REGISTERED ARCHITECT  
 NO. AR97605  
 STATE OF FLORIDA

**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: ISSUED FOR PERMIT  
 ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G  
 DRAWN BY: JP  
 CHECKED BY: DC  
 Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE:  
**ADA SHEET**

SHEET NUMBER:  
**GN-102**  
 REVIT 2023

# RESPONSIBILITY SCHEDULE

DISCLAIMER: THIS RESPONSIBILITY MATRIX IS NOT INTENDED TO DENOTE ALL RESPONSIBILITIES INVOLVED IN THE COMPLETION OF THIS PROJECT. THE GENERAL CONTRACTOR SHALL REVIEW ALL PROJECT DOCUMENTATION AND REVIEW EXISTING SITE CONDITIONS PRIOR TO BID SUBMISSION. ALL CLARIFICATION AND QUESTIONS RELATED TO SCOPE OF WORK AND THIS RESPONSIBILITY SCHEDULE SHALL BE DIRECTED TO ARCHITECT PRIOR TO SUBMISSION OF GENERAL CONTRACTOR'S BID. IT IS ASSUMED THAT ANY FINISH MATERIAL SPECIFIED INT HE DRAWING SET IS THE SCOPE OF THE GENERAL CONTRACTOR TO FURNISH AND INSTALL UNLESS NOTED OTHERWISE

| ITEM | SCOPE   | DOCUMENTATION      |            | PURCHASE/<br>SUPPLY  | INSTALLATION   | COMMENTS   |
|------|---|--------------------|------------|----------------------|----------------|--|
|      |   | PRIMARY<br>AOR/EOR | SECONDARY  |                      |                |  |
| 01   | ARCHITECTURE AND ENGINEERING  | AOR/EOR            | -          | SSP                  | CM             |  |
| 02   | 30% DESIGN SUBMISSION   | DESIGNER/AOR       |            |                      |                | CM TO PROVIDE PRICING  |
| 03   | 60% DRAWING SUBMISSION  | AOR                |            |                      |                | CM TO PROVIDE PRICING  |
| 04   | 90% CONSTRUCTION DOCUMENT SUBMISSION  | AOR                |            |                      |                | CM TO PROVIDE PRICING  |
| 05   | 100% CONSTRUCTION DOCUMENT SUBMISSION   | AOR                |            |                      |                | CM TO PROVIDE PRICING  |
| 06   | AS-BUILT DRAWINGS   | AOR                | CM         | -                    | -              | AOR TO PROVIDE ARCHITECTURAL AS-BUILTS<br>CM TO PROVIDE MEP+S AS-BUILTS FROM CONSTRUCTION<br>AOR TO COMPLETE PAPERWORK AND ISSUE TO AHJ<br>CM TO PAY FOR FEES, INSURANCE, AND PICK UP PERMIT IF NEEDED   |
| 07   | BUILDING PERMIT, FEES, & INSURANCE  | -                  | -          | -                    | AOR + CM       |  |
| 08   | FOOD LICENSE APPLICATION AND FEES   | AOR                |            | -                    | -              |  |
| 09   | LIQUOR LICENSE APPLICATION ANF FEES   | SSP D&C            | AOR        | -                    | -              | COORDINATE WITH SSP SUPPORT CENTER   |
| 10   | FURNITURE (BANQUETTE SEATING, BOOTH SEATING, COMMUNAL TABLES, CHAIRS, TABLES) | AOR                | -          | SSP                  | CM             | USE SSP APPROVED VENDORS<br>CM TO SUPPLY BANQUETTES/BOOTHs, IF MILLWORK  |
| 11   | MILLWORK  | AOR                | CM         | CM                   | CM             | CM TO PROVIDE AND REVIEW SHOP DRAWINGS   |
| 12   | RETAIL MERCHANDISING FIXTURES   | AOR                | -          | CM                   | CM             | SSP MARKETING TEAM TO PROVIDE SPECS  |
| 13   | ARTIFACTING   | AOR                | -          | SSP                  | CM             |  |
| 14   | GRAPHICS (FRAMED ARTWORK, MURALS, WALL ART)                                   | AOR                | SSP        | SSP/CM               | CM             | DIGITAL FILES (WHEN APPLICABLE) PROVIDED BY SSP AND/OR EXTERNAL BRAND (IF APPLICABLE)<br>UNLESS NOTED OTHERWISE, GC TO FABRICATE AND INSTALL   |
| 15   | BRANDING (MEMORABILIA, SHELVING DISPLAYS)                                     | AOR                | SSP        | SSP                  | CM             | SSP TO PRVIDE. CM TO INSTALL   |
| 16   | SIGNAGE   | AOR                | SSP        | CM                   | CM             | GRAPHICS, FONT, IMAGES, AND LOGOS PROVIDED BY SSP AND/OR EXTERNAL BRAND (IF APPLICABLE)<br>CM RESPONSIBLE FOR POWER FEED, CONNECTIVITY, TIME CLOCK AND SHOP DRAWINGS<br>CM TO PROVIDE SHOP DRAWINGS AND REVIEW IN CONJUNCTION WITH ARCH AND MEP SCOPE OF WORK. CM SHALL ALSO BE RESPONSIBLE FOR RECEIVING SSP-PROCURED ITEMS, INCLUDING UNCRATING AND HELPING WITH DELIVERY/LOGISTICS<br>CM SHALL USE SSP APPROVED VENDORS<br>FINAL CONNECTIONS BY CM<br>KE VENDOR TO PROVIDE SHOP DRAWINGS TO AOR AND EOR FOR REVIEW AND APPROVAL |
| 17   | FOOD SERVICE EQUIPMENT (NEW)  | AOR/KEC            | -          | SSP                  | CM             | ALL EXISTING EQUIPMENT/INFRASTRUCTURE TO BE INVESTIGATED AND THOROUGHLY TESTED EARLY IN THE DESIGN PHASE. CM TO COMPLETE. ANY ITEMS NEEDING REPAIR/REPLACEMENT SHOULD BE COORDINATED WITH KEC AND DESIGN TEAM  |
| 18   | FOOD SERVICE EQUIPMENT (EXISTING)   | AOR/KEC            | -          |                      |                |  |
| 19   | DISHWASHING CHEMICALS   | SSP OPS            | -          | SSP OPS              | SSP OPS        |  |
| 20   | MAU/EXHAUST FANS  | AOR/KEC            | -          | CM                   | CM             | CM RESPONSIBLE FOR STRUCTURAL SUPPORT REQUIRED (DESIGNED BY AOR)   |
| 21   | EXHAUST HOOD & ANSUL SYSTEM   | AOR/KEC            | -          | SSP / KE VENDOR / CM | CM             | CM RESPONSIBLE FOR STRUCTURAL SUPPORT REQUIRED (DESIGNED BY AOR)<br>CM RESPONSIBLE FOR MAU / PCU (IF NEEDED) / BLACK IRON DUCTWORK / BMS / CONTROLS<br>KE VENDOR RESPONSIBLE FOR ANSUL (ALL) / EXHAUST FAN / HOOD  |
| 22   | BEER LINES AND CONDIUT  | AOR/KEC            | -          | CM                   | CM             |  |
| 23   | SODA SYSTEM   | AOR/KEC            | -          | SSP                  | CM             | CM TO INSTALL BEVERAGE CONDIUT AND MEP CONNECTIONS ONLY. NO HOOK UPS OR TUBES  |
| 24   | SOAP DISPENSER / PAPER TOWEL DISPENSER  | AOR/KEC            | -          | SSP/CM               | KE VENDOR / CM |  |
| 25   | IT KITCHEN REMOTE PRINTERS  | AOR/KEC            | SSP        | SSP                  | SSP/CM         | CM TO INSTALL CABLE AND CONDUIT ONLY<br>CM TO INSTALL CABLE, CONDUIT, AND MOUNTS<br>SSP TO PROVIDE MOUNTS (WALL AND POLE ONLY)   |
| 26   | IT KITCHEN DISPLAY SYSTEMS (KDS)  | AOR/KEC            | SSP        | SSP                  | SSP/CM         | CM TO INSTALL CABLE AND CONDUIT ONLY   |
| 27   | IT POS TERMINALS  | AOR/KEC            | SSP        | SSP                  | SSP/CM         | CM TO INSTALL CABLE AND CONDUIT ONLY   |
| 28   | IT SELF ORDER KIOSKS (SOK)  | AOR/KEC            | SSP        | SSP                  | SSP/CM         | CM TO INSTALL CABLE AND CONDUIT ONLY   |
| 29   | IT DATA SERVERS   | AOR                | SSP        | SSP                  | SSP/CM         | CM TO INSTALL CABLE, CONDUIT, AND RACK ONLY  |
| 30   | IT RACK   | AOR                | SSP        | CM                   | SSP/CM         | SSP TO PROVIDE SPECS. CM TO INSTALL CABLE, CONDUIT, AND RACK<br>CM IS RESPONSIBLE FOR CABLING/CONDUIT TO AIRPORT COMM ROOM   |
| 31   | IT TABLE LOCATOR  | -                  | -          | SSP                  | CM             |  |
| 32   | MENU BOARDS (DIGITAL)   | AOR                | -          | CM                   | SSP/CM         | CONNECTION AND SETUP BY SSP<br>SSP VENDOR TO SUPPLY AND INSTALL BOARDS AND MOUNTS (UNLESS NOTED OTHERWISE)<br>CM TO INSTALL CABLE AND CONDIUT  |
| 33   | MENU BOARDS (STATIC)  | AOR                | -          | CM                   | SSP/CM         | GRAPHICS TO BE SUPPLIED BY SSP. INSTALLED BY CM  |
| 34   | MUSIC SYSTEM  | AOR                | -          | SSP                  | SSP/CM         | SSP VENDOR TO SUPPLY AND INSTALL SPEAKERS (UNLESS NOTED OTHERWISE)<br>CM TO INSTALL CABLE AND CONDIUT  |
| 35   | MUSIC SERVICE PROVIDER  | -                  | -          | SSP                  | SSP            |  |
| 36   | TELEVISIONS   | AOR                | -          | CM                   | SSP/CM         | SSP VENDOR TO SUPPLY AND INSTALL TVS AND MOUNTS (UNLESS NOTED OTHERWISE)<br>CM TO INSTALL CABLE AND CONDIUT<br>CM TO COORDINATE INSTALL WITH ANY 3RD PARTY PROVIDER (DIRECT TV) AND MAKE SURE CBLE/CONDUIT IS INSTALLED FROM DISH (ROOF) TO RECEIVER (IT RACK) TO TV   |
| 37   | SATELLITE TV SERVICE  | -                  | -          | SSP                  | CM             |  |
| 38   | TELEPHONE/DATA EQUIPMENT  | AOR                | -          | SSP                  | SSP            |  |
| 39   | TELEPHONE/DATA WIRING/CONDIUT   | AOR                | -          | CM                   | CM             |  |
| 40   | LP ALARMS   | AOR                | SSP        | SSP                  | SSP            |  |
| 41   | LP SECURITY CAMERAS   | AOR                | SSP        | SSP                  | SSP            | CM TO INSTALL CABLE AND CONDUIT ONLY<br>CAMERAS INSTALLED BY SSP VENDOR. CM TO COORDINATE  |
| 42   | LP SMART SAFES (GLORY SAFE)   | AOR                | SSP        | SSP                  | SSP            | CM TO PROVIDE POWER/DATA AND CONDIUT   |
| 43   | EMPLOYEE LOCKERS / COAT HOOKS   | AOR                | -          | CM                   | CM             |  |
| 44   | SMALLWARES  | -                  | -          | SSP                  | SSP            |  |
| 45   | FIRE EXTINGUISHERS AND CABINETS   | AOR                | -          | CM                   | CM             |  |
| 46   | LIGHTING  | AOR                | -          | CM                   | CM             | CM TO PROVIDE LAMPING<br>CM TO PROVIDE SHOP DRAWINGS AND REVIEW IN CONJUNCTION WITH ARCH, MECHANICAL, AND PLUMBING SCOPE OF WORK   |
| 47   | SPRINKLER SYSTEM DESIGN AND INSTALLATION                                      | AOR                | -          | CM                   | CM             | NEW WORK TO BE BY LICENSED SPRINKLER CONTRACTOR  |
| 48   | FIRE ALARM TIE-INS  | -                  | -          | CM                   | CM             |  |
| 49   | TEMP BARRICADE WALL   | AOR                | -          | CM                   | CM             | BARRICADE PLANS/DIMENSIONS/DETAILS TO BE PROVIDED BY CM. SHOWN IN DRAWINGS FOR GENERAL INTENT ONLY   |
| 50   | TEMP BARRICADE GRAPHICS   | AOR                | SSP        | CM                   | CM             | GRAPHICS PROVIDED BY AIRPORT/BRAND/SSP. INSTALLED BY CM  |
| 51   | TEMP UTILITIES  | -                  | -          | CM                   | CM             |  |
|      | FINAL CLEANING OF SPACE   | -                  | -          | CM                   | CM             | CM TO BROOM CLEAN AFTER CONSTRUCTION. FINAL BY TENANT  |
|      | TIMING  |                    | 30% - 100% | BID                  | CONSTRUCTION   |  |

**GENERAL NOTES**


- THIS MATRIX SHOULD BE REVIEWED AND CONFIRMED BY TEAM ON A PROJECT BY PROJECT BASIS
- CM SHALL SUPPLY AND INSTALL ALL ITEMS THAT ARE REASONABLE CONSIDERED PART OF THE PROJECT SCOPE THAT MAY NOT BE HIGHLIGHTED ON THE DRAWINGS
- ALL DESIGN COORDINATION AS IT RELATES TO SITE CONDITIONS PRIOR TO AND DURING CONSTRUCTION SHALL BE THE RESPONSIBILITY OF THE CM. DRAWINGS SHOULD BE FULLY VETTED AND ALL ROUTING/LOCATIONS OF MEP WORK SHALL BE KNOWN BY CM PRIOR TO PRE-CONSTRUCTION MEETING
- CM SHALL BE RESPONSIBLE FOR ANY UTILITY CHANGES THAT OCCUR DURING THE DESIGN AND CONSTRUCTION PHASE
- ENSURE BACKFLOW PREVENTERS ARE INSTALLED ON ALL APPLICABLE PLUMBING FIXTURES
- CM TO JET ALL NEW AND EXISTING DRAIN LINES
- CM SHALL BE RESPONSIBLE FOR ALL PROJECT AND VEHICLE ESCORTING ON AIRPORT GROUNDS. THIS SHALL INCLUDE SSP VENDORS
- CM SHALL BE RESPONSIBLE FOR ANY COST ASSOCIATED WITH MISSED ITEMS THAT SHOULD HAVE BEEN REASONABLE CAUGHT DURING THE DESIGN PROCESS
- CM TO PROVIDE 3RD PARTY TESTING, INSPECTIONS, AND INSTALLATION ON MEP, STRUCTURAL, AND ARCHITECTURAL SYSTEMS ASSOCIATED WITH THE PROJECT AS MANDATED BY AIRPORT TEAMS, MANUALS, OR INSPECTORS
- THE ENTIRE DESIGN AND CONSTRUCTION TEAM(AOR, EOR, GC/CM) ARE RESPONSIBLE RO REVIEW ALL AIRPORT DOCUMENTS AND GUIDELINES FOR LATEST FORMS, INSPECTION PROCEDURES, DAIL OPERATIONS, SAFETY, DESIGN CRITERIA, ETC.
- IT IS THE RESPONSIBILITY OF THE DESIGN TEAM TO VISIT THE SITE (INCLUDING SPACES DIRECTLY ABOVE AND BELOW) TO ENSURE PROPER KNOWLEDGE OF FIELD CONDITIONS. CHANGES TO COST OR SCHEDULE DUE TO KNOWN CONDITIONS WILL BE UNACCEPTABLE
- CM SHALL WORK WITH SSP ON RESPONSIBILITIES FOR ANY ITEMS THAT MIGHT NOT COMPLY WITH AIRPORT REGULATIONS OR ORDINANCES MANDATING UNION LABOR, ETC.



180 SYLVAN AVENUE, SUITE 3  
ENGLEWOOD CLIFFS, NJ 07632  
TEL 201 | 894 | 1000  
EN|V-team.com  
ENVIRONETICS GROUP ARCHITECTS, P.C.  
COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED

CLIENT:  
**SSP AMERICA**  
20408 BASHAN DRIVE  
SUITE 300  
ASHBURN, VA 20147

PROJECT TEAM:  
ARCHITECT:  
ENVIRONETICS GROUP ARCHITECTS  
180 SYLVAN AVE.  
ENGLEWOOD CLIFFS, NJ 07632  
MEP ENGINEER  
GUTH DECONZO CONSULTING  
ENGINEERS, PC  
520 8TH AVENUE, SUITE 2201  
NEW YORK, NY 10011



**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA



| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |

DESIGN DELIVERABLE: ISSUED FOR PERMIT  
ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G  
DRAWN BY: JP  
CHECKED BY: DC

Copyright (c) by Environetcs, Inc. All Rights Reserved.  
SHEET TITLE:  
**RESPONSIBILITY MATRIX**

SHEET NUMBER:  
**GN-103**



**EGRESS LEGEND:**

— OCCUPANCY TYPE

|        |           |
|--------|-----------|
| A      | ROOM NAME |
| ROOM # | AREA      |

XX OCCUPANT LOAD BY EXIT

XX EXIT CAPACITY

▬ .5 HOUR RATED WALL ASSEMBLY

▬ 1 HOUR RATED WALL ASSEMBLY

▬ 2 HOUR RATED WALL ASSEMBLY

🔥 FIRE EXTINGUISHER CABINET  
 SEE DETAIL FOR ADDITIONAL INFO.

- FIRE ALARM AND SPRINKLER NOTES**
- ALL NEW BUILDING MODIFICATIONS SHALL BE FULLY SPRINKLERED.
  - ALL FIRE EXTINGUISHING SYSTEMS SHALL CONFORM TO THE STANDARDS AND REQUIREMENTS OF APPLICABLE CODES AND AHJ.
  - THE EXISTING AUTOMATIC FIRE SPRINKLER AND FIRE ALARM SYSTEM SHALL BE ANALYZED AND COMPLY WITH ANY NEW REQUIREMENTS DUE TO BUILDING MODIFICATIONS. THE FIRE SPRINKLER AND ALARM CONTRACTORS SHALL BE PREPARED AND SUBMIT FOR REVIEW AND APPROVAL BY THE ARCHITECT.
- NOTE: REFERENCE CEILING PLAN FOR EXIT SIGN LOCATIONS

**ROOM OCCUPANCY LOAD SCHEDULE**

| ROOM NUMBER  | ROOM NAME    | FUNCTION OF SPACE   | AREA (SQ. FT.) | OCCUPANT LOAD FACTOR | OCCUPANT LOAD (PERSONS) |
|--------------|--------------|---|----------------|----------------------|-------------------------|
| 101          | SITTING AREA | ASSEMBLY WITHOUT FIXED SEATS - CONCENTRATED (TABLES AND CHAIRS) | 402 SF         | 15                   | 27                      |
| 102          | BAR BOH      | KITCHENS, COMMERCIAL  | 307 SF         | 200                  | 2                       |
| 103          | BOH          | KITCHENS, COMMERCIAL  | 151 SF         | 200                  | 1                       |
| 104          | KITCHEN      | KITCHENS, COMMERCIAL  | 129 SF         | 200                  | 1                       |
| <b>TOTAL</b> |              |   |                |                      | <b>31</b>               |

**EGRESS WIDTH PER OCCUPANT SERVED**

| OCCUPANCY | OTHER EGRESS COMPONENTS (INCHES PER OCCUPANT) |                    | STAIRWAY (INCHES PER OCCUPANT) |                    |
|-----------|---|--------------------|--------------------------------|--------------------|
|           | WITH SPRINKLERS                               | WITHOUT SPRINKLERS | WITH SPRINKLERS                | WITHOUT SPRINKLERS |
| A-2       | 0.15" PER OCCUPANT                            | 0.2" PER OCCUPANT  | 0.2" PER OCCUPANT              | 0.3" PER OCCUPANT  |

**Egress Distance Calculation**

| ROOM NUMBER | EGRESS DISTANCE |
|-------------|-----------------|
| 101         | 181'            |
| 102         | 230'            |
| 103         | 210'            |
| 104         | 221'            |

**EXIT ACCESS TRAVEL DISTANCE**

| WITHOUT SPRINKLERS | WITH SPRINKLERS |
|--------------------|-----------------|
| 200' - 0"          | 250' - 0"       |

- CHAPTER 8 INTERIOR FINISHES AND DECORATIVE MATERIALS**  
 GROUP A-2 (SPRINKLERED)
- INTERIOR EXIT STAIRWAYS AND RAMPS AND EXIT PASSAGEWAYS: B
  - CORRIDORS AND ENCLOSURE FOR EXIT ACCESS STAIRWAYS AND RAMPS: B
  - ROOMS AND ENCLOSED SPACES: C

**EGRESS PLAN**  
 3/32" = 1'-0"

**2** RATED FIRE EXTINGUISHER CABINET  
 3" = 1'-0"

FIRE EXTINGUISHER CABINETS SHALL BE MODEL FS 2409-6R SEMI-RECESSED WITH ROLLED EDGE, RECESSED HANDLE WITH SOLID DOOR IN STAINLESS STEEL FINISH. PROVIDE MULTI-PURPOSE DRY CHEMICAL EXTINGUISHER (SEE SPECS FOR ADDITIONAL INFORMATION)

**3** OCCUPANCY SIGNAGE  
 1 1/2" = 1'-0"

RAISED 1" OR 1 1/4" HIGH CHARACTERS (WHITE ON GREY BACKGROUND)

1/2" TYP.

1/2" TYP.

3/4" - 3/4" - 3/4" - 3/4"

1/2" THICK ACRYLIC SIGN

COUNTERSUNK HOLE FOR FASTENER (TYP.)

OCCUPANCY BY MORE THAN XX PERSONS IS DANGEROUS & UNLAWFUL

**4** EGRESS DOOR CLEARANCE  
 1/2" = 1'-0"

**SINGLE DOOR**

DOOR FRAME: 2 1/2"

PARTITION: 33" (MIN.)


DOOR AS SCHEDULED: 30.00"

**DOUBLE DOOR**


DOOR FRAME: 2 1/2"

PARTITION: 66" (MIN.)

DOOR AS SCHEDULED: 30.00"



**DEMOLITION LEGEND**



**DEMOLITION GENERAL NOTES:**


- A: THE FOLLOWING ARE EXISTING TO REMAIN:**
- ONE CIRCUIT FOR TEMPORARY LIGHTING AND ONE CIRCUIT FOR TEMPORARY POWER.
- B: DEMOLITION SHALL INCLUDE BUT NOT BE LIMITED TO THE FOLLOWING:**
- REMOVE PLUMBING FIXTURES AND ASSOCIATED PIPING AS INDICATED. CAP SANITARY MAIN, VENT AND CW AND HW PIPING.
  - CUT AND CAP ALL REMAINING FLOOR CONDUITS, PLUMBING/ELEC. LINES, ETC. BELOW SLAB. PATCH SLAB SMOOTH AS REQD TYP. BRING WIRING BACK TO PANEL.
  - ALL WALL MOUNTED EQUIP., LIGHTING, ELECTRICAL DEVICES, WIRING, PIPING, ETC SHALL BE REMOVED UNLESS NOTED OTHERWISE. CUT AND CAP ALL LINES 2" FROM FINISH SURFACE.
  - ALL ABANDONED AND ACTIVE WIRING, REMOVALS SHALL EXTEND TO NEAREST ACTIVE REMAINING SOURCE PANEL. THE FEEDER CONDUIT TO THE PANEL SHALL BE IDENTIFIED AND MARKED ACCORDINGLY.
  - DISCONNECT POWER TO OUTLETS, EQUIP. & LIGHTING PRIOR TO DEMOLITION.
  - REMOVE ALL WALL MOUNTED EQUIPMENT. PREP ROOM FOR NEW FINISHES. COORDINATE WITH OWNER FOR ITEMS TO BE SALVAGED. PATCH AND REPAIR ALL SURFACES IN PREPARATION FOR NEW FINISHES.
  - ALL DOORS, FRAMES, SADDLES AND HARDWARE AS INDICATED ON PLANS.
  - THE ENTIRE CEILING SYSTEM, FINISH CEILING MATERIAL AND SUPPORTS, SOFFITS, LIGHTING, DIFFUSERS AND RETURN AIR GRILLES.
  - ALL FINISH FLOOR MATERIAL AND ADHESIVE TO BE REMOVED TO EXISTING MASONRY.
  - EXISTING SMOKE/HEAT DETECTOR WIRING SHALL BE PROTECTED, ROLLED AND HUNG FROM DECK FOR RELOCATION. EXISTING FIRE ALARM SYSTEM IS TO BE MAINTAINED IN OPERATIONAL CONDITION UNTIL NEW SYSTEM IS INSTALLED AND OPERATIONAL.
  - EXISTING THERMOSTATS SHALL BE DISCONNECTED AND CONTROL WIRING ROLLED AND HUNG FROM DECK W/ THERMOSTAT. REMOVE ALL OLD UNUSED SYSTEMS AND WIRING.
  - REMOVE ALL FURNITURE, CASEWORK AND EQUIPMENT. COORDINATE WITH OWNER FOR ITEMS TO BE SALVAGED. PATCH AND REPAIR ALL SURFACES IN PREPARATION FOR NEW FINISHES.
  - EXISTING STEAM AND OTHER UTILITY RISERS THROUGH THE SPACE ARE TAGGED AND IDENTIFIED AS TO SOURCE AND DESTINATION.
  - ACCESS HOLES ARE TO BE MADE IN ANY RISER CHASE ENCLOSURE FOR ENGINEERING REFERENCE.
  - ALL EXISTING, OR REMAINING FLOOR BURRS, RIDGES, BUMPS, ETC. SHALL BE GROUND SMOOTH. ALL VOIDS, DEPRESSIONS, POCKETS, VOIDS RESULTING FROM DEMOLITION SHALL BE FILLED SOLID WITH CONC.
  - EXISTING FLUORESCENT LIGHTING TO BE REMOVED. VERIFY IF EXISTING BALLAST CONTAIN PCB AND DISPOSE PROPERLY.
  - EXISTING INTERCOM AND BELL SYSTEM SHALL BE PROTECTED AND TEMPORARILY SUPPORTED DURING CONSTRUCTION. G.C. SHALL MAINTAIN ALL BUILDING SYSTEMS DURING CONSTRUCTION. REMOVE AND DISCONNECT EXISTING BUILDING SYSTEM ONCE NEW SYSTEM IS IN PLACE AND OPERATIONAL. (TYP. FOR FIRE, DATA, INTERCOM, BELL, PHONE ETC.)
  - A KEYNOTE SHALL BE CONSIDERED GENERAL IN NATURE TO PERFORM A PROCEDURE, OPERATION, ETC. THEREFORE CONTRACTOR SHALL PERFORM ALL WORK OR MULTIPLE WORK IN AREA.
  - THE TERM "TYP." FOLLOWING A NOTE, TAG OR DETAIL FLAG INDICATES THAT ALL LIKE, SIMILAR OR INDICATED ITEMS SHALL BE PROVIDED WITH SPECIFIED DETAIL, NOTE OR SPECIFICATION.
- C: EXECUTION**
- CONDUCT WALL DEMOLITION OPERATIONS IN A MANNER TO PREVENT DAMAGE TO POSSIBLY HIDDEN STRUCTURAL ELEMENTS (COLUMNS, BEAMS, ETC.)
  - IF UNCOVERED, ANY PREVIOUSLY HIDDEN STRUCTURAL ELEMENTS ARE TO REMAIN INTACT. - CONTACT ARCHITECT IMMEDIATELY.
  - TEMPORARY LIGHTING IS TO BE PROVIDED BY CONTRACTOR. LIGHT LEVELS TO BE ADEQUATE FOR THE SAFE PERFORMANCE OF DEMOLITION OPERATIONS.
  - NOTIFY THE ARCHITECT IF EXISTING PLUMBING LINES, DUCTWORK, AND ELECTRICAL LINES SCHEDULED FOR REMOVAL ARE REQD FOR SERVICING OTHER AREAS OF THE BUILDING. DO NOT REMOVE ABOVE MENTIONED EQUIP. WITHOUT INSTRUCTIONS FROM THE ARCHITECT.

**DEMOLITION KEYED NOTES**

|      |  |
|------|--|
| D-1  | EXISTING PARTITION TO BE REMOVED IN ITS ENTIRETY, INCLUDING BUT NOT LIMITED TO WALL FINISHES, SUBSTRATE, STUDS, UTILITIES, ETC. CAP OR REMOVE UTILITIES AS REQUIRED. REFER TO MEP DRAWINGS FOR ADDITIONAL INFORMATION. PATCH AND REPAIR ADJACENT WALL/ FLOORS/ CEILINGS AS REQUIRED FOR NEW FINISHES.  |
| D-2  | EXISTING COUNTER TOPS TO BE REMOVED IN THEIR ENTIRETY. GC TO PATCH AND REPAIR ANY DAMAGED AREAS FROM CONSTRUCTION.   |
| D-3  | EXISTING CONCOURSE FINISHES, FLOOR TO CEILING, TO BE PROTECTED DURING ALL CONSTRUCTION PHASES. GC TO PATCH AND REPAIR ANY DAMAGED AREAS FROM CONSTRUCTION.   |
| D-4  | EXISTING FLOORING TO BE REMOVED IN ITS ENTIRETY. GC TO SHOTBLAST DECK SMOOTH AND FLASH PATCH FLOOR AS REQUIRED TO ACHIEVE A LEVEL SURFACE. PATCH AND REPAIR FLOOR AND ANY DAMAGED AREAS TO RECEIVE NEW FINISH PER MANUFACTURERS SPECIFICATIONS.  |
| D-5  | EXISTING WINDOW FRAMING AND GLAZING TO BE PROTECTED FOR DURATION OF CONSTRUCTION. GC TO CONFIRM WINDOWS ARE SEALED TIGHT OF ANY LEAKS. GC TO REPAIR ANY DAMAGED GASKETS AT WINDOWS.  |
| D-6  | LEASE LINE. HATCHED AREA IS OUTSIDE OF THE SCOPE OF WORK. GC TO CONFIRM FINAL DIMENSIONS WITH AIRPORT/ LANDLORD.   |
| D-7  | EXISTING CEILING TO BE REMOVED IN ITS ENTIRETY, INCLUDING BUT NOT LIMITED TO SUPPORTS, ANCHORS, ACT GRIDS, LIGHTING, GYP, SOFFITS, DIFFUSERS, AND HVAC GRILLES. REMOVE ALL BOXES, ASSOCIATED WIRING AND CIRCUITING TO BE TAKEN BACK TO NEAREST ACTIVE SOURCE PANEL AND CAP AS REQUIRED. ALL EXISTING DUCTS, PIPES, CONDUITS, AND CABLES IN THE CEILING TO BE REMOVED AS REQUIRED FOR NEW LAYOUT. REFERENCE RCP, MEP DRAWINGS FOR ADDITIONAL INFORMATION. |
| D-8  | EXISTING SECURITY GRILL WITH ASSOCIATED HARDWARE TO BE REMOVED IN ITS ENTIRETY.  |
| D-9  | EXISTING DOOR, DOOR FRAME, AND HARDWARE TO BE REMOVED IN ITS ENTIRETY.   |
| D-10 | REMOVE ALL EXISTING MILLWORK, FURNITURE, AND EQUIPMENT IN ITS ENTIRETY. DISCONNECT EQUIPMENT FROM PLUMBING/ ELECTRICAL. REFER TO MEP FOR MEP DEMO WORK.  |
| D-11 | EXISTING WALLS TO REMAIN. GC TO REMOVE EXISTING WALL BASE AND WALL FINISHES AS REQUIRED IN ITS ENTIRETY. GC TO PATCH AND PREPARE TO RECEIVE NEW FINISHES.  |
| D-12 | GC SHALL CONFIRM THAT EXISTING TENANT SEPARATION WALL(S) ARE MIN 1-HOUR RATED. IF LESS THAN 1 HOUR CONTRACTORS SHALL MAKE EXISTING WALLS 1-HOUR RATED.   |
| D-19 | UPON COMPLETION OF CONSTRUCTION & REMOVAL OF BARRICADES, CONTRACTOR SHALL CLEAN, PATCH, AND REPAIR ALL AREAS (FLOOR, WALLS, CEILING) FROM BARRICADE REMOVAL.   |
| D-21 | EXISTING FIRE EXTINGUISHER CABINET AND FIRE EXTINGUISHER TO BE REMOVED IN ITS ENTIRETY.  |
| D-22 | EXISTING DRINK RAIL COUNTER, FRAME, AND ANCHORS TO BE REMOVED IN ITS ENTIRETY. PATCH SUBSTRATE AS REQUIRED TO MATCH EXISTING ADJACENT.   |
| D-23 | EXISTING TVS AND SIGNAGE TO BE COORDINATED WITH TENANT IF TO BE RETURNED TO TENANT OR BE DISCARDED.  |
| D-24 | EXISTING ADJACENT TENANT BLADE SIGNAGE TO REMAIN VISIBLE THROUGHOUT DEMOLITION AND CONSTRUCTION. GC TO PATCH AND REPAIR ANY DAMAGE TO SIGNAGE.   |

**BARRICADE KEYED NOTES**

|     |  |
|-----|--|
| B-1 | G.C. TO PROVIDE MODULAR BARRICADE. COORDINATE ALL REQUIREMENTS WITH AIRPORT AND OPERATOR PRIOR TO ORDERING. UPON COMPLETION OF CONSTRUCTION AND REMOVABLE OF BARRICADE, G.C. TO CLEAN/PATCH/REPAIR EXISTING FINISHES THAT BARRICADE ASSEMBLY WAS ATTACHED TO. SEE ELEVATIONS AND BARRICADE DETAIL FOR ADDITIONAL INFORMATION.  |
| B-2 | PROVIDE (2) 36"x84" H.M. DOUBLE DOORS AS INDICATED ON PLAN. DOORS TO BE PAINTED W/ (2) COATS OF AIRPORT APPROVED METAL PAINT. HARDWARE TO BE LOCKED FROM CONCOURSE SIDE. DOORS TO HAVE RIM PANIC EXIT DEVICES. STOREROOM LOCKSETS ONLY WITH A 1 1/2" VERTICAL METAL FLANGE/ ASTRAGAL USED IN COMBINATION W/ SLIDE-BOLT PADLOCK SYSTEM. BARRICADE LOCKS MUST BE COMPATIBLE W/ "BEST" 7-BIN AUTOMATICALLY WHEN CLOSED. |




| REV                 | DATE              | DESCRIPTION |
|---------------------|-------------------|-------------|
| DESIGN DELIVERABLE: | ISSUED FOR PERMIT |             |
| ISSUE DATE:         | 08/16/2024        |             |

|                 |        |
|-----------------|--------|
| PROJECT NUMBER: | 24017G |
| DRAWN BY:       | JP     |
| CHECKED BY:     | DC     |

Copyright (c) by Environetics, Inc. All Rights Reserved.  
 SHEET TITLE:  
**BARRICADE AND DEMOLITION PLAN**

SHEET NUMBER:  
**AD-101**





**DEMOLITION LEGEND**

- EXISTING DOOR TO REMAIN
- EXISTING DOOR, FRAME, & HARDWARE TO BE REMOVED
- ITEM TO BE REMOVED ENTIRELY
- WALL OR WALL PORTION TO BE REMOVED ENTIRELY
- WALL, WALL PORTION, OR ITEM TO REMAIN
- DEMOLITION KEY NOTE
- AREA NOT IN SCOPE
- NEW FLOOR PENETRATION, G.C. TO COORDINATE FINAL CORE SIZES WITH SPECIFIED OPTIONS. SEE MEP DRAWINGS FOR ADDITIONAL DETAILS
- DEMOLISHED CEILING
- DEMOLISHED ACT. CEILING
- LEASE LINE

**DEMOLITION GENERAL NOTES:**

- A: THE FOLLOWING ARE EXISTING TO REMAIN:**
- ONE CIRCUIT FOR TEMPORARY LIGHTING AND ONE CIRCUIT FOR TEMPORARY POWER.
- B: DEMOLITION SHALL INCLUDE BUT NOT BE LIMITED TO THE FOLLOWING:**
- REMOVE PLUMBING FIXTURES AND ASSOCIATED PIPING AS INDICATED. CAP SANITARY MAIN, VENT AND CW AND HW PIPING.
  - CUT AND CAP ALL REMAINING FLOOR CONDUITS, PLUMBING/ELEC. LINES, ETC. BELOW SLAB. PATCH SLAB SMOOTH AS REQD TYP. BRING WIRING BACK TO PANEL.
  - ALL WALL MOUNTED EQUIP., LIGHTING, ELECTRICAL DEVICES, WIRING, PIPING, ETC SHALL BE REMOVED UNLESS NOTED OTHERWISE. CUT AND CAP ALL LINES 2" FROM FINISH SURFACE.
  - ALL ABANDONED AND ACTIVE WIRING, REMOVALS SHALL EXTEND TO NEAREST ACTIVE REMAINING SOURCE PANEL. THE FEEDER CONDUIT TO THE PANEL SHALL BE IDENTIFIED AND MARKED ACCORDINGLY.
  - DISCONNECT POWER TO OUTLETS, EQUIP. & LIGHTING PRIOR TO DEMOLITION.
  - REMOVE ALL WALL MOUNTED EQUIPMENT. PREP ROOM FOR NEW FINISHES. COORDINATE WITH OWNER FOR ITEMS TO BE SALVAGED. PATCH AND REPAIR ALL SURFACES IN PREPARATION FOR NEW FINISHES.
  - ALL DOORS, FRAMES, SADDLES AND HARDWARE AS INDICATED ON PLANS.
  - THE ENTIRE CEILING SYSTEM; FINISH CEILING MATERIAL AND SUPPORTS, SOFFITS, LIGHTING, DIFFUSERS AND RETURN AIR GRILLES.
  - ALL FINISH FLOOR MATERIAL AND ADHESIVE TO BE REMOVED TO EXISTING MASONRY
  - EXISTING SMOKE/HEAT DETECTOR WIRING SHALL BE PROTECTED, ROLLED AND HUNG FROM DECK FOR RELOCATION. EXISTING FIRE ALARM SYSTEM IS TO BE MAINTAINED IN OPERATIONAL CONDITION UNTIL NEW SYSTEM IS INSTALLED AND OPERATIONAL.
  - EXISTING THERMOSTATS SHALL BE DISCONNECTED AND CONTROL WIRING ROLLED AND HUNG FROM DECK WITH THERMOSTAT. REMOVE ALL OLD UNUSED SYSTEMS AND WIRING.
  - REMOVE ALL FURNITURE, CASEWORK AND EQUIPMENT. COORDINATE WITH OWNER FOR ITEMS TO BE SALVAGED. PATCH AND REPAIR ALL SURFACES IN PREPARATION FOR NEW FINISHES.
  - EXISTING STEAM AND OTHER UTILITY RISERS THROUGH THE SPACE ARE TAGGED AND IDENTIFIED AS TO SOURCE AND DESTINATION.
  - ACCESS HOLES ARE TO BE MADE IN ANY RISER CHASE ENCLOSURE FOR ENGINEERING REFERENCE.
  - ALL EXISTING, OR REMAINING FLOOR BURRS, RIDGES, BUMPS, ETC. SHALL BE GROUND SMOOTH. ALL VOIDS, DEPRESSIONS, POCKETS, VOIDS RESULTING FROM DEMOLITION SHALL BE FILLED SOLID WITH CONC.
  - EXISTING FLUORESCENT LIGHTING TO BE REMOVED. VERIFY IF EXISTING BALLAST CONTAIN PCB AND DISPOSE PROPERLY.
  - EXISTING INTERCOM AND BELL SYSTEM SHALL BE PROTECTED AND TEMPORARILY SUPPORTED DURING CONSTRUCTION. G.C. SHALL MAINTAIN ALL BUILDING SYSTEMS DURING CONSTRUCTION. REMOVE AND DISCONNECT EXISTING BUILDING SYSTEM ONCE NEW SYSTEM IS IN PLACE AND OPERATIONAL. (TYP. FOR FIRE, DATA, INTERCOM, BELL, PHONE ETC.)
  - A KEYNOTE SHALL BE CONSIDERED GENERAL IN NATURE TO PERFORM A PROCEDURE, OPERATION, ETC. THEREFORE CONTRACTOR SHALL PERFORM ALL WORK OR MULTIPLE WORK IN AREA.
  - THE TERM "TYP." FOLLOWING A NOTE, TAG OR DETAIL FLAG INDICATES THAT ALL LIKE, SIMILAR OR INDICATED ITEMS SHALL BE PROVIDED WITH SPECIFIED DETAIL, NOTE OR SPECIFICATION.
- C: EXECUTION**
- CONDUCT WALL DEMOLITION OPERATIONS IN A MANNER TO PREVENT DAMAGE TO POSSIBLY HIDDEN STRUCTURAL ELEMENTS (COLUMNS, BEAMS, ETC.)
  - IF UNCOVERED, ANY PREVIOUSLY HIDDEN STRUCTURAL ELEMENTS ARE TO REMAIN INTACT. - CONTACT ARCHITECT IMMEDIATELY.
  - TEMPORARY LIGHTING IS TO BE PROVIDED BY CONTRACTOR. LIGHT LEVELS TO BE ADEQUATE FOR THE SAFE PERFORMANCE OF DEMOLITION OPERATIONS.
  - NOTIFY THE ARCHITECT IF EXISTING PLUMBING LINES, DUCTWORK, AND ELECTRICAL LINES SCHEDULED FOR REMOVAL ARE REQD FOR SERVICING OTHER AREAS OF THE BUILDING. DO NOT REMOVE ABOVE MENTIONED EQUIP. WITHOUT INSTRUCTIONS FROM THE ARCHITECT.


**DEMOLITION KEYED NOTES**

|      |   |
|------|---|
| D-17 | EXISTING FLOOR DRAIN/ FLOOR SINK TO BE REMOVED IN ITS ENTIRETY. INFILL SLAB AS REQUIRED. SEE INFILL DETAILS FOR ADDITIONAL INFORMATION. SEE PLUMBING DRAWINGS FOR ADDITIONAL INFORMATION.   |
| D-18 | G.C. TO CORE DRILL SLAB FOR NEW FLOOR SINK/ FLOOR DRAIN / FLOOR FUNNEL DRAIN OR MOP SINK. COORDINATE EXACT LOCATION WITH KITCHEN EQUIPMENT DRAWINGS, PLUMBING, AND STRUCTURE BELOW. CONTRACTOR TO SCAN SLAB AND DRILL PILOT HOLES PRIOR TO CUTTING FINAL CORES TO ENSURE NO STRUCTURAL DAMAGE WILL OCCUR. PROVIDE FIRE STOPPING AS REQUIRED. COORDINATE FINAL CORE SIZES WITH SPECIFIED ITEMS. SEE PLUMBING DRAWINGS FOR ADDITIONAL INFORMATION. SEE FLOOR PENETRATION DETAILS. |
| D-20 | GC SHALL COORDINATE WITH MEP DRAWINGS FOR ALL OTHER CORING REQUIRED. ALL CORES IF OVER 4" SHALL HAVE GC HIRE STRUCTURAL ENGINEER FOR ANY REQUIRED ADDITIONAL REINFORCING. ENGINEERED DRAWINGS TO BE PROVIDED FOR REVIEW AND RECORD.   |

**ENV**  
ARCHITECTURE + DESIGN  
180 SYLVAN AVENUE, SUITE 3  
ENGLEWOOD CLIFFS, NJ 07632  
TEL 201 | 894 | 1000  
ENV-team.com  
ENVIRONETICS GROUP ARCHITECTS, P.C.  
COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED

CLIENT:  
**SSP AMERICA**  
20408 BASHAN DRIVE  
SUITE 300  
ASHBURN, VA 20147

PROJECT TEAM:  
ARCHITECT:  
ENVIRONETICS GROUP ARCHITECTS  
180 SYLVAN AVE.  
ENGLEWOOD CLIFFS, NJ 07632  
MEP ENGINEER  
GUTH DECONZO CONSULTING  
ENGINEERS, PC  
520 8TH AVENUE, SUITE 2201  
NEW YORK, NY 10001



**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: ISSUED FOR PERMIT  
ISSUE DATE: 08/16/2024


PROJECT NUMBER: 24017G  
DRAWN BY: JP  
CHECKED BY: DC

Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE:  
**CORING PLAN**

SHEET NUMBER:  
**AD-102**

8/16/2024 5:19:57 PM



**DEMOLITION LEGEND**

- EXISTING DOOR TO REMAIN
- EXISTING DOOR, FRAME, & HARDWARE TO BE REMOVED
- ITEM TO BE REMOVED ENTIRELY
- WALL OR WALL PORTION TO BE REMOVED ENTIRELY
- WALL, WALL PORTION, OR ITEM TO REMAIN
- DEMOLITION KEY NOTE
- AREA NOT IN SCOPE
- NEW FLOOR PENETRATION, G.C. TO COORDINATE FINAL CORE SIZES WITH SPECIFIED OPTIONS. SEE MEP DRAWINGS FOR ADDITIONAL DETAILS
- DEMOLISHED CEILING
- DEMOLISHED ACT. CEILING
- LEASE LINE

**DEMOLITION GENERAL NOTES:**

- A: THE FOLLOWING ARE EXISTING TO REMAIN:**
- ONE CIRCUIT FOR TEMPORARY LIGHTING AND ONE CIRCUIT FOR TEMPORARY POWER.
- B: DEMOLITION SHALL INCLUDE BUT NOT BE LIMITED TO THE FOLLOWING:**
- REMOVE PLUMBING FIXTURES AND ASSOCIATED PIPING AS INDICATED. CAP SANITARY MAIN, VENT AND CW AND HW PIPING.
  - CUT AND CAP ALL REMAINING FLOOR CONDUITS, PLUMBING/ELEC. LINES, ETC. BELOW SLAB. PATCH SLAB SMOOTH AS REQD TYP. BRING WIRING BACK TO PANEL.
  - ALL WALL MOUNTED EQUIP., LIGHTING, ELECTRICAL DEVICES, WIRING, PIPING, ETC SHALL BE REMOVED UNLESS NOTED OTHERWISE. CUT AND CAP ALL LINES 2" FROM FINISH SURFACE.
  - ALL ABANDONED AND ACTIVE WIRING, REMOVALS SHALL EXTEND TO NEAREST ACTIVE REMAINING SOURCE PANEL. THE FEEDER CONDUIT TO THE PANEL SHALL BE IDENTIFIED AND MARKED ACCORDINGLY.
  - DISCONNECT POWER TO OUTLETS, EQUIP. & LIGHTING PRIOR TO DEMOLITION.
  - REMOVE ALL WALL MOUNTED EQUIPMENT. PREP ROOM FOR NEW FINISHES. COORDINATE WITH OWNER FOR ITEMS TO BE SALVAGED. PATCH AND REPAIR ALL SURFACES IN PREPARATION FOR NEW FINISHES.
  - ALL DOORS, FRAMES, SADDLES AND HARDWARE AS INDICATED ON PLANS.
  - THE ENTIRE CEILING SYSTEM; FINISH CEILING MATERIAL AND SUPPORTS, SOFFITS, LIGHTING, DIFFUSERS AND RETURN AIR GRILLES.
  - ALL FINISH FLOOR MATERIAL AND ADHESIVE TO BE REMOVED TO EXISTING MASONRY
  - EXISTING SMOKE/HEAT DETECTOR WIRING SHALL BE PROTECTED, ROLLED AND HUNG FROM DECK FOR RELOCATION. EXISTING FIRE ALARM SYSTEM IS TO BE MAINTAINED IN OPERATIONAL CONDITION UNTIL NEW SYSTEM IS INSTALLED AND OPERATIONAL.
  - EXISTING THERMOSTATS SHALL BE DISCONNECTED AND CONTROL WIRING ROLLED AND HUNG FROM DECK WITH THERMOSTAT. REMOVE ALL OLD UNUSED SYSTEMS AND WIRING.
  - REMOVE ALL FURNITURE, CASEWORK AND EQUIPMENT. COORDINATE WITH OWNER FOR ITEMS TO BE SALVAGED. PATCH AND REPAIR ALL SURFACES IN PREPARATION FOR NEW FINISHES.
  - EXISTING STEAM AND OTHER UTILITY RISERS THROUGH THE SPACE ARE TAGGED AND IDENTIFIED AS TO SOURCE AND DESTINATION.
  - ACCESS HOLES ARE TO BE MADE IN ANY RISER CHASE ENCLOSURE FOR ENGINEERING REFERENCE.
  - ALL EXISTING, OR REMAINING FLOOR BURRS, RIDGES, BUMPS, ETC. SHALL BE GROUND SMOOTH. ALL VOIDS, DEPRESSIONS, POCKETS, VOIDS RESULTING FROM DEMOLITION SHALL BE FILLED SOLID WITH CONC.
  - EXISTING FLUORESCENT LIGHTING TO BE REMOVED. VERIFY IF EXISTING BALLAST CONTAIN PCB AND DISPOSE PROPERLY.
  - EXISTING INTERCOM AND BELL SYSTEM SHALL BE PROTECTED AND TEMPORARILY SUPPORTED DURING CONSTRUCTION. G.C. SHALL MAINTAIN ALL BUILDING SYSTEMS DURING CONSTRUCTION. REMOVE AND DISCONNECT EXISTING BUILDING SYSTEM ONCE NEW SYSTEM IS IN PLACE AND OPERATIONAL. (TYP. FOR FIRE, DATA, INTERCOM, BELL, PHONE ETC.)
  - A KEYNOTE SHALL BE CONSIDERED GENERAL IN NATURE TO PERFORM A PROCEDURE, OPERATION, ETC. THEREFORE CONTRACTOR SHALL PERFORM ALL WORK OR MULTIPLE WORK IN AREA.
  - THE TERM "TYP." FOLLOWING A NOTE, TAG OR DETAIL FLAG INDICATES THAT ALL LIKE, SIMILAR OR INDICATED ITEMS SHALL BE PROVIDED WITH SPECIFIED DETAIL, NOTE OR SPECIFICATION.
- C: EXECUTION**
- CONDUCT WALL DEMOLITION OPERATIONS IN A MANNER TO PREVENT DAMAGE TO POSSIBLY HIDDEN STRUCTURAL ELEMENTS (COLUMNS, BEAMS, ETC.)
  - IF UNCOVERED, ANY PREVIOUSLY HIDDEN STRUCTURAL ELEMENTS ARE TO REMAIN INTACT. - CONTACT ARCHITECT IMMEDIATELY.
  - TEMPORARY LIGHTING IS TO BE PROVIDED BY CONTRACTOR. LIGHT LEVELS TO BE ADEQUATE FOR THE SAFE PERFORMANCE OF DEMOLITION OPERATIONS.
  - NOTIFY THE ARCHITECT IF EXISTING PLUMBING LINES, DUCTWORK, AND ELECTRICAL LINES SCHEDULED FOR REMOVAL ARE REQD FOR SERVICING OTHER AREAS OF THE BUILDING. DO NOT REMOVE ABOVE MENTIONED EQUIP. WITHOUT INSTRUCTIONS FROM THE ARCHITECT.


**DEMOLITION KEYED NOTES**

|      |   |
|------|---|
| D-6  | LEASE LINE. HATCHED AREA IS OUTSIDE OF THE SCOPE OF WORK. GC TO CONFIRM FINAL DIMENSIONS WITH AIRPORT/ LANDLORD.  |
| D-7  | EXISTING CEILING TO BE REMOVED IN ITS ENTIRETY, INCLUDING BUT NOT LIMITED TO SUPPORTS, ANCHORS, ACT GRIDS, LIGHTING, GYP, SOFFITS, DIFFUSERS, AND HVAC GRILLS. REMOVE ALL BOXES, ASSOCIATED WIRING AND CIRCUITING TO BE TAKEN BACK TO NEAREST ACTIVE SOURCE PANEL AND CAP AS REQUIRED. ALL EXISTING DUCTS, PIPES, CONDUITS, AND CABLES IN THE CEILING TO BE REMOVED AS REQUIRED FOR NEW LAYOUT. REFERENCE RCP, MEP DRAWINGS FOR ADDITIONAL INFORMATION. |
| D-13 | EXISTING CONCOURSE CEILING AND LIGHTING TO REMAIN. GC TO PATCH AND REPAIR AS NECESSARY INCLUDING BUT NOT LIMITED TO WALL, CEILING, AND ANY EXISTING FINISHES DAMAGED DURING DEMOLITION/ CONSTRUCTION PHASE.   |
| D-14 | EXISTING GYP CEILING TO REMAIN. PROTECT THROUGH DEMOLITION AND CONSTRUCTION PHASE. PREP GYP TO RECEIVE NEW FINISH. EXISTING LIGHTING TO BE REMOVED IN ITS ENTIRETY. PATCH CEILING FROM FIXTURES THAT WERE REMOVED AND CUT NEW OPENINGS FOR NEW FIXTURES AS REQUIRED. COORDINATE LIGHTING AND EQUIPMENT LOCATIONS WITH RCP AND MEP DRAWINGS.   |
| D-15 | EXISTING LINEAR DIFFUSER TO BE MODIFIED AS REQUIRED. REFERENCE MECHANICAL DRAWINGS FOR ADDITIONAL INFORMATION.  |
| D-16 | EXISTING AIRPORT LINEAR DIFFUSER TO REMAIN. PROTECT THROUGH DEMOLITION AND CONSTRUCTION PHASE. REFERENCE MECHANICAL DRAWINGS FOR ADDITIONAL INFORMATION.  |
| D-25 | EXISTING SPRINKLERS TO REMAIN AND BE MODIFIED AS REQUIRED. REFER TO SPRINKLER DRAWINGS FOR SPRINKLER SCOPE AND ADDITIONAL INFORMATION.  |

**ENV**  
ARCHITECTURE + DESIGN  
180 SYLVAN AVENUE, SUITE 3  
ENGLEWOOD CLIFFS, NJ 07632  
TEL 201 | 894 | 1000  
ENV-team.com  
ENVIRONETICS GROUP ARCHITECTS, P.C.  
COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED

CLIENT:  
**SSP AMERICA**  
20408 BASHAN DRIVE  
SUITE 300  
ASHBURN, VA 20147

PROJECT TEAM:  
ARCHITECT:  
ENVIRONETICS GROUP ARCHITECTS  
180 SYLVAN AVE.  
ENGLEWOOD CLIFFS, NJ 07632  
MEP ENGINEER  
GUTH DECONZO CONSULTING  
ENGINEERS, PC  
520 8TH AVENUE, SUITE 2201  
NEW YORK, NY 10001



**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA



| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: ISSUED FOR PERMIT  
ISSUE DATE: 08/16/2024


PROJECT NUMBER: 24017G  
DRAWN BY: MK, JP  
CHECKED BY: DC  
Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE:  
**DEMOLITION REFLECTED CEILING PLAN**

SHEET NUMBER:  
**AD-110**




**NOTE:**  
CONTRACTOR SHALL BE RESPONSIBLE FOR PLACING TEMPORARY WAY-FINDING AND EMERGENCY EGRESS SIGNAGE AS REQUIRED SHOULD ANY PART OF THE CONSTRUCTION BARRIER OR OTHER CONSTRUCTION ACTIVITY OBSTRUCTS EXISTING SIGNAGE.  
BARRIER DESIGN WILL ADHERE TO ALL REQUIREMENTS OF LANDLORD, AHJ, AND APPLICABLE CODES  
COORDINATE WITH LANDLORD AND OPERATOR REPRESENTATIVES PRIOR TO ORDERING, NO MECHANICAL FASTENING TO FLOOR. ALL BRACING WILL NEED TO BE PROVIDED AS NECESSARY. VISQUEEN TO BE PROVIDED AS NECESSARY FOR CONTAINMENT OF ANY DUST/DEBRIS  
BARRICADE TO BE CONSTRUCTED OF NON-COMBUSTIBLE MATERIALS PER APPLICABLE CODE



FLOOR PENETRATION MUST COMPLY WITH UL ASSEMBLY SYSTEM NO. C-AJ-1276. SEE FIRE STOPPING DETAILS FOR ADDITIONAL INFORMATION.


BARRICADE SECTION 1  
1/2" = 1'-0"

TYPICAL FLOOR PENETRATION 1  
3" = 1'-0"



**NOTE:**  
CORE DRILL OR SAW-CUT AS NECESSARY TO REMOVE SLAB. SLAB REINFORCEMENT CAN ONLY BE CUT WITH STRUCTURAL ENGINEER'S APPROVAL.  
LOCATE FLOOR SINK UNDER EQUIPMENT/ETC. TO AVOID TRIPPING HAZARD.

FLOOR PENETRATION MUST COMPLY WITH UL SYSTEM NO. F-A-1135. SEE FIRE STOPPING DETAILS FOR ADDITIONAL INFORMATION.



FLOOR PENETRATION MUST COMPLY WITH UL SYSTEM NO. F-A-1135. SEE FIRE STOPPING DETAILS FOR ADDITIONAL INFORMATION.

TYPICAL FLOOR PENETRATION 2  
1 1/2" = 1'-0"

TYPICAL FLOOR PENETRATION 3  
1 1/2" = 1'-0"

**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA

| REV                 | DATE              | DESCRIPTION |
|---------------------|-------------------|-------------|
| DESIGN DELIVERABLE: | ISSUED FOR PERMIT |             |
| ISSUE DATE:         | 08/16/2024        |             |

|  |        |
|--|--------|
| PROJECT NUMBER:  | 24017G |
| DRAWN BY:  | JP     |
| CHECKED BY:  | DJB    |
| Copyright (c) by Environetics, Inc. All Rights Reserved. |        |


SHEET TITLE:  
**CORING AND BARRICADE DETAILS**

SHEET NUMBER:  
**AD-401**

**PARTITION GENERAL NOTES**

- WHERE WALL IS DESIGNATED WITH A RATED TAG, USE TYPE X FIRE RATED GYPSUM BOARD
- WHERE WALL IS DESIGNATED WITH A WET LOCATION TAG, USE 5/8" MOLD AND WATER RESISTANT GYP. BD. (USE 5/8" GLASS MESH MORTAR UNITS WHERE CERAMIC TILE FINISH TO BE INSTALLED)
- WHERE WALL IS DESIGNATED WITH A RATED AND WET LOCATION TAG, USE 5/8" MOLD, WATER AND FIRE RATED HEAVY DUTY ABUSE RESISTANT TYPE X GYP. BD.
- PARTITION TYPES APPLY TO INTERIOR PARTITIONS ONLY.
- DEEP LEG DEFLECTION TRACK HEAD CONDITIONS ARE REQUIRED AT ALL PARTITIONS TO DECK OR STRUCTURE.
- GENERAL CONTRACTOR IS RESPONSIBLE FOR CONSTRUCTING THE COMPLETE ASSEMBLY OF ALL FIRE RATED PARTITIONS IN FULL ACCORDANCE WITH UL LISTING.
- ALL STUDS TO BE 20 GAUGE, UNLESS NOTED OTHERWISE. REFERENCE SPECIFICATIONS FOR FRAMED OPENING CONDITIONS.
- ALL SHAFTWALL STUDS TO BE 20 GAUGE, UNLESS NOTED OTHERWISE.
- REFERENCE CHART BELOW FOR MINIMUM REQUIRED PARTITION BRACING REQUIREMENTS.
- REFERENCE STRUCTURAL DRAWINGS AND SPECIFICATIONS FOR ANY ADDITIONAL REQUIREMENTS FOR CONCRETE MASONRY UNIT PARTITIONS.

**PARTITION LEGEND**



**FOR RATED WALL ASSEMBLY USE:**



- UL TYPE SCX GYPSUM AT FIRE RATED LOCATIONS, AS NOTED ON EGRESS PLANS
- CONTINUOUS ACOUSTICAL / FIRESTOPPING SEALANT AT BASE AND HEAD, TYP.

**FOR WET LOCATIONS USE:**

- AT ALL WET LOCATIONS AND AREAS TO RECEIVE TILE FINISH, USE DUROCK CEMENT BOARD IN PLACE OF GYPSUM BOARD


**NOTE: WALLS NOTED AS RATED IN A WET LOCATION, THE FIRE RATED ASSEMBLY TAKES PRECEDENCE**

**NOTE:** REFERENCE EGRESS PLANS AND BUILDING SECTIONS FOR THE CODE MINIMUM FIRE-RESISTANCE RATING REQUIRED AT EACH HORIZONTAL AND VERTICAL ASSEMBLY. DUE TO THE NATURE OF FLOOR AND PARTITION CONSTRUCTION, THE ASSEMBLIES DESIGNATED MAY EXCEED THE MINIMUM CODE-REQUIRED VALUES. HOWEVER WHEN EXPLORING ALTERNATES, THE MINIMUM FIRE RESISTANCE RATING REQUIREMENTS SHOWN ON THE EGRESS PLANS AND BUILDING SECTIONS MUST BE MAINTAINED.




| PARTITION TYPE C |                   |  |           |             | PARTITION TYPE A |        |                   |  |           |             |            |
|------------------|-------------------|--|-----------|-------------|------------------|--------|-------------------|--|-----------|-------------|------------|
| DESIG.           | TYPE              | DESCRIPTION  | UL NUMBER | FIRE RATING | STC RATING       | DESIG. | TYPE              | DESCRIPTION  | UL NUMBER | FIRE RATING | STC RATING |
| C3               | PARTITION TYPE C3 | STANDARD NON-LOAD BEARING STUD PARTITION WITH 1 LAYER OF 5/8" GYP. BD. ON 3-5/8" METAL STUD. | U419      | 1HR         | 48               | A3     | PARTITION TYPE A3 | STANDARD NON-LOAD BEARING STUD PARTITION WITH 1 LAYER OF 5/8" GYP. BD. ON 3-5/8" METAL STUD. |           |             |            |

FOR RATED WALL ASSEMBLY, REF. UL DES. U419



| PARTITION TYPE I |                   |   |           |             |            |
|------------------|-------------------|---|-----------|-------------|------------|
| DESIG.           | TYPE              | DESCRIPTION   | UL NUMBER | FIRE RATING | STC RATING |
| I3               | PARTITION TYPE I3 | STANDARD NON-LOAD BEARING STUD DIE WALL PARTITION WITH 2 LAYER OF 5/8" GYP. BD. ON 3 5/8" METAL STUD. |           |             |            |



| PARTITION TYPE H |                   |   |           |             |            |
|------------------|-------------------|---|-----------|-------------|------------|
| DESIG.           | TYPE              | DESCRIPTION   | UL NUMBER | FIRE RATING | STC RATING |
| H3               | PARTITION TYPE H3 | STANDARD NON-LOAD BEARING STUD PARTITION WITH 1 LAYER OF 5/8" GYP. BD. ON 3-5/8" METAL STUD. LOW WALL |           |             |            |

**ENV**  
ARCHITECTURE + DESIGN  
180 SYLVAN AVENUE, SUITE 3  
ENGLEWOOD CLIFFS, NJ 07632  
TEL 201 | 894 | 1000  
ENV-team.com

ENVIRONETICS GROUP ARCHITECTS, P.C.  
CLIENT:  
**SSP AMERICA**  
20408 BASHAN DRIVE  
SUITE 300  
ASHBURN, VA 20147

PROJECT TEAM:  
ARCHITECT:  
ENVIRONETICS GROUP ARCHITECTS  
180 SYLVAN AVE.  
ENGLEWOOD CLIFFS, NJ 07632  
MEP ENGINEER  
GUTH DECONZO CONSULTING  
ENGINEERS, PC  
520 8TH AVENUE, SUITE 2201  
NEW YORK, NY 10001

DocuSigned by:

**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA


| REV                 | DATE              | DESCRIPTION |
|---------------------|-------------------|-------------|
| DESIGN DELIVERABLE: | ISSUED FOR PERMIT |             |
| ISSUE DATE:         | 08/16/2024        |             |

PROJECT NUMBER: 24017G  
DRAWN BY: JP  
CHECKED BY: DC  
Copyright (c) by Environetics, Inc. All Rights Reserved.


SHEET TITLE:  
**PARTITION TYPES**

SHEET NUMBER:  
**A-001**

### PARTITION BRACING DETAIL WHEN STUDS




### DEVICE MOUNTING DETAIL



NOTES:  
 1. VERTICALLY ALIGN ADJACENT SWITCHES, SIGNAGE, SCONCES, THERMOSTATS, OUTLETS, ETC. AS INDICATED BELOW. NOTIFY ARCHITECT OF LOCATION CHANGES PRIOR TO INSTALLATION.  
 2. ALL MOUNTING HEIGHTS SHALL COMPLY WITH MANUFACTURER'S RECOMMENDATIONS AND A.D.A. (CABO/ANSI) AND ALL OTHER APPLICABLE CODES AND REGULATIONS.


### PARTITION HEAD CONDITIONS



A = PARTITION TO BOTTOM OF CEILING WALL EXTENDS TO UNDERSIDE OF CEILING  
 B = PARTITION TO ABOVE HIGHEST CEILING WALLS WILL TERMINATE AT A MINIMUM OF 6" ABOVE HIGHEST ADJOINING CEILING UNLESS NOTES OTHERWISE ON PLAN. TERMINATE 1 FULL COURSE ABOVE AT MASONRY WALLS.  
 C = PARTITION TO UNDERSIDE OF DECK WALLS WILL TERMINATE TO BOTTOM OF STRUCTURAL DECK  
 D = PARTITION TO UNDERSIDE OF DECK GYP. BD. TO TERMINATE AT A MINIMUM OF 6" ABOVE HIGHEST ADJOINING CEILING UNLESS NOTED OTHERWISE ON PLAN.  
 E = UNBRACED PARTITION TO UNDERSIDE OF DECK WALLS WILL TERMINATE TO BOTTOM OF STRUCTURAL DECK


### INTERIOR PARTITION METAL STUD SPAN CHART

THIS DATA IS BASED ON ASTM C-754-15 STANDARD SPECIFICATION FOR INSTALLATION OF STEEL FRAMING MEMBERS TO RECEIVE SCREW-ATTACHED GYPSUM PRODUCTS FOR THE PURPOSE OF LIMITING THE HEIGHTS OF UNBRACED PARTITIONS. THE USE OF THIS DATA IS SET TO MAXIMUM HEIGHT STANDARD FOR SUCH PARTITIONS. (CALCULATED AT 5 PSF LATERAL LOAD AND L/240 DEFLECTION AND ONE LAYER OF 5/8" GYPSUM BOARD EACH SIDE OF STUD.) FOR UNBRACED SPANS GREATER THAN 27' CONSULT ARCHITECT.




NOTES:  
 1. MAXIMUM UNBRACED SPAN IS DEFINED AS THE TOTAL DISTANCE BETWEEN THE TOP OF FINISHED FLOOR AND THE UNDERSIDE OF STRUCTURAL DECK OR APPROPRIATE LATERAL BRACE. SEE LATERAL BRACING DIAGRAM.  
 2. THESE SPANS ARE CALCULATED FOR ONE LAYER OF GYPSUM BOARD ON EACH SIDE OF A METAL STUD PARTITION. THESE MAXIMUM UNBRACED SPANS MUST BE REDUCED BY 2'-0" IF ONLY ONE SIDE OF 5/8" GYPSUM BOARD IS USED.  
 3. SUSPENDED CEILINGS OF ANY KIND ARE NOT TO BE CONSIDERED APPROPRIATE LATERAL BRACING FOR ANY PARTITION CONSTRUCTION AND SHALL REDUCE THE MEASUREMENT OF UNBRACED SPAN.  
 4. IN NO CASE SHALL THE MAXIMUM UNBRACED SPANS EXCEED THE REQUIREMENTS OF ASTM C-754.

### PARTITION HEAD DETAILS




PARTITION NOTES:  
 1. USE WATER AND MOLD RESISTANT GYP. BD. AT KITCHENS, BATHROOMS, JANITORS CLOSETS, AND OTHER WET AREAS.  
 2. SUBSTITUTE GLASS MESH MORTAR UNITS FOR GYP. BD. AT ALL CERAMIC TILE FINISH ROOMS. (SEE SPECS. FOR SPECIAL STUD AND ANCHORAGE REQ'D.)  
 3. USE 20ga BACKING PLATES AT HANDRAILS, GRAB BARS & OTHER WALL MOUNTED ITEMS.  
 4. PARTITION THICKNESS INDICATED ARE MINIMUM.  
 5. ALL MASONRY PARTITION TYPES TO HAVE VERTICAL MORTAR JOINTS AT BOTTOM COURSE TO BE STRUCK FLUSH.  
 6. UNLESS OTHERWISE NOTED, EXTEND ALL PARTITIONS TO DECK.

### ALTERNATE WALL BLOCKING DETAIL 'A'




### ALTERNATE WALL BLOCKING DETAIL 'B'




NOTES:  
 1. PROVIDE IN WALL BLOCKING AS REQUIRED FOR INSTALLATION OF WALL MOUNTED FIXTURES, RAILS OR OTHER ATTACHMENTS  
 2. PROVIDE ADDITIONAL BRACING AS REQ'D TO CARRY FIXTURES AND MILLWORK, TYP.

### TYPICAL WALL BLOCKING DETAIL



NOTES:  
 1. PROVIDE ADD'L BRACING WHERE REQUIRED FOR FIXTURES AND LOADS  
 2. PROVIDE ADD'L FURRING @ STUDS AS REQ'D. FOR SMOOTH FLAT SURFACE  
 3. MOUNT ALL BLOCKING AS REQ'D. FOR SUPPORT OF ACCESSORIES SHOWN ON DWGS. PROVIDE ADDITIONAL BRACING FOR SOUNDNESS AS REQ'D.



| REV                 | DATE              | DESCRIPTION |
|---------------------|-------------------|-------------|
| DESIGN DELIVERABLE: | ISSUED FOR PERMIT |             |
| ISSUE DATE:         | 08/16/2024        |             |

PROJECT NUMBER: 24017G  
 DRAWN BY: JP  
 CHECKED BY: DC

Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE:  
**PARTITION DETAILS**

SHEET NUMBER:  
**A-002**

| DOOR SCHEDULE |      |                |                   |         |         |           |       |                |                   |           |                       |              |          |   |
|---------------|------|----------------|-------------------|---------|---------|-----------|-------|----------------|-------------------|-----------|-----------------------|--------------|----------|---|
| MARK          | TYPE | DOOR           |                   |         |         |           | FRAME |                |                   |           | FIRE RATING (MINUTES) | HARDWARE SET | COMMENTS |   |
|               |      | PANEL MATERIAL | DOOR PANEL FINISH | WIDTH   | HEIGHT  | THICKNESS | TYPE  | FRAME MATERIAL | DOOR FRAME FINISH | THRESHOLD |                       |              |          | HEAD  |
| 101           | D-1  | HPL            | BY MANUFACTURER   | 3' - 0" | 7' - 0" | 1 3/4"    | F-1   | HM             | BY MANUFACTURER   | -         | H-1                   | J-1          | 1        | ELIASON DOOR. INSTALL PER MANUFACTURER'S INSTRUCTIONS |
| 102           | D-2  | HPL            | BY MANUFACTURER   | 3' - 0" | 7' - 0" | 1 3/4"    | F-1   | HM             | BY MANUFACTURER   | -         | H-1                   | J-1          | 1        | ELIASON DOOR. INSTALL PER MANUFACTURER'S INSTRUCTIONS |


### DOOR MATERIAL / SIZES / HARDWARE NOTES

|   |  |  |
|---|--|--|
| <b>MATERIAL:</b><br>AL ALUMINUM<br>HM HOLLOW METAL<br>WD SOLID CORE WOOD STAIN GRADE 5 PLY PREFINISHED<br>MTL METAL<br>IN INSULATED METAL<br>HPL HIGH PRESSURE LAMINATE | <b>FINISH:</b><br>PT EPOXY PAINT<br>ST STAIN FINISH<br>AN ANNOXIDIZED<br>FRP FIBER REINFORCED POLYESTER<br>FF FACTORY FINISH<br>DF DECORATIVE FINISH | <b>HARDWARE NOTES:</b><br>- KNOCK DOWN FRAMES SHALL HAVE MITRED CORNERS.<br>- ALL HARDWARE TO BE 26D.<br>- SEE SPECIFICATIONS FOR HARDWARE SETS<br>- VERIFY ALL HARDWARE WITH OWNER BEFORE ORDERING. |
| <b>REMARKS:</b><br>GLAZING = G1 = 1/4" TEMPERED GLASS<br>G2 = 1/4" FIRE SAFETY GLASS<br>G3 = 1" INSULATED TEMPERED GLASS  |  | <b>FIRE DOORS:</b><br>• ALL FIRE RATED DOORS TO BE RATED PER NFPA 252<br>• PROVIDE FIRE GASKETING AT ALL RATED DOORS IN ACCORDANCE WITH UL1784<br>• RATED DOORS TO INCLUDE CLOSER AND LATCH          |


- DOOR, FRAME & HARDWARE NOTES:**
- CONTRACTOR TO VERIFY ALL CONDITIONS IN FIELD. ANY DISCREPANCIES FROM WHAT IS INDICATED ON THE CONTRACT DOCUMENTS ARE TO BE BROUGHT TO THE ARCHITECTS ATTENTION. EXISTING CONDITIONS ARE TO BE INDICATED ON SHOP SUBMITTALS.
  - ALL HOLLOW METAL FRAMES SHALL BE WELDED IN NEW WALL CONSTRUCTION. PROVIDE KNOCK DOWN FRAMES IN EXISTING OPENINGS.
  - KEY LOCKS SHALL COMPLY WITH ALL LANDLORD STANDARDS.
  - VERIFY ALL HARDWARE WITH OWNER BEFORE ORDERING. ALL HARDWARE TO HAVE 26D FINISH.
  - ALL FRAMES TO BE 16 GA HOLLOW METAL.
  - PROVIDE 8" MIN. BEARING AT LINTELS, TYP.
  - PROVIDE 3 DOOR SILENCERS PER JAMB (PER 7'-0" HIGH DOOR).
  - HARDWARE SHALL BE MOUNTED AT THE LOWEST HEIGHT ALLOWED BY ICC/ANSI A117.1-2017.

**HARDWARE GROUP 1:**  
 (1) ELIASON DOOR  
 (1) HARDWARE BY MANUFACTURER  
 (1) GC TO INSTALL  
 (1) WALL STOP  
 (1) LOCK (TOGGLE SWITCH ON INSIDE AND KEY ENTRY ON OUTSIDE OF DOOR)



### DOOR LEGEND



### FRAME LEGEND



### METAL STUD HEADS + JAMBS




**ENV**  
 ARCHITECTURE + DESIGN  
 180 SYLVAN AVENUE, SUITE 3  
 ENGLEWOOD CLIFFS, NJ 07632  
 TEL 201 | 894 | 1000  
**ENV-team.com**  
 ENVIRONETICS GROUP ARCHITECTS, P.C.  
 COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED

CLIENT:  
**SSP AMERICA**  
 20408 BASHAN DRIVE  
 SUITE 300  
 ASHBURN, VA 20147

PROJECT TEAM:  
 ARCHITECT:  
 ENVIRONETICS GROUP ARCHITECTS  
 180 SYLVAN AVE.  
 ENGLEWOOD CLIFFS, NJ 07632

MEP ENGINEER  
 GUTH DECONZO CONSULTING  
 ENGINEERS, PC  
 520 8TH AVENUE, SUITE 2201  
 NEW YORK, NY 10001



**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA


| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: ISSUED FOR PERMIT  
 ISSUE DATE: 08/16/2024


PROJECT NUMBER: 24017G  
 DRAWN BY: JP  
 CHECKED BY: DC

Copyright (c) by Environetics, Inc. All Rights Reserved.  
 SHEET TITLE:  
**DOOR SCHEDULES**

SHEET NUMBER:  
**A-003**



CONSTRUCTION LEGEND




CONSTRUCTION GENERAL NOTES:

- ALL EXISTING GAS, WATER, PLUMBING AND ELECTRICAL ITEMS SHALL BE COORDINATED WITH ENGINEER AND OWNER PRIOR TO REMOVAL. PATCH & REPAIR REMAINING AREAS.
- PATCH, REPAIR, AND PREPARE ALL DAMAGED OR UNLEVELED FLOOR AREAS TO RECEIVE NEW FLOOR FINISH. COORDINATE TREATMENT OF EXISTING SURFACE TO NEW FINISH.
- WHERE PARTIAL WALL DEMOLITION IS CALLED OUT, CONTRACTOR SHALL ASSURE REMAINING PORTION TO BE FLUSH, SMOOTH AND PREPARED TO RECEIVE PLANNED ELEMENT AS SHOWN.
- ALL EXISTING REMAINING CONDUITS SHALL BE RELOCATED BEHIND THE FACE OF THE EXISTING MASONRY. ALL NEW CONDUIT SHALL BE RUN IN THE NEW OR EXISTING CONSTRUCTION. SURFACE MOUNTED CONDUIT IS UNACCEPTABLE.
- PATCH ALL DISTURBED MASONRY FLUSH WITH ADJACENT BLOCK.
- SEE APPROPRIATE SHEETS FOR FINISH AND CEILING SCHEDULES.
- CONTRACTOR SHALL PROVIDE LINTELS OVER NEW MASONRY OPENINGS. COORDINATE WITH STRUCTURAL DRAWINGS FOR EXACT SIZE, QUANTITY, AND LOCATION.
- CONTRACTOR SHALL ASSURE THAT ALL PATCHES TO EXISTING SURFACES ARE FLUSH, SMOOTH, AND PREPARED TO RECEIVE NEW FINISH SO THAT ALL PRODUCT WARRANTIES ARE ENACTED.
- CONTRACTOR SHALL ASSURE THAT ALL PATCHES DONE TO PENETRATIONS IN 2-HR. FIRE RATED WALL TO RECEIVE ANNUAL SEALANT SO THAT WALL MAINTAINS CODES COMPLIANCE.
- REFER TO DEMOLITION PLAN FOR LOCATION OF CONC. FLOOR REPAIR.
- CONTRACTOR SHALL REPAIR ALL PIPE, DUCT AND UTILITY PENETRATIONS MADE BY HIS CONTRACTORS. ALL PATCHES SHALL MATCH ADJACENT CONSTRUCTION WHERE EXPOSED. EXTEND FINISH AND PAINT TO A LOGICAL TERMINATION POINT, CORNER, WALL INTERSECTION, ETC.
- UNLESS NOTED OTHERWISE ALL CONSTRUCTION SHALL BE CONSIDERED NEW UNLESS NOTED AS EXISTING.
- UNLESS NOTED OTHERWISE CONTRACTOR SHALL PROVIDE NEW PIPE ENCLOSURE (SIZE TO MATCH EXIST.) FOR HWS/R PIPING.
- CONTRACTOR SHALL TYPICALLY PROVIDE TRANSITION STRIPS AT ALL LOCATIONS WHERE DIFFERENT FLOOR MATERIALS ARE SPECIFIED AND LOCATED.
- CONTRACTOR SHALL TYPICALLY SEAL AROUND WALL, FLOOR, AND CEILING PENETRATIONS WITH FIRE SEALANT PUTTY IN RATED WALLS.
- ALL BLOCKING TO BE FIRE RETARDANT WOOD BLOCKING.
- PATCH WALLS, FLOORS, & CEILINGS TO MATCH EXISTING AT AREAS BEYOND THE CONTRACT SCOPE OF WORK DAMAGED BY THE WORK. FINISH WALL TO MATCH ADJACENT WALLS. REFINISH WORK TO NEAREST WALL INTERSECTION OR CORNER. REPLACE BASE AS NECESSARY TO MATCH EXISTING LENGTHS NO SHORTER THAN 4'-0" OR AS CONST. ALLOWS. CUT EXISTING CEILING SYSTEMS TO REMAIN AS REQUIRED BY NEW CONSTRUCTION. PROVIDE NEW CONTINUOUS GUT WALL ANGLES NEEDED BY NEW CEILING LAYOUT. FINISH WALL TO MATCH ADJACENT WALLS. REFINISH WORK TO NEAREST WALL INTERSECTION OR CORNER. REPLACE BASE AS NECESSARY TO MATCH EXISTING LENGTHS NO SHORTER THAN 4'-0" OR AS CONST. ALLOWS. FINISH NEW INFILL WORK TO MATCH AND BLEND WITH EXISTING ADJACENT FINISH. AT BOTH EXTERIOR AND INTERIOR SURFACES.
- AT COMPLETION OF JOB, CONTRACTOR SHALL LEAVE THE AREA DUST FREE AND CLEAN.
- METAL REVEALS SHALL BE FRY REGLET OR APPROVED EQ., MILL FINISH, UNPAINTED. ALL INTERSECTIONS SHALL BE MITRED CORRECTLY.
- THE CONTRACTOR SHALL MAINTAIN ALL BARRICADES, SHORING, BRACING AND OTHER SAFETY MEASURES TO PROTECT THE BUILDING, WORKMEN AND THE PUBLIC.
- CONTRACTOR SHALL COORDINATE WITH STATE'S ASBESTOS ABATEMENT CONTRACTOR.
- PATCH ALL DISTURBED GWB FLUSH WITH ADJACENT GWB.
- THE CONTRACTOR SHALL FULLY ACQUAINT HIMSELF WITH THE EXISTING CONDITIONS AND SHALL HAVE VISITED AND INSPECTED THE JOB SITE AND BE FULLY INFORMED AS TO THE NATURE OF EQUIPMENT AND FACILITIES NEEDED FOR THE PROPER EXECUTION OF THE WORK. STARTING OF DEMOLITION AND REMOVAL OPERATIONS WILL BE CONSIDERED AS EVIDENCE THAT THE CONTRACTOR HAS COMPLIED WITH THESE REQUIREMENTS ANY LATER CLAIMS FOR DIFFICULTIES ENCOUNTERED, WHICH COULD HAVE BEEN FORESEEN, WILL NOT BE CONSIDERED.
- CONSTRUCTION OPERATIONS WILL NOT BLOCK HALLWAYS, CORRIDORS OR MEANS OF EGRESS FOR BUILDING OCCUPANTS FROM VARIOUS AREAS OF THE BUILDING.
- CONSTRUCTION OPERATIONS WILL NOT INVOLVE THE INTERRUPTION OF LIFE SAFETY OR FIRE SAFETY SERVICES TO THE BUILDING UNLESS NOTIFICATION IS MADE TO THE OWNER AND ALL LOCAL GOVERNING AUTHORITIES.
- STAGING AREAS FOR DEMOLITION AND DEBRIS REMOVAL SHALL BE COORDINATED WITH THE OWNER. DUMPSTERS SHALL BE STAGED IN THE EXISTING PAVED PARKING LOT AREA.
- RE-INSULATE HEATING PIPES, ELBOWS, FITTINGS, ETC. WHERE ASBESTOS WAS REMOVED THROUGHOUT WORK AREA.
- THE TERM "TYP." FOLLOWING A NOTE, TAG OR DETAIL FLAG INDICATES THAT ALL LIKE, SIMILAR OR INDICATED ITEMS SHALL BE PROVIDED WITH SPECIFIED DETAIL, NOTE OR SPECIFICATION.

CONSTRUCTION KEYED NOTES


| KEYNOTE | DESCRIPTION   |
|---------|---|
| C-1     | LEASE LINE. HATCHED AREA IS OUTSIDE OF THE SCOPE OF WORK. GC TO CONFIRM FINAL DIMENSIONS WITH THE AIRPORT/LANDLORD.   |
| C-2     | EXISTING CONCOURSE AREA TO BE PROTECTED THROUGH DEMO & CONSTRUCTION PHASE. PATCH/REPAIR AS REQUIRED. ANY DAMAGED AREA TO MATCH EXISTING ADJACENT.   |
| C-3     | NEW FIRE EXTINGUISHERS TO BE INSTALLED.   |
| C-4     | G.C. TO INSTALL NEW MILLWORK. SEE MILLWORK DRAWINGS FOR ADDITIONAL INFORMATION.   |
| C-5     | EXISTING WALLS TO REMAIN AND BE PROTECTED THROUGH DEMO & CONSTRUCTION PHASE. PATCH/REPAIR AS REQUIRED. INSTALL NEW FINISHES PER MANUFACTURERS' INSTRUCTION AND SPEC. MAINTAIN EXISTING RATINGS. |
| C-6     | GC TO INSTALL NEW FLOORING. GC TO PROVIDE AN ADA TRANSITION BETWEEN NEW & EXISTING FLOORING. SEE FINISH PLAN FOR ADDITIONAL INFO.   |
| C-7     | ALL FOOD SERVICE EQUIPMENT TO BE COORDINATED WITH FOOD SERVICE DRAWINGS & MEP DRAWINGS FOR ADDITIONAL INFORMATION.  |
| C-8     | NEW FLOOR SNK, FLOOR DRAIN, FLOOR CLEANOUT. REFERENCE PLUMBING DRAWINGS FOR ADDITIONAL INFORMATION.   |
| C-9     | GC TO PROVIDE WATERPROOFING PRIOR TO INSTALLING BOH FLOORING. INSTALL PER MANUFACTURER'S INSTRUCTION & SPEC.  |
| C-10    | GC TO PROVIDE WALL BLOCKING AND SUPPORT FOR SHELVING, TV MOUNTS, ETC. REFERENCE ELEVATIONS FOR ADDITIONAL INFORMATION.  |
| C-11    | UPON COMPLETION OF CONSTRUCTION & REMOVAL OF BARRICADES, CONTRACTOR SHALL CLEAN, PATCH, AND REPAIR ALL AREAS (FLOOR, WALLS, CEILING) FROM BARRICADE REMOVAL.                                    |
| C-12    | GC TO INSTALL MOVABLE PLANTERS ON CASTER AFTER CONSTRUCTION IS COMPLETE. GC TO CAP PLANTER PRIOR TO INSTALLATION REFERENCE MILLWORK DRAWINGS FOR ADDITIONAL INFORMATION.                        |
| C-13    | NEW QUEUEING RAIL IN CONCOURSE. REFER TO DETAILS FOR ADDITIONAL INFORMATION. PATCH AND REPAIR CONCOURSE AREA AS REQUIRED.   |
| C-14    | NEW ELEVATED MOP SINK. REFERENCE FOOD SERVICE DRAWINGS AND PLUMBING DRAWINGS FOR ADDITIONAL INFORMATION.  |
| C-15    | NEW ILLUMINATED SIGNAGE. REFERENCE SIGNAGE DETAILS FOR ADDITIONAL INFORMATION.  |
| C-16    | WATER HEATER MOUNTED ON 12" THICK CONCRETE PAD. PROVIDE 6" HIGH INTEGRAL BASE. SEE FOOD SERVICE AND PLUMBING DRAWINGS FOR ADDITIONAL INFORMATION.   |
| C-17    | GC TO SUPPLY POWER AND DATA AS REQUIRED AT POS STATIONS. SEE MILLWORK PLANS AND ELECTRICAL INFORMATION.   |
| C-18    | NEW PASS THROUGH WINDOW. SEE DETAILS FOR ADDITIONAL INFORMATION.  |
| C-19    | NEW FOOT RAIL AT BAR DIE WALL.  |
| C-20    | NEW I.T. CABINET ABOVE. SEE FOOD SERVICE AND ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION.  |
| C-21    | EXISTING GLASS CURTAIN WALL TO REMAIN AND BE PROTECTED THROUGH DEMO & CONSTRUCTION PHASE. PATCH/REPAIR AS REQUIRED.   |



**ENV**  
 ARCHITECTURE + DESIGN  
 180 SYLVAN AVENUE, SUITE 3  
 ENGLEWOOD CLIFFS, NJ 07632  
 TEL 201 | 894 | 1000  
 ENV-team.com  
 ENVIRONETICS GROUP ARCHITECTS, P.C.  
 COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED

CLIENT:  
**SSP AMERICA**  
 20408 BASHAN DRIVE  
 SUITE 300  
 ASHBURN, VA 20147

PROJECT TEAM:  
 ARCHITECT:  
 ENVIRONETICS GROUP ARCHITECTS  
 180 SYLVAN AVE.  
 ENGLEWOOD CLIFFS, NJ 07632  
 MEP ENGINEER  
 GUTH DECONZO CONSULTING  
 ENGINEERS, PC  
 520 8TH AVENUE, SUITE 2201  
 NEW YORK, NY 10001




**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA


| REV                 | DATE              | DESCRIPTION |
|---------------------|-------------------|-------------|
| DESIGN DELIVERABLE: | ISSUED FOR PERMIT |             |
| ISSUE DATE:         | 08/16/2024        |             |

PROJECT NUMBER: 24017G  
 DRAWN BY: MK, JP  
 CHECKED BY: DC

Copyright (c) by Environetics, Inc. All Rights Reserved.  
 SHEET TITLE:  
**CONSTRUCTION PLAN**  
 SHEET NUMBER:  
**A-101**



### CEILING LEGEND



### CEILING GENERAL NOTES

- CONTRACTOR SHALL INSTALL ACOUSTIC TILE CEILING AS SHOWN ON REFLECTED CEILING PLANS.
- UNLESS OTHERWISE NOTED, ALL LIGHT FIXTURES SHOWN MOUNTED WITHIN THE SUSPENDED CEILING GRID SHALL BE CENTERED ON THE TILE.
- ALL GRIDS SHALL BE SEISMICALLY BRACED.
- CONTRACTOR TO PROVIDE ALL ASSOCIATED POWER/BOXES/WIRING FOR NEW LIGHT FIXTURES.
- CONTRACTOR TO PROVIDE AND INSTALL CLG. ACCESS PANELS WHERE UTILITY VALVES, FILTERS, ETC. ARE LOCATED. COORDINATE IN FIELD EXACT LOCATIONS. SEE DETAIL DRAWINGS FOR ADDITIONAL INFO.
- CONTRACTOR TO VERIFY ANY LOCATION AT CEILING THAT REQUIRES AN ACCESS PANEL
- GC IS RESPONSIBLE TO PROVIDE NEW FIRE PROOFING IN ALL AREAS OF EXISTING FIRE PROOFING TO BE REMOVED IN ORDER TO ATTACH NEW CEILING AND WALL SUPPORTS, FRAMING, HANGERS, ETC. TYPICAL AT ALL STEEL BEAMS, DECK, COLUMNS, ETC. IF APPLICABLE.
- ALL DIFFUSERS, ACCESS PANELS, SPRINKLER CAPS, ETC. IN OTHER THAN WHITE CEILING TO BE PAINTED TO MATCH CEILING COLOR AFTER A.O.R. APPROVAL
- CEILING FINISHES ARE TO BE LRV 70% OR HIGHER AND EASILY CLEANABLE

### CEILING SCHEDULE

| TYPE  | MANUFACTURER | MODEL NO.         | DESCRIPTION                           | COMMENTS     |
|-------|--------------|-------------------|---------------------------------------|--------------|
| ACT-1 | ARMSTRONG    | KITCHEN ZONE #673 | 2x2 ACT TILE - WASHABLE               | COLOR: WHITE |
| ACT-2 | ARMSTRONG    | LYRA              | ACOUSTIC TILE CEILING CEILING (24x24) | COLOR: WHITE |
| GYP-1 | -            | -                 | GYP SUM CEILING                       | -            |

### LIGHTING FIXTURE SCHEDULE

| Type Mark | DESCRIPTION                        | MANUFACTURER    | MODEL NO.                       | Comments  |
|-----------|------------------------------------|-----------------|---------------------------------|---|
| A         | 24"x24" LED TROFFER LIGHT          | ACUITY          | CPX-2X2-AL07-SWW7-5 0-VB        |   |
| B         | BLACK 6" ROUND DOWNLIGHT- RECESSED | WILLIAMS        | 6DR                             |   |
| C         | BULB PENDANT LIGHTS                | B.LUX           | ILDE WOOD S / 700355U           | NATURAL OAK- BROWN TEXTILE CABLE                      |
| E         | LED TAPE LIGHT                     | KLUS            | K-CR-1220-24 / C2966 LIGER LENS | UNDER BAR LIGHTING                                    |
| G         | CANOPY LIGHTING                    | BELFER LIGHTING | MQ 2504/ BULBRITE 776785        | CHRISTINA BARSEGYAN   818.674.0070   MYILLUMINATE.COM |

ALL LIGHTING TO BE PURCHASED THROUGH:  
 CONTACT:  
 ANTHONY JOHNSON  
 ANTHONY.JOHNSON@DAVISASSOCIATESINC.COM  
 (652)-698-7898


### RCP KEYED NOTES

- R-1 DASHED LINE REPRESENTS LEASE LINE. HATCHED AREA IS OUTSIDE OF THE SCOPE OF WORK. G.C. TO CONFIRM FINAL DIMENSIONS WITH THE AIRPORT/LANDLORD.
- R-2 EXISTING AIRPORT CEILING AND LIGHTING TO REMAIN AND BE PROTECTED THROUGHOUT CONSTRUCTION. PATCH AND REPAIR AS REQUIRED. DAMAGED ITEMS TO MATCH EXISTING.
- R-3 NEW WALL MOUNTED 55" TVs TO BE INSTALLED. CONTRACTOR TO PROVIDE POWER, DATA, AND FIRE TREATED BLOCKING AS REQUIRED. REFERENCE ELEVATIONS AND MEP DRAWINGS FOR ADDITIONAL INFORMATION.
- R-4 NEW ILLUMINATED SIGNAGE. PROVIDE FIRE TREATED BLOCKING. SEE SIGNAGE DRAWINGS AND MEP DRAWINGS FOR ADDITIONAL INFORMATION.
- R-5 NEW WASHABLE ACT CEILING TO BE INSTALLED. REFERENCE CEILING SCHEDULE FOR ADDITIONAL INFORMATION.
- R-6 NEW 6" RECESSED CANS FOR GENERAL LIGHTING. REFERENCE LIGHTING SCHEDULE FOR ADDITIONAL INFORMATION.
- R-7 NEW SPEAKERS. COORDINATE WITH CLIENT'S CONSULTANT. REFERENCE ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION.
- R-8 NEW CANOPY AT STOREFRONT. REFER TO DETAILS FOR ADDITIONAL INFORMATION.
- R-9 NEW HOOD. SEE FOOD SERVICE AND MEP DRAWINGS FOR ADDITIONAL INFORMATION.
- R-10 NEW EXIT SIGN. FOR EMERGENCY LIGHTS REFER TO MEP PLANS.
- R-11 NEW MECHANICAL DIFFUSER. REFERENCE MECHANICAL DRAWINGS FOR ADDITIONAL INFORMATION.
- R-12 NEW SPRINKLER. REFERENCE SPRINKLER DRAWINGS FOR ADDITIONAL INFORMATION.
- R-13 NEW CAMERA SURFACE MOUNTED. COORDINATE WITH CLIENT'S SECURITY CONSULTANT. REFERENCE ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION.
- R-14 NEW HEAT DETECTOR. REFER TO FIRE ALARM DRAWINGS FOR ADDITIONAL INFORMATION.



CLIENT:  
**SSP AMERICA**  
 20408 BASHAN DRIVE  
 SUITE 300  
 ASHBURN, VA 20147

PROJECT TEAM:  
 ARCHITECT:  
 ENVIRONETICS GROUP ARCHITECTS  
 180 SYLVAN AVE.  
 ENGLEWOOD CLIFFS, NJ 07632  
 MEP ENGINEER  
 GUTH DECONZO CONSULTING  
 ENGINEERS, PC  
 520 8TH AVENUE, SUITE 2201  
 NEW YORK, NY 10001



**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: PERMIT  
 ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G  
 DRAWN BY: MK, JP  
 CHECKED BY: DC





Copyright (c) by Environetico, Inc. All Rights Reserved.

SHEET TITLE:  
**REFLECTED CEILING PLAN**


SHEET NUMBER:  
**A-110**

REVIT 2023






- NOTES:
1. AT EACH END OF LIGHT FIXTURE AN INTERLOCKING CROSS TEE OR LOCKING BAR MUST BE USED.
  2. THE TOTAL WEIGHT OF A LIGHT FIXTURE AND OTHER EQUIPMENT (AIR BOXES, ETC.) AND CEILING MATERIAL SUPPORTED BY THE MAIN BEAM MUST NOT EXCEED THE ALLOWABLE DEFLECTION DATA MUST BE FURNISHED AND CERTIFIED BY THE MANUFACTURER.
  3. SURFACE OR PENDENT FIXTURE MUST BE INDEPENDENTLY SUPPORTED FROM 1-1/2\"/>







CEILING GRID DETAIL  
3/8" = 1'-0"




CEILING SUPPORT DETAIL  
12" = 1'-0"


NOTE:  
HANGER WIRES 'N' & 'S' ARE IN THE SAME VERTICAL PLANE AS THE RUNNER. HANGER WIRES 'E' & 'W' ARE IN VERTICAL PLANES PERP. TO THE MAIN RUNNER. TYPICAL BRACING POINTS SHALL BE @ 12" o/c. EACH WAY w/ THE FIRST POINT WITHIN 4' OF EACH WALL.



DRYWALL GRID SYST CEILING DETAILS  
12" = 1'-0"



ACCESS PANEL IN GYP. BD. CEILING  
1 1/2" = 1'-0"




CEILING SUPPORT DETAIL - GYPSUM  
12" = 1'-0"

**EN|V**  
ARCHITECTURE + DESIGN  
180 SYLVAN AVENUE, SUITE 3  
ENGLEWOOD CLIFFS, NJ 07632  
TEL 201 | 894 | 1000  
EN|V-team.com

ENVIRONETICS GROUP ARCHITECTS, P.C.  
CLIENT:  
**SSP AMERICA**  
20408 BASHAN DRIVE  
SUITE 300  
ASHBURN, VA 20147

PROJECT TEAM:  
ARCHITECT:  
ENVIRONETICS GROUP ARCHITECTS  
180 SYLVAN AVE.  
ENGLEWOOD CLIFFS, NJ 07632  
MEP ENGINEER  
GUTH DECONZO CONSULTING  
ENGINEERS, P.C.  
520 8TH AVENUE, SUITE 2201  
NEW YORK, NY 10001




**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |


DESIGN DELIVERABLE: ISSUED FOR PERMIT  
ISSUE DATE: 08/16/2024  
PROJECT NUMBER: 24017G  
DRAWN BY: JP  
CHECKED BY: DC  
Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE:  
**TYPICAL CEILING DETAILS**


SHEET NUMBER:  
**A-112**




**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA




CEILING SECTION AT BAR SOFFIT  
 1 1/2" = 1'-0" 1




CEILING SECTION AT STOREFRONT SOFFIT  
 1 1/2" = 1'-0" 2




CEILING SECTION AT EXISTING SOFFIT  
 1 1/2" = 1'-0" 3



CEILING SECTION AT EXISTING SOFFIT AND NEW ACT  
 1 1/2" = 1'-0" 4



CANOPY DETAIL  
 3" = 1'-0" 5



CEILING SECTION AT NEW HOOD  
 1 1/2" = 1'-0" 6

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |


DESIGN DELIVERABLE: ISSUED FOR PERMIT  
 ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G  
 DRAWN BY: JP  
 CHECKED BY: DC

Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE:  
**CEILING SECTION DETAILS**

SHEET NUMBER:  
**A-113**



### FINISH PLAN LEGEND

| SYMBOL / DESCRIPTION | SYMBOL | DESCRIPTION  |
|----------------------|--------|--|
|                      |        | FINISH TAG   |
|                      |        | TRANSITION STRIP SPECIFY TYPE PER FLOORING MATERIAL CHANGE |
|                      |        | DIRECTIONAL ARROW FOR FINISH INSTALL                       |
|                      |        | EXTENTS OF FINISH  |

**NOTE FOR WATERPROOFING MEMBRANE AT BACK OF HOUSE, BAR AND AT PENETRATIONS**

- PROVIDE LATICRETE HYDROBAN (OR APPROVED EQUAL) WATERPROOFING UNDER TILE AND TO TURN 10" UP AT ALL WALLS FOLLOW MANUFACTURER'S RECOMMENDATIONS FOR SURFACE PREPARATION AND INSTALLATION METHODS.
- PRETREAT TRANSITIONS, COVES, PENETRATIONS AND DRAINS AS RECOMMENDED BEFORE APPLICATION.
- USE LATASIL AND FOAM BACKER ROD TO SEAL SPACE BETWEEN DRAIN OR PENETRATION AND FINISH. DO NOT USE A GROUT OR JOINT FILLER MORTAR.

**FINISH GENERAL NOTES**

- (ALL GENERAL NOTES APPLY TO ALL CONSTRUCTION DWGS, UNLESS NOTED OTHERWISE)
- GC TO SITE VERIFY ALL DIMENSIONS PRIOR TO CONSTRUCTION.
- GC TO SEAL AROUND ALL PENETRATIONS, CRACKS, CREVICES AND ANY OTHER OPENINGS CAPABLE OF HARBORING INSECTS OR RODENTS.
- GC TO SUBMIT CUT SHEETS AND (2) PHYSICAL SAMPLES OF ALL SPECIFIED FINISHES AND PRODUCT TO ARCHITECT FOR APPROVAL PRIOR TO ORDERING AND FABRICATION, TYP. ENTIRE CHAINSETS, PRODUCT CATALOGUES OR SAMPLE BOXES WILL NOT BE ACCEPTED AS SUBMITTALS.
- SUBMIT TWO (2) SETS OF 8 1/2" X 11" (215X280MM) DRAW DOWNS OF ALL PAINT COLORS TO ARCHITECT FOR APPROVAL PRIOR TO PAINTING.
- ALL TILE TO BE INSTALLED PER TILE COUNCIL OF AMERICA STANDARDS.
- ALL FLOOR TILE TO BE SLIP RESISTANT IN COMPLIANCE WITH ANSI A117.1-2017, SECTION 302.1
- WALL TILE AND THRESHOLD GROUT JOINTS TO ALIGN WITH TILE FLOOR GROUT JOINTS.
- HATCHED TILE DENOTES LOCATION OF FIRST FULL TILE. SEE FINISH PLAN AND ELEVATIONS FOR MORE INFO.
- REMOVAL OF EXCESS GROUT WILL BE DONE WITH WATER. THE USE OF SULFURIC OR MURIATIC ACID IS PROHIBITED. IF THESE ACIDS ARE USED, THE INSTALLER WILL BE REQUIRED TO REMOVE THE ACID AND RESTORE THE GROUT AT THEIR EXPENSE.
- GC TO PATCH, LEVEL, PREP, AND READY ALL NEW AND EXISTING SUBSTRATES THAT ARE SCHEDULED TO RECEIVE NEW FINISHES.
- GC TO PATCH AND REPAIR ANY DAMAGE TO EXISTING GWB WALLS TO A SMOOTH, PAINT-READY SURFACE PRIOR TO PAINTING.
- CONTRACTOR TO VERIFY EXISTING FINISH COATINGS AND COORDINATE COMPATIBILITY WITH NEW PAINT FINISHES. IF EXISTING FINISH COATING SPECIFICATIONS ARE UNAVAILABLE THE CONTRACTOR SHALL DO A 24"X24" MINIMUM TEST PATCH AND ALL PREVIOUSLY PAINTED SURFACES TO CHECK COMPATIBILITY. TEST PATCH TO REMAIN ON SURFACE FOR A MINIMUM OF ONE (1) WEEK.
- REFER TO INTERIOR ELEVATIONS FOR WALL FINISHES AND INSTALL PATTERNS WHERE NOTED.
- ALL WALLS SCHEDULED TO RECEIVE PAINT OR WALL COVERING MUST BE PREPARED WITH A LEVEL 4 GYPSUM BOARD FINISH (SEE GYPSUM ASSOCIATION). ALL WALLS THROUGHOUT TO RECEIVE (1) COAT OF PRIMER AND (2) COATS OF SPECIFIED PAINT. REFER TO FINISH SCHEDULE AND PAINT LEGEND FOR MORE INFO.
- ALL PAINTED DOOR FRAMES TO MATCH ADJACENT WALL COLOR, REF. PAINT LEGEND FOR PAINT FINISH.
- GC TO SUPPLY AND INSTALL SCHEDULED TRANSITION STRIP STYLE AND COLOR AT ALL LOCATIONS WHERE INDICATED ON FINISH PLAN NO EXCEPTIONS. GC TO PROVIDE SAMPLE OF EACH TRANSITION PROFILE AS SUBMITTAL PRIOR TO ORDERING.
- GC TO ENSURE ALL SUBS AND INSTALLERS REACH OUT DIRECTLY TO NOTED ARCHITECTURAL SALES REPS PROVIDED IN
- THE FINISH SCHEDULE FOR ACCURATE PRODUCT ORDERS AND PRICING SPECIFIC TO THIS PROJECT, TYP.
- REFER TO ARCHITECTURAL REFLECTED CEILING PLAN FOR ALL CEILING INFORMATION.
- SMOKE-DEVELOPMENT RATING AND FLAME SPREAD RATINGS FOR ALL CEILING TILES ARE TO COMPLY WITH APPLICABLE CODES
- GC TO COORDINATE ALL WORK WITH OWNER AS REQUIRED.
- GC, SUBCONTRACTORS AND SUPPLIERS TO COORDINATE ANY CONFLICTS & SCHEDULING WITH EACH DISCIPLINE'S SCOPE OF WORK.
- ALL FINISHES & MATERIALS SUPPLIED & INSTALLED BY GC. U.N.O
- ALL FINISHES ARE TO BE INSTALLED AS PER MANUFACTURER'S RECOMMENDATIONS.
- ALL INTERIOR FINISHES TO HAVE A MINIMUM OF A CLASS C FIRE RATED FINISH ALL BLOCKING TO BE FIRE RATED

**FINISH KEYED NOTES**

|     |  |
|-----|--|
| F-1 | EXISTING CONCOURSE FLOORING TO REMAIN. PROTECT DURING CONSTRUCTION AND DEMOLITION PHASE. PATCH AND REPAIR AS REQUIRED TO MATCH EXISTING FLOOR.                           |
| F-2 | PROVIDE WATERPROOF MEMBRANE FOR FULL EXTENT OF KITCHEN AND BOH.  |
| F-3 | NEW CORNER GAURD OR WALL TRANSITION STRIP TO BE INSTALLED. REFERENCE FINISH DETAILS FOR ADDITIONAL INFORMATION.  |
| F-4 | REFERENCE MILLWORK DRAWINGS FOR ADDITIONAL INFORMATION REGARDING FINISHES AND LOCATIONS.   |
| F-5 | NEW WINDOW FILM SPECIFIED BY AIRPORT TO BE APPLIED TO WINDOW. CONCESSIONAIRE TO PROPOSE AND AIRPORT TO APPROVE.  |
| F-6 | NEW FLOOR SINK/FLOOR DRAIN/CLEAN OUT LOCATION WHERE INDICATED. REFERENCE FOOD SERVICE AND MEP DRAWINGS FOR ALL LOCATIONS AND ADDITIONAL INFORMATION.                     |
| F-7 | WATER HEATER MOUNTED ON 12" THICK CONCRETE PAD. PROVIDE 6" HIGH INTEGRAL BASE. SEE FOOD SERVICE AND PLUMBING DRAWINGS FOR ADDITIONAL INFORMATION.                        |
| F-8 | NEW MOP SINK. SEE FOOD SERVICE DRAWINGS AND PLUMBING DRAWINGS FOR ADDITIONAL INFORMATION.  |
| F-9 | GC TO INSTALL MOVABLE PLANTERS ON CASTER AFTER CONSTRUCTION IS COMPLETE. GC TO CAP PLANTER PRIOR TO INSTALLATION REFERENCE MILLWORK DRAWINGS FOR ADDITIONAL INFORMATION. |

**ENV**  
ARCHITECTURE + DESIGN


180 SYLVAN AVENUE, SUITE 3  
ENGLEWOOD CLIFFS, NJ 07632  
TEL 201 | 894 | 1000  
ENV-team.com

ENVIRONETICS GROUP ARCHITECTS, P.C.  
COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED

CLIENT:  
**SSP AMERICA**  
20408 BASHAN DRIVE  
SUITE 300  
ASHBURN, VA 20147

PROJECT TEAM:  
ARCHITECT:  
ENVIRONETICS GROUP ARCHITECTS  
180 SYLVAN AVE.  
ENGLEWOOD CLIFFS, NJ 07632

MEP ENGINEER  
GUTH DECONZO CONSULTING  
ENGINEERS, PC  
520 8TH AVENUE, SUITE 2201  
NEW YORK, NY 10001



**BFB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA

| REV                 | DATE              | DESCRIPTION |
|---------------------|-------------------|-------------|
| DESIGN DELIVERABLE: | ISSUED FOR PERMIT |             |
| ISSUE DATE:         | 08/16/2024        |             |

PROJECT NUMBER: 24017G  
DRAWN BY: MK  
CHECKED BY: DC




Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE:  
**FINISH PLAN**


SHEET NUMBER:  
**A-120**

# FINISH SCHEDULE

| MARK                 | GROUP         | DESCRIPTION                 | MANUFACTURER         | MODEL                          | STYLE/COLOR                     | COMMENTS                      | CONTACT  |
|----------------------|---------------|-----------------------------|----------------------|--------------------------------|---------------------------------|-------------------------------|--|
| <b>BASE</b>          |               |                             |                      |                                |                                 |                               |  |
| B-1                  | BASE          | BASE                        | CHEMETAL             | 354                            | ALU DARK                        | --                            | Cam Post   800.807.7341 ext. 2100   cpost@chemetal.com           |
| RSB-1                | BASE          | INTEGRAL BASE               | ALTRO                | STRONGHOLD 30                  | TUNDRA                          | --                            | Jennifer Williamson   320.463.3215   jwilliamson@altro.com       |
| <b>BOH FLOORING</b>  |               |                             |                      |                                |                                 |                               |  |
| RSF-1                | BOH FLOORING  | RESILIENT FLOORING          | ALTRO                | STRONGHOLD 30                  | TUNDRA                          | --                            | Jennifer Williamson   320.463.3215   jwilliamson@altro.com       |
| <b>FLOOR TILE</b>    |               |                             |                      |                                |                                 |                               |  |
| FT-1                 | FLOOR TILE    | FLOOR TILE                  | DALTILE              | IMAGICA, COLORBODY             | 12" X 24" HAZE IG97, UNPOLISHED | LATICRETE GROUT: SPECTARLOCK  | Terrie Miller   216.409.3153   terrie.miller@daltile.com         |
| <b>GLASS</b>         |               |                             |                      |                                |                                 |                               |  |
| GL-1                 | GLASS         | 1-1/4" INSULATED            |                      |                                |                                 | GLASS UNIT WITH LOW-E COATING |  |
| <b>METAL</b>         |               |                             |                      |                                |                                 |                               |  |
| MT-1                 | METAL         | LAZER CUT METAL             | MOZ DESIGNS          | LINES                          | SILVER METALLIC                 | --                            | Katie Hynes   410.698.3767   katie@mozdesigns.com                |
| MT-2                 | METAL         | METAL                       | MOZ DESIGNS          | CUSTOM CLASSIC METAL           | NICKLE                          | --                            | Katie Hynes   410.698.3767   katie@mozdesigns.com                |
| PC-1                 | METAL         | POWDER COAT                 | PRISMATIC POWDERS    | RAL-6018                       | RAL 6018                        | --                            | Jessie Graham   541.830.6502   jessie@nicindustries.com          |
| PC-2                 | METAL         | POWDER COAT                 | PRISMATIC POWDERS    | USS-11164                      | BLACK OUT                       | --                            | Jessie Graham   541.830.6502   jessie@nicindustries.com          |
| PC-3                 | METAL         | POWDER COAT                 | PRISMATIC POWDERS    | USS-0238                       | WHISPER WHITE                   | --                            | Jessie Graham   541.830.6502   jessie@nicindustries.com          |
| PC-4                 | METAL         | POWDER COAT                 | PRISMATIC POWDERS    | PSS-5768                       | SUBLIME                         | --                            | Jessie Graham   541.830.6502   jessie@nicindustries.com          |
| <b>PAINT</b>         |               |                             |                      |                                |                                 |                               |  |
| PNT-1                | PAINT         | CEILING PAINT               | BENJAMIN MOORE       | OC-152                         | SUPER WHITE                     | --                            | Diana Rattazzi   914.261.8603   diana.rattazzi@benjaminmoore.com |
| <b>SOLID SURFACE</b> |               |                             |                      |                                |                                 |                               |  |
| SS-1                 | SOLID SURFACE | SOLID SURFACE               | WILSONART            | 9243SS                         | CLOUD MIST                      | --                            | Rhichelle Sigafos   215.219.1133   sigafor@wilsonart.com         |
| <b>TRANSITION</b>    |               |                             |                      |                                |                                 |                               |  |
| TR-1                 | TRANSITION    | TRANSITION                  | SCHULTER             | RENO-U                         | BRUSHED CHROME ANODIZED         | --                            | Andrew Ferraiuolo   973.204.0455   aferraiuolo@schluter.com      |
| TR-2                 | TRANSITION    | TRANSITION                  | SCHULTER             | SCHIENE                        | BRUSHED CHROME ANODIZED         | --                            | Andrew Ferraiuolo   973.204.0455   aferraiuolo@schluter.com      |
| <b>WALL COVERING</b> |               |                             |                      |                                |                                 |                               |  |
| WC-1                 | WALL COVERING | WALL COVERING               | KOROSEAL             | DIGIAL WALLCOVERING            | CUSTOM                          | --                            | Tina Rouzarie   201.953.0853   trouzarie@koroseal.com            |
| <b>WALL PANELING</b> |               |                             |                      |                                |                                 |                               |  |
| WP-1                 | WALL PANELING | WALL PANELING               | URBAN EVOLUTIONS     | CLASSIC SLAT WALL              | WHITE OAK MATTE/CLEAR           | --                            | Matt Rasmussen   920.257.5978   matt@urbanevolutions.com         |
| WP-2                 | WALL PANELING | WALL PANELING               | TERRAMAI             | ENGINEERED FLOORING & PANELING | MC WHITE OAK                    | --                            | Rick Ogle   332.259.6236   rick@terramai.com                     |
| WP-3                 | WALL PANELING | CHALK BOARD PANEL           | FORMICA              | M2253                          | BLACK MAGNETIC CHALKBOARD       | --                            | Kathleen Schielke   646.302.5540   kathleen.schielke@formica.com |
| <b>WALL TILE</b>     |               |                             |                      |                                |                                 |                               |  |
| FRP-1                | WALL TILE     | FIBERGLASS REINFORCED PANEL | MARLITE              | STANDARD FRP                   | P100                            | --                            | Tom Lenox   330.260.7608   tlenox@marlite.com                    |
| WT-1                 | WALL TILE     | WALL TILE                   | SANTOS HERTAGE FIELD | 4" x 4" GLAZED TILE            | EMERALD GREEN, RUNNING BOND     | GROUT: MAPEI 5221 MOONBEAM    | Jon Waldorf   jon@designanddirectsource.com                      |
| WT-2                 | WALL TILE     | WALL TILE                   | DALTILE              | COLOR WHEEL CLASSIC            | ARCTIC WHITE                    | GROUT: MAPEI 5221 MOONBEAM    | Terrie Miller   216.409.3153   terrie.miller@daltile.com         |
| <b>WOOD VENEER</b>   |               |                             |                      |                                |                                 |                               |  |
| WV-1                 | WOOD VENEER   | WOOD VENEER                 | FORMICA              | 6932-26                        | MACCHIATO WALNUT                | --                            | Kathleen Schielke   646.302.5540   kathleen.schielke@formica.com |




MFR: SCHLUTER  
 STYLE: JOLLY  
 FINISH: BRUSHED CHROME ANODIZED  
 LOCATION: TILE PLATFORM




CORNER GUARD DETAILS  
 3" = 1'-0"


SCHLUTER JOLLY  
 6" = 1'-0"




TYPICAL FLOOR CRACK DETAIL  
 3" = 1'-0"




TYP. CONTROL JOINT DETAIL  
 3" = 1'-0"




SCHLUTER SCHIENE  
 6" = 1'-0"



SCHLUTER RENO-U  
 6" = 1'-0"



WATERPROOFING DETAIL  
 6" = 1'-0"



RESILIENT FLOOR COVE BASE DETAIL  
 6" = 1'-0"

**ENV**  
 ARCHITECTURE + DESIGN  
 180 SYLVAN AVENUE, SUITE 3  
 ENGLEWOOD CLIFFS, NJ 07632  
 TEL 201 | 894 | 1000  
 ENV-team.com  
 ENVIRONETICS GROUP ARCHITECTS, P.C.  
 COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED

CLIENT:  
**SSP AMERICA**  
 20408 BASHAN DRIVE  
 SUITE 300  
 ASHBURN, VA 20147

PROJECT TEAM:  
 ARCHITECT:  
 ENVIRONETICS GROUP ARCHITECTS  
 180 SYLVAN AVE.  
 ENGLEWOOD CLIFFS, NJ 07632  
 MEP ENGINEER  
 GUTH DECONZO CONSULTING  
 ENGINEERS, PC  
 520 8TH AVENUE, SUITE 2201

DocuSigned by:  
  
 PETER ERDEMUGLU  
 REGISTERED ARCHITECT  
 NO. AR97605


**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA

| REV                 | DATE              | DESCRIPTION |
|---------------------|-------------------|-------------|
| DESIGN DELIVERABLE: | ISSUED FOR PERMIT | 08/16/2024  |

|                 |        |
|-----------------|--------|
| PROJECT NUMBER: | 24017G |
| DRAWN BY:       | MK, JP |
| CHECKED BY:     | DC     |

Copyright (c) by Environetics, Inc. All Rights Reserved.  
 SHEET TITLE:  
**FINISH SCHEDULE AND TYPICAL FINISH DETAILS**

SHEET NUMBER:  
**A-121**




**GENERAL MILLWORK NOTES**

- GC IS RESPONSIBLE FOR DRY WALL CONSTRUCTION, MILLWORK TO ATTACH TO WALL.
- GC TO SUBMIT SHOP DRAWINGS FOR ARCHITECT APPROVAL PRIOR TO FABRICATION.
- ALL EQUIPMENT, CUT OUTS AND CLEARANCES TO BE COORDINATED WITH FS DRAWINGS AND CUT SHEETS.
- INSTALL ALL CABINETS AND MILLWORK PRIOR TO TILING THE FLOOR.
- ALL POWER SOURCES AND ELECTRICAL WIRING MUST BE FULLY CONCEALED FROM CUSTOMERS SIGHTLINES.
- ALL STORAGE SHELVES MUST HAVE HINGED DOORS WITH RECESSED/FLUSH LOCKS AND PULL HANDLES. (U.N.O)
- CONTINUOUS LED LIGHTING WITHIN FIXTURES/MILLWORK MUST BE INSTALLED IN A RECESSED MANNER WITHIN COVE OR OTHERWISE NOTED, AND A DIFFUSER MUST BE PROVIDED TO AVOID "HOT" OR "SHADOW" SPOTS.
- ALL COUNTERTOPS TO BE SOLID SURFACES OR OTHER DURABLE MATERIAL AND MUST HAVE BEVELED OR RADIUS EDGES.
- POS EQUIPMENT MUST BE FULLY INTEGRATED AND CONCEALED WITHIN MILLWORK AND SHROUDS MUST BE PROVIDED FOR COUNTERTOP MONITORS.
- ALL FIXTURES AND MILLWORK MUST BE PROPERLY PROTECTED AT EXPOSED EDGES AND POINTS OF IMPACT BY USE ON NECESSARY CORNER GUARDS OR SPLINES. CORNER GUARDS MUST BE OF SLIM DESIGN, RECESSED FLUSH AND POWDER COATED TO MATCH ADJACENT MATERIAL FINISH FOR A CONSISTENT LOOK.
- ALL UPHOLSTERY/ FABRICS MUST MEET AIRPORT AND LOCAL CODE FLAMMABILITY REQUIREMENTS AND HAVE A COMMERCIAL-GRADE RATING OF 100,000 DOUBLE-RUBS OR GREATER.

**ENV**  
 ARCHITECTURE + DESIGN  
 180 SYLVAN AVENUE, SUITE 3  
 ENGLEWOOD CLIFFS, NJ 07632  
 TEL 201 | 894 | 1000  
 ENV-team.com  
 ENVIRONETICS GROUP ARCHITECTS, P.C.  
 COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED

CLIENT:  
**SSP AMERICA**  
 20408 BASHAN DRIVE  
 SUITE 300  
 ASHBURN, VA 20147

PROJECT TEAM:  
 ARCHITECT:  
 ENVIRONETICS GROUP ARCHITECTS  
 180 SYLVAN AVE.  
 ENGLEWOOD CLIFFS, NJ 07632  
 MEP ENGINEER  
 GUTH DECONZO CONSULTING  
 ENGINEERS, PC  
 520 8TH AVENUE, SUITE 2201  
 NEW YORK, NY 10001



**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: DESIGN  
 ISSUE DATE: 08/16/2024  
 ISSUED FOR PERMIT  
 08/16/2024


PROJECT NUMBER: 24017G  
 DRAWN BY: JP  
 CHECKED BY: DC

Copyright (c) by Environetics, Inc. All Rights Reserved.


SHEET TITLE:  
**MILLWORK PLAN**

SHEET NUMBER:  
**A-130**


NOTE: FINAL SHOP DRAWINGS TO BE PROVIDED FOR ALL MILLWORK FOR FINAL APPROVAL BY ARCHITECT PRIOR TO ORDER, FABRICATION, OR INSTALLATION.




BAR ENLARGED PLAN 1/2" = 1'-0" 1




BAR MILLWORK ELEVATION 1/2" = 1'-0" 2




ADA BAR SEATING ELEVATION 1/2" = 1'-0" 3




SECTION AT BAR COUNTER 1 1/2" = 1'-0" 4




SECTION AT ADA BAR COUNTER 1 1/2" = 1'-0" 5



FRONT COUNTER ENLARGED PLAN 1/2" = 1'-0" 6



FRONT COUNTER ELEVATION 1/2" = 1'-0" 7



SECTION AT FRONT COUNTER 1 1/2" = 1'-0" 8





Table with columns: REV, DATE, DESCRIPTION. Row 1: DESIGN DELIVERABLE: ISSUED FOR PERMIT. Row 2: ISSUE DATE: 08/16/2024

Table with columns: PROJECT NUMBER, DRAWN BY, CHECKED BY. Row 1: PROJECT NUMBER: 24017G, DRAWN BY: JP, CHECKED BY: DC


Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE: MILLWORK ENLARGED PLANS, ELEVATIONS, AND DETAILS


NOTE: FINAL SHOP DRAWINGS TO BE PROVIDED FOR ALL MILLWORK FOR FINAL APPROVAL BY ARCHITECT PRIOR TO ORDER, FABRICATION, OR INSTALLATION.




BACK OF BAR COUNTER ENLARGED PLAN  
1/2" = 1'-0" 1




BACK OF BAR COUNTER ELEVATION  
1/2" = 1'-0" 2




BACK OF BAR COUNTER SECTION  
1 1/2" = 1'-0" 3




QUEUEING RAIL ENLARGED PLAN  
1/2" = 1'-0" 4




QUEUEING RAIL ELEVATION  
1/2" = 1'-0" 5




SECTION DETAIL AT QUEUEING RAIL  
1 1/2" = 1'-0" 6



PLANTER ENLARGED PLAN  
1/2" = 1'-0" 7



PLANTER ELEVATION  
1/2" = 1'-0" 8




PLANTER SECTION  
1 1/2" = 1'-0" 9

**ENV**  
ARCHITECTURE + DESIGN  
180 SYLVAN AVENUE, SUITE 3  
ENGLEWOOD CLIFFS, NJ 07632  
TEL 201 | 894 | 1000  
ENV-team.com  
ENVIRONETICS GROUP ARCHITECTS, P.C.  
COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED

CLIENT:  
**SSP AMERICA**  
20408 BASHAN DRIVE  
SUITE 300  
ASHBURN, VA 20147

PROJECT TEAM:  
ARCHITECT:  
ENVIRONETICS GROUP ARCHITECTS  
180 SYLVAN AVE.  
ENGLEWOOD CLIFFS, NJ 07632  
MEP ENGINEER  
GUTH DECONZO CONSULTING  
ENGINEERS, PC  
520 8TH AVENUE, SUITE 2201  
NEW YORK, NY 10001



**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA


| REV                 | DATE              | DESCRIPTION |
|---------------------|-------------------|-------------|
| DESIGN DELIVERABLE: | ISSUED FOR PERMIT |             |
| ISSUE DATE:         | 08/16/2024        |             |

PROJECT NUMBER: 24017G  
DRAWN BY: JP  
CHECKED BY: DC

Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE:  
**MILLWORK ENLARGED PLANS, ELEVATIONS, AND DETAILS**

SHEET NUMBER:  
**A-132**



**FURNITURE PLAN GENERAL NOTES**

- BUILT-IN CABINETS AND BAR ARE BY MILLWORKER. FIELD VERIFY EXISTING CONDITIONS PRIOR TO FABRICATION. SEE SPECS FOR SHOP DRAWING SUBMITTAL REQUIREMENTS.
- FIELD VERIFY ALL EXISTING CONDITIONS FOR BOOTHS. SEE SPECIFICATIONS FOR SHOP DRAWING SUBMITTAL REQUIREMENTS.
- SEE KITCHEN DRAWINGS FOR BAR AND KITCHEN EQUIPMENT INFORMATION. IT IS THE GENERAL CONTRACTORS RESPONSIBILITY TO VERIFY AND CONFIRM W/ VENDORS ALL EQUIPMENT AND QUANTITIES. CONFIRM THE ORDERED EQUIPMENT MATCHES EQUIPMENT PLAN AND MODEL NUMBER IN THE EQUIPMENT/ FURNITURE SCHEDULE. REPORT ANY DISCREPANCIES TO ARCHITECT AND VERIFY WITH ENGINEERS DRAWINGS (OR DESIGN BUILD M.E.P. AS APPLICABLE).
- G.C. TO SET IN PLACE ALL KITCHEN AND BAR EQUIPMENT (INCLUDING WALK-IN BOXES). ELECTRICAL CONTRACTOR AND PLUMBING CONTRACTOR ARE RESPONSIBLE FOR CONTROL AND INTERCONNECTION WIRING FOR WALK-IN BOXES AND HOODS. ELECTRICAL CONTRACTOR AND PLUMBING CONTRACTOR ARE RESPONSIBLE FOR ALL FINAL CONNECTIONS TO EQUIPMENT.
- KITCHEN VENDOR TO VERIFY CLEAR DIMENSIONS PRIOR TO ORDERING WALK-IN BOXES. COORDINATE W/ G.C. TO PROVIDE 1-1/2" AIR SPACE AROUND WALK-IN BOXES.
- G.C. TO FIRMLY ANCHOR ANY FURNITURE OR EQUIPMENT REQUIRED TO BE FIXED. CAULK AND SEAL TO WALLS AND FLOOR.
- KITCHEN EQUIPMENT BELOW HOOD MUST BE ON CASTERS AND INSTALLED WITH QUICK DISCONNECTS FOR CLEANING PURPOSES.
- 3" GROMMET WITH SLEEVE TYP. IN COUNTERTOP AT MONITORS, PRINTERS, ETC. G.C. TO COORDINATE EXACT LOCATION WITH OWNER.
- G.C. TO SEAL ALL WALK-IN BOX PENETRATIONS.

**FURNITURE EQUIPMENT SCHEDULE**

| MARK | DESCRIPTION                  | MANUF.          | MODEL            | COMMENTS                                | QTY |
|------|------------------------------|-----------------|------------------|---|-----|
| CH-1 | RESTO BARSTOOL               | DIVISION TWELVE | RESTRO-101301A   | JET BLACK POWDER COAT                   | 16  |
| CH-2 | RESTO DINING CHAIR           | DIVISION TWELVE | RESTRO-101101A   | JET BLACK POWDER COAT                   | 8   |
| T-1  | FUNK SQUARE 24" DINING TABLE | DIVISION TWELVE | D12-FUNK-105400A | JET BLACK POWDER COAT AND WHITE OAK TOP | 3   |

**ACCESSORY SCHEDULE**

| MARK | DESCRIPTION      | MANUF. | MODEL                   | COMMENTS | QTY |
|------|------------------|--------|-------------------------|----------|-----|
| H    | HEWI DOUBLE HOOK | HAFELE | 842.62.2.90 / JET BLACK |          | 9   |

**FURNITURE/EQUIPMENT KEYED NOTES**

- FE-1 FOOD SERVICE EQUIPMENT SHOWN HERE FOR REFERENCE ONLY. SEE MEP AND FOOD SERVICE DRAWINGS FOR ADDITIONAL INFORMATION.
- FE-2 LOCATIONS OF ADA SEATING. DASHED LINES INDICATED CLEAR FLOOR SPACE REQUIRED.
- FE-3 NEW MILLWORK. COORDINATE WITH CLIENT ON POWER AND DATA. REFER TO MILLWORK PLANS AND DETAILS FOR ADDITIONAL INFORMATION.
- FE-4 POS STATION. PROVIDE POWER AND DATA AS REQUIRED.
- FE-5 NEW SELF ORDER KIOSK. GC TO PROVIDE POWER AND DATA AS REQUIRED. SELF ORDER KIOSK WILL COMPLY WITH ALL ACCESSIBILITY REQUIREMENTS INCLUDING PROVIDING A CLEAR FLOOR SPACE AS ILLUSTRATED. GC TO SUBMIT SELF ORDER KIOSK AND/ OR MOUNTING STAND TO ARCHITECT PRIOR TO ORDERING AND INSTALLATION.
- FE-6 NEW FOOTRAIL FOR SEATING. SEE CONSTRUCTION DRAWINGS FOR ADDITIONAL INFORMATION.


| SEATING COUNT - LOCATION |                 |
|--------------------------|-----------------|
| DINING                   | 6 SEATS         |
| BAR:                     | 18 SEATS        |
| <b>TOTAL:</b>            | <b>24 SEATS</b> |

| ADA SEATING SCHEDULE   |  |
|------------------------|--|
| 24 SEATS X (.10) = 2.4 |  |
| 2 ADA SEATS REQUIRED   |  |
| 3 ADA SEATS PROVIDED   |  |

**ENV**  
ARCHITECTURE + DESIGN  
180 SYLVAN AVENUE, SUITE 3  
ENGLEWOOD CLIFFS, NJ 07632  
TEL 201 | 894 | 1000  
ENV-team.com  
ENVIRONETICS GROUP ARCHITECTS, P.C.  
COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED

CLIENT:  
**SSP AMERICA**  
20408 BASHAN DRIVE  
SUITE 300  
ASHBURN, VA 20147

PROJECT TEAM:  
ARCHITECT:  
ENVIRONETICS GROUP ARCHITECTS  
180 SYLVAN AVE.  
ENGLEWOOD CLIFFS, NJ 07632  
MEP ENGINEER  
GUTH DECONZO CONSULTING  
ENGINEERS, PC  
520 8TH AVENUE, SUITE 2201  
NEW YORK, NY 10001



**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: ISSUED FOR PERMIT  
ISSUE DATE: 08/16/2024


PROJECT NUMBER: 24017G  
DRAWN BY: JP  
CHECKED BY: DC

Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE:  
**FURNITURE & EQUIPMENT PLAN**

SHEET NUMBER:  
**A-140**





### POWER/COMM. LEGEND

#### WIRING DEVICES

WALL MTD CONVENIENCE OUTLETS @ 18" AFF (UNO)  
SUBSCRIPT DENOTES MT. HT. TO CTR. OF DEVICE OTHERWISE





FLOOR MTD CONVENIENCE OUTLETS:  
SINGLE DUPLEX "TRIPLEX" "QUAD" SPECIAL PURPOSE

#### TELECOMM (VOICE/DATA) DEVICES


WALL MTD VOICE/DATA OUTLETS @ 18" AFF (UNO)  
SUBSCRIPT DENOTES MT. HT. TO CTR. OF DEVICE OTHERWISE




#### FLOOR MTD VOICE/DATA OUTLETS:



#### JUNCTION/PULL BOXES



#### KEYPAD LOCKS





#### WIREMOLD



**NOTE 1**  
PROVIDE BACKBOXES WITH BLANK PLATE, CONDUITS AND PULLS FOR FUTURE DATA RECEPTACLES.

**NOTE 2**  
REFERENCE ELCTRICAL PLANS FOR ALL POWER, DATA LOCATIONS.


#### FLOOR CORE DRILL



#### ELECTRIC PANEL



#### STROBE/LOUD SPEAKERS/AV DEVICES



TO BE CONNECTED TO BUILDING ANNOUNCEMENT SYSTEM, COORDINATE W/ BLDG. MGMT.

#### POWER & DATA KEYED NOTES

|     |   |
|-----|---|
| P-1 | SEE FOOD SERVICE DRAWINGS FOR INFORMATION ON ALL EQUIPMENT. GO TO PROVIDE POWER AND DATA TO NEW EQUIPMENT AS REQUIRED. SEE ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION.          |
| P-2 | NEW POWER AND DATA TO BE SUPPLIED TO NEW POS LOCATION. SEE FOOD SERVICE DRAWINGS FOR ADDITIONAL INFORMATION. SEE ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION.                    |
| P-3 | NEW POWER AND DATA TO BE SUPPLIED TO DIGITAL MENU BOARDS. SEE ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION.   |
| P-4 | NEW POWER AND DATA TO BE SUPPLIED TO TELEVISION. SEE MANUFACTURER'S DETAILS FOR ADDITIONAL INFORMATION ON BLOCKING AND BRACKET. SEE ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION. |
| P-5 | NEW POWER AND DATA TO BE SUPPLIED TO MILLWORK. NEW OUTLETS TO BE INSTALLED THROUGHOUT BAR SEATING 4'-0" O.C. SEE ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION.                    |
| P-6 | NEW POWER TO BE SUPPLIED TO SIGNAGE ABOVE. GO TO PROVIDE POWER AS REQUIRED. SEE LOCATION OF SIGNAGE ON ELEVATIONS. SEE ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION.              |
| P-7 | NEW I.T. CABINET. GO TO PROVIDE POWER AS REQUIRED. SEE ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION.  |
| P-8 | NEW ELECTRICAL PANEL. SEE ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION.   |
| P-9 | NEW POWER AND DATA TO BE RUN FOR NEW SELF ORDER KIOSK. REFER TO ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION.   |




180 SYLVAN AVENUE, SUITE 3  
ENGLEWOOD CLIFFS, NJ 07632  
TEL 201 | 894 | 1000  
ENV-team.com

ENVIRONETICS GROUP ARCHITECTS, P.C.  
COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED

CLIENT:  
**SSP AMERICA**  
20408 BASHAN DRIVE  
SUITE 300  
ASHBURN, VA 20147

PROJECT TEAM:  
ARCHITECT:  
ENVIRONETICS GROUP ARCHITECTS  
180 SYLVAN AVE.  
ENGLEWOOD CLIFFS, NJ 07632

MEP ENGINEER  
GUTH DECONZO CONSULTING  
ENGINEERS, PC  
520 8TH AVENUE, SUITE 2201  
NEW YORK, NY 10001



**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA

| REV                 | DATE              | DESCRIPTION |
|---------------------|-------------------|-------------|
| DESIGN DELIVERABLE: | ISSUED FOR PERMIT |             |
| ISSUE DATE:         | 08/16/2024        |             |


PROJECT NUMBER: 24017G  
DRAWN BY: JP  
CHECKED BY: DC

Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE:  
**POWER & DATA PLAN**

SHEET NUMBER:  
**A-150**

REVIT 2023



**ELEVATION KEYED NOTES**

|       |   |
|-------|---|
| IE-1  | LIGHT FIXTURE. REFER TO LIGHTING PLAN FOR ADDITIONAL INFORMATION.   |
| IE-2  | FURNITURE/EQUIPMENT PROVIDED BY VENDOR.   |
| IE-3  | NEW ILLUMINATED SIGNAGE. GC TO SUPPLY DATA AND POWER AS REQUIRED. SEE DETAILS FOR ADDITIONAL INFORMATION. SEE ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION. |
| IE-4  | NEW SIGNAGE. SEE DETAILS FOR ADDITIONAL INFORMATION.  |
| IE-5  | POS STATION. GC TO PROVIDE POWER AND DATA AS REQUIRED. PROVIDE 2" GROMMET IN COUNTERTOP.  |
| IE-6  | NEW TV TO BE PROVIDED AND INSTALLED BY GC. PROVIDE POWER AND DATA AS REQUIRED.  |
| IE-8  | EXISTING BASE BUILDING FINISH TO REMAIN AND BE PROTECTED. REPAIR ANY DAMAGE TO MATCH EXISTING.  |
| IE-10 | NEW PASS THROUGH WINDOW AND COUNTER. SEE DETAILS FOR ADDITIONAL INFORMATION.  |
| IE-11 | EXISTING CURTAIN WALL GLAZING AND FRAME.  |
| IE-12 | NEW SELF ORDER KIOSK. GC TO PROVIDE POWER AND DATA AS REQUIRED.   |
| IE-13 | NEW ROLLABLE PLANTERS. REFERENCE MILLWORK DRAWINGS FOR ADDITIONAL INFORMATION.  |
| IE-14 | NEW OUTLET TO BE INSTALLED. REFERENCE ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION.   |
| IE-15 | NEW SECURITY CAMERAS. PROVIDE POWER AND DATA AS REQUIRED.   |
| IE-16 | NEW BAR FOOT RAIL.  |
| IE-17 | NEW COAT HOOK TO BE INSTALLED. REFERENCE ACCESSORIES SCHEDULE FOR ADDITIONAL INFORMATION.   |
| IE-18 | NEW FIRE EXTINGUISHER ON WALL.  |


**ENV**  
ARCHITECTURE + DESIGN

180 SYLVAN AVENUE, SUITE 3  
ENGLEWOOD CLIFFS, NJ 07632  
TEL 201 | 894 | 1000  
ENV-team.com


ENVIRONETICS GROUP ARCHITECTS, P.C.  
COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED

CLIENT:  
**SSP AMERICA**  
20408 BASHAN DRIVE  
SUITE 300  
ASHBURN, VA 20147


PROJECT TEAM:  
ARCHITECT:  
ENVIRONETICS GROUP ARCHITECTS  
180 SYLVAN AVE.  
ENGLEWOOD CLIFFS, NJ 07632  
MEP ENGINEER  
GUTH DECONZO CONSULTING  
ENGINEERS, PC  
520 8TH AVENUE, SUITE 2201  
NEW YORK, NY 10001




CONCOURSE ELEVATION  
1/2" = 1'-0" 1




STOREFRONT ELEVATION  
1/4" = 1'-0" 2




INTERIOR ELEVATION - BACK WALL  
1/4" = 1'-0" 3



INTERIOR ELEVATION - BAR SEATING  
1/4" = 1'-0" 4



INTERIOR ELEVATION - BAR COUNTER  
1/4" = 1'-0" 5



INTERIOR ELEVATION - SIDE WALL  
1/4" = 1'-0" 6

**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA


| REV                 | DATE              | DESCRIPTION |
|---------------------|-------------------|-------------|
| DESIGN DELIVERABLE: | ISSUED FOR PERMIT |             |
| ISSUE DATE:         | 08/16/2024        |             |

PROJECT NUMBER: 24017G  
DRAWN BY: MK  
CHECKED BY: DC  
Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE:  
**ELEVATIONS**

SHEET NUMBER:  
**A-200**

NOTE: FINAL SHOP DRAWINGS TO BE PROVIDED FOR ALL SIGNAGE FOR FINAL APPROVAL BY ARCHITECT PRIOR TO ORDER, FABRICATION, OR INSTALLATION.



CUSTOM WALL COVERING. REFER TO FINISH SCHEDULE FOR ADDITIONAL INFORMATION.

WC-1

PC-2



WP-1

**ENV**  
ARCHITECTURE + DESIGN  
180 SYLVAN AVENUE, SUITE 3  
ENGLEWOOD CLIFFS, NJ 07632  
TEL 201 | 894 | 1000  
ENV-team.com


ENVIRONETICS GROUP ARCHITECTS, P.C.  
CLIENT:  
**SSP AMERICA**  
20408 BASHAN DRIVE  
SUITE 300  
ASHBURN, VA 20147

PROJECT TEAM:  
ARCHITECT:  
ENVIRONETICS GROUP ARCHITECTS  
180 SYLVAN AVE.  
ENGLEWOOD CLIFFS, NJ 07632  
MEP ENGINEER  
GUTH DECONZO CONSULTING  
ENGINEERS, PC  
520 8TH AVENUE, SUITE 2201  
NEW YORK, NY 10001


WALL COVERING ELEVATION  
3/4" = 1'-0"




STOREFRONT SIGNAGE ELEVATION  
3/4" = 1'-0"




EMBLEM SIGNAGE ELEVATION  
3/4" = 1'-0"




MOVABLE PLANTER SIGNAGE ELEVATION  
3/4" = 1'-0"




STOREFRONT SIGNAGE SECTION  
3" = 1'-0"




EMBLEM SIGNAGE SECTION  
3" = 1'-0"



MOVABLE PLANTER SIGNAGE SECTION  
3" = 1'-0"



INTERIOR LOGO SIGNAGE ELEVATION  
3/4" = 1'-0"



INTERIOR LOGO SIGNAGE SECTION  
3" = 1'-0"

**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA

| REV                 | DATE              | DESCRIPTION |
|---------------------|-------------------|-------------|
| DESIGN DELIVERABLE: | ISSUED FOR PERMIT |             |
| ISSUE DATE:         | 08/16/2024        |             |

PROJECT NUMBER: 24017G  
DRAWN BY: JP  
CHECKED BY: DC


Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE:  
**SIGNAGE DETAILS**

SHEET NUMBER:  
**A-201**

**PLASTIC PIPE THROUGH CONCRETE FLOOR/WALL OR BLOCK WALL**

**System No. C-AJ-2109**  
F RATING = 3-HR.  
T RATING = 0, 2 & 3 HR. (See Item 2)



- Floor or Wall Assembly** - Min 4-1/2 in. thick reinforced lightweight or normal weight (100-150 pcf) concrete. Wall may also be constructed of any UL Classified Concrete Blocks\*. Max diam of opening is 7 in. See Concrete Blocks (CAZT) category in the Fire Resistance Directory for names of manufacturers.
- Through Penetrants** - One nonmetallic pipe or tubing to be installed either concentrically or eccentrically within the firestop system. The annular space between pipe and periphery of opening shall be min 0 in. (point contact) to max 1/2 in. Pipe to be rigidly supported on both sides of floor or wall assembly. The T Ratings are dependent on the size and/or type of pipe as shown in the table below. The following types and sizes of nonmetallic pipes may be used:
  - A. Polyvinyl Chloride (PVC) Pipe - Nom 6 in. diam (or smaller) Schedule 40 solidcore or cellular cor PVC pipe for use in closed (process or supply) or vented (drain, waste or vent) piping system.
  - B. Chlorinated Polyvinyl Chloride (CPVC) Pipe - Nom 6 in. diam (or smaller) SDR17 CPVC pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems.
  - C. Acrylonitrile Butadiene Styrene Pipe - Nom 6 in. diam (or smaller) Schedule 40 solid-core or cellular core ABS pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems.
  - D. Flame Retardant Polypropylene (CPVC) Pipe - Nom 6 in. diam (or smaller) Schedule 40 FRPP pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems.

| Pipe Type  | Nom Pipe Diam. in. | T Rating, hr |
|------------|--------------------|--------------|
| PVC, CPVC  |                    | 2            |
| ABS, FRPP  | 1-1/2, 2, 3        |              |
| PVC, CPVC  | 4                  | 3            |
| ABS, FRPP  | 6                  | 3            |
| PVC, CPVC  | 6                  | 0            |
| ABS+, FRPP | 6                  |              |
| ABS++      | 6                  |              |

+ - indicates solid core ABS only  
++ - indicates cellular core ABS only

- Fill, Void or Cavity Material\*** - Sealant - Min 1/2 in. thickness of fill material applied within the annulus, flush with bottom surface of floor or with both surfaces of wall.


- Firestop Device\*** - Firestop Collar - Firestop collar shall be installed in accordance with the accompanying installation instructions. Collar to be installed and latched around the pipe and secured to underside of floor or both sides of wall using the anchor hooks provided with the collar. (Minimum 2 anchor hooks for 1-1/2 and 2 in. diam pipes, 3 anchor hooks for 3 and 4 in. diam pipes, and 6 anchor hooks for 6 in. diam pipes). The anchor hooks are to be secured with 1/4 in. diam by min 1-1/2 in. long steel expansion bolts, or equivalent, in conjunction with steel nuts and min 3/4 in. diam steel washers with one anchor bolt in each anchor hook.

HILTI, Inc. - CP 643 50/1.5", CP 643 63/2", CP 643 90/3", CP 643 110/4" OR CP 642 160/6" Firestop Collar

\*Bearing the UL Classification Marking

**BLANK OPENING IN CONCRETE FLOOR/WALL OR BLOCK WALL**

**System No. C-AJ-0058**  
F RATING = 3-HR.  
T RATING = 1-HR.



- Floor or Wall Assembly** - Min 4-1/2 in. thick reinforced lightweight or normal weight (100-150 pcf) concrete. Wall may also be constructed of any UL Classified Concrete Blocks\*. Max diam of opening is 4 in. See Concrete Blocks (CAZT) category in the Fire Resistance Directory for names of manufacturers.
- Firestop System** - The firestop system shall consist of the following:
  - A. **Packing or Forming Materials** - One of the following packing or forming materials may be used:
    - A1. Foam backer rod tightly packed into the opening as a permanent form. Packing material to be recessed from the top surface of floor or both surfaces of wall as required to accommodate the required thickness of putty.
    - A2. Mineral wool batt insulation, min 4 pcf, tightly packed into the opening as a permanent form. Packing material to be recessed from the top surface of floor or both surfaces of wall as required to accommodate the required thickness of putty.
  - B. **Fill, Void or Cavity Material\*** - Putty - Min 3/4 in. thickness of putty applied within the annulus, flush with top surface of floor or with both surfaces of wall.


- Forming materials\*** - Forming material to be foamed into the opening as a permanent form. Forming material to be recessed from the top surface of floor or both surfaces of wall as required to accommodate the required thickness of putty.

HILTI, Inc. - CF128 Foam Sealant  
B. **Fill, Void or Cavity Material\*** - Putty - Min 3/4 in. thickness of putty applied within the annulus, flush with top surface of floor or with both surfaces of wall.

HILTI, Inc. - CP 618 Firestop Putty Slick  
\*Bearing the UL Classification Marking

**CABLE TRAYS THROUGH CONCRETE FLOOR/WALL OR BLOCK WALL**

**System No. C-AJ-4017**  
F RATING = 3-HR.  
T RATING = 0-HR.



- Floor or Wall Assembly** - Min 2-1/2 in. thick reinforced lightweight or normal weight (100-150 pcf) concrete. Wall may also be constructed of any UL Classified Concrete Blocks\*. Max area of opening is 1024 sq in. with max dimension of 32 in. See Concrete Blocks (CAZT) category in the Fire Resistance Directory for names of manufacturers.
- Cable Tray\*** - The following types of cable trays may be used:
  - A. Max 24 in. wide by max 4 in. deep open ladder cable tray with channel-shaped side rails formed of min 0.050 in. thick steel with A-shaped rungs spaced 9 in. OC.
  - B. Max 24 in. wide by max 4-3/16 in. deep open ladder cable tray formed of min 0.097 in. aluminum with 7/8 in. wide by 1 in. deep rungs spaced 9 in. OC.
- A max of three cable trays to be installed in the opening. Of the three cable trays only one may be aluminum. The annular space between the cable trays shall be a min 5-1/4 in. Cable tray to be rigidly supported on both sides of floor or wall assembly.
- Cables** - Aggregate cross-sectional area of cables in cable tray shall be max 30 percent of the cross-sectional area of steel cable tray and max 20 percent of the cross-sectional area of aluminum cable tray, based on a max 3 in. cable loading depth within the cable tray. Any combination of the following types and sizes of copper conductor cables may be used:
  - A. Max 350 kcmil single-conductor power cables with polyvinyl chloride (PVC) insulation and jacket.
  - B. 7/C No. 12 AWG copper conductor cable with PVC insulation and jacket.
  - C. Max 100 pair No. 24 AWG cable with PVC insulation and jacket.


- Forms (Not Shown)** - Used as a form to prevent leakage of fill material during installation. Forms to be a rigid sheet material, cut to fit the contour of the penetrating item and positioned as required to accommodate the required thickness of fill materials. Forms may be removed after fill material has cured.

- Fill, Void or Cavity Material\*** - Trowelable Firestop Compound - Min 2-1/2 in. thickness of fill material applied within the annulus. Fill material is mixed at a rate of 2.5 parts dry mix to one part water by weight in accordance with the installation instructions supplied with fill material.

HILTI, Inc. - Type FS635  
\*Bearing the UL Classification Marking

**METAL PIPE THROUGH CONCRETE FLOOR/WALL OR BLOCK WALL**


**System No. C-AJ-1276**  
F RATING = 3-HR.  
T RATING = 0-HR.



- Floor or Wall Assembly** - Min 4-1/2 in. thick reinforced lightweight or normal weight (100-150 pcf) concrete. Wall may also be constructed of any UL Classified Concrete Blocks\*. Max diam of opening is 6 in. See Concrete Blocks (CAZT) category in the Fire Resistance Directory for names of manufacturers.
- Through Penetrants** - One metallic pipe, conduit or tubing to be centered within the firestop system. Pipe, conduit or tubing to be rigidly supported on both sides of floor or wall assembly. The following types and sizes of metallic pipes, conduits or tubing may be used:
  - A. Steel Pipe - Nom 4 in. diam (or smaller) Schedule 10 (or heavier) steel pipe. A nom annular space of 3/4 in. is required within the firestop system.
  - B. Conduit - Nom 4 in. diam (or smaller) steel electrical metallic tubing or steel conduit. A nom annular space of 3/4 in. is required within the firestop system.
- Firestop System** - The firestop system shall consist of the following:
  - A. **Packing or Forming Materials** - Optional - One of the following packing or forming materials may be used:
    - A1. Foam backer rod tightly packed into the opening as a permanent form. Packing material to be recessed from the top surface of floor or both surfaces of wall as required to accommodate the required thickness of putty.
    - A2. Mineral wool batt insulation, min 4 pcf, tightly packed into the opening as a permanent form. Packing material to be recessed from the top surface of floor or both surfaces of wall as required to accommodate the required thickness of putty.
    - A3. Forming materials\* - Forming material to be foamed into the opening as a permanent form. Forming material to be recessed from the top surface of floor or both surfaces of wall as required to accommodate the required thickness of putty.
  - B. **Fill, Void or Cavity Material\*** - Putty - Min 1 in. thickness of putty applied within the annulus, flush with top surface of floor or with both surfaces of wall.

**CABLE BUNDLE THROUGH 2-HR CONCRETE WALL ASSEMBLY**

**System No. W-J-3036**  
F Rating - 1 and 2 Hr  
T Rating - 0 Hr




- Wall Assembly** - Min 5 in. thick reinforced lightweight or normal weight (100-150 pcf) concrete. Wall may also be constructed of any UL Classified Concrete Blocks\*. Max diam of opening is 4 in. See Concrete Blocks (CAZT) category in the Fire Resistance Directory for names of manufacturers.
- Metallic Sleeve** - Nom 4 in. diam steel electrical metallic tubing (EMT) or Schedule 5 steel pipe friction fit into wall assembly and installed flush with wall surfaces.
- Cables** - Aggregate cross-sectional area of cables in opening to be max 25 percent of the cross-sectional area of the opening. The annular space between the cable bundle and the periphery of the opening to be min 1/8 in. to max 3/4 in. Cables to be rigidly supported on both sides of the wall assembly. Any combination of the following types and sizes of cables may be used:
  - A. 6 pair - No. 24 AWG telephone cable with polyvinyl chloride (PVC) insulation and PVC jacket.
  - B. 24 fiber optic cable with polyvinyl chloride (PVC) outer and subunit jacket.
  - C. Type RGU/59 coaxial cable with polyethylene (PE) insulation and polyvinyl (PVC) jacket.
  - D. The 2/C No. 10 AWG cable with ground with polyvinyl (PVC) insulation and jacket.
  - E. 3/C No. 12 AWG cable with polyvinyl chloride (PVC) insulation in a nominal 1/2 in. flexible metal conduit.
- Fill, Void or Cavity Material\*** - Putty - Min 5/8 in. thickness of fill material applied within annulus flush with both surfaces of wall. Fill material to be forced into interstices of cable bundle to the max extent possible on both surfaces of wall. Additional fill material to be installed such that a min 1/4 in. crown is formed around the cable bundle and lapped over the steel sleeve. HILTI, Inc. - CP618 Firestop Putty Slick  
\*Bearing the UL Classification Marking

**GLASS PIPE THROUGH CONCRETE FLOOR/WALL OR BLOCK WALL**

**System No. C-AJ-2118**  
F RATING = 3-HR.  
T RATING = 0-HR.

L Rating At Ambient - Less Than 1 CFM/sq ft  
L Rating At 400 F - 4 CFM/sq ft




- Floor or Wall Assembly** - Min 4-1/2 in. thick reinforced lightweight or normal weight (100-150 pcf) concrete floor or min 5 in. thick reinforced lightweight or normal weight concrete wall. Wall may also be constructed of any UL Classified Concrete Blocks\*. Max diam of opening is 10 in. See Concrete Blocks (CAZT) category in the Fire Resistance Directory for names of manufacturers.
- Metallic Sleeve (Optional)** - Nom 10 in. diam (or smaller) Schedule 10 (or heavier) steel pipe cast or grouted into floor or wall assembly, flush with floor or wall surfaces.
- Through Penetrants\*** - Glass Pipe - Nom 6 in. diam (or smaller) glass pipe used for use in closed (process or supply) or vented (drain, waste or vent) piping systems. One pipe to be installed either concentrically or eccentrically within the firestop system. The annular space shall be min 1/4 in. to max 3-1/2 in. Pipe couplings to be located min 12 in. from floor or wall surfaces. Pipe to be rigidly supported on both sides of floor or wall assembly.
- Firestop System** - The firestop system shall consist of the following:
  - A. **Packing Material** - Min 4.0 pcf mineral wool batt insulation installed in through opening as a permanent form. Pieces of batt cut to min width of 3-1/2 in. and installed edge-first into opening such that batt sections are tightly-compressed in thickness and such that the compressed batt sections are recessed from top surface of floor or from both surfaces of wall as required to accommodate the required thickness of fill material.
  - B. **Fill, Void or Cavity Material\*** - Sealant - Min 3/4 in. thickness of fill material applied within the annulus, flush with top surface of floor or with both surfaces of wall.

HILTI, Inc. - FS605 or FS-ONE Sealant.  
(Note: L ratings apply only when FS-ONE Sealant is used).  
\*Bearing the UL Classification Marking


**CABLE TRAY THROUGH CONCRETE FLOOR/WALL OR BLOCK WALL**

**System No. C-AJ-4035**  
F RATING = 3-HR.  
T RATING = 0-HR.



- Floor or Wall Assembly** - Min 4-1/2 in. thick reinforced lightweight or normal weight (100-150 pcf) concrete. Wall may also be constructed of any UL Classified Concrete Blocks\*. Max area of opening is 270 sq in. with max dimension of 30 in. See Concrete Blocks (CAZT) category in the Fire Resistance Directory for names of manufacturers.
- Cable Tray\*** - Max 24 in. wide by max 4 in. deep open-ladder cable tray with channel-shaped side rails formed of 0.10 in. thick aluminum or 0.060 in. thick galv steel and with 1-1/2 in. wide by 1 in. channel shape rungs spaced 9 in. OC. The annular space between the cable tray and the periphery of the opening shall be min 1 in. to max 4 in. Cable tray to be rigidly supported on both sides of floor or wall assembly.
- Cables** - Aggregate cross-sectional area of cables in cable tray to be max 40 percent of the cross-sectional area of the cable tray. Any combination of the following types and sizes of copper conductor or fiber optic cables may be used:
  - A. 1/C, 500 kcmil with thermoplastic insulation and PVC jacket.
  - B. 300 pair-No. 24 AWG cable with PVC insulation and jacket.
  - C. 24 fiber optic cable with PVC subunit and jacket.
  - D. Three 1/C No. 12 AWG wire, insulated with polyvinyl chloride, in a nominal 3/4 in. flexible metal conduit.
- Firestop System** - The firestop system shall consist of the following:
  - A. **Fill, Void or Cavity Material\*** - Fire blocks installed with the long dimension placed horizontally within the opening, flush with bottom of floor assemblies. Blocks to completely fill the entire width of opening of wall assemblies.
  - B. **Fill, Void or Cavity Material\*** - Fill material to be forced into interstices of cables and between cables and cable trays to max extent possible on both surfaces of the penetration.

HILTI, Inc. - FS-Fire Block  
HILTI, Inc. - FS-ONE Sealant  
\*Bearing the UL Classification Marking




| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

|                     |                   |
|---------------------|-------------------|
| DESIGN DELIVERABLE: | ISSUED FOR PERMIT |
| ISSUE DATE:         | 08/16/2024        |

|                 |            |
|-----------------|------------|
| PROJECT NUMBER: | 24017G     |
| DRAWN BY:       | RW, JR, PQ |
| CHECKED BY:     | DJB        |

MULTIPLE ITEMS THROUGH CONCRETE FLOOR/WALL OR BLOCK WALL

System No. C-AJ-8056  
F RATING = 3-HR.  
T RATING = 0 HR.  
L Rating At Ambient - 5 CFM/sq ft  
L Rating At 400 F - 2 CFM/sq ft




- 1. Floor or Wall Assembly - Min 4-1/2 in. thick reinforced lightweight or normal weight (100-150 pcf) concrete. Wall may also be constructed of any UL Classified Concrete Blocks\*. Max area of opening is 1296 sq in. with max dimension of 36 in.
- 2. Cable Tray\* - Max 18 in. wide by max 6 in deep open-ladder cable tray with channel-shaped side rails formed of 0.060 in. thick aluminum or steel and with 1-1/2 in. wide by 1 in. channel shape rungs spaced 9 in.
- 3. Cables - Aggregate cross-sectional area of cables in cable tray to be max30 percent of the cross-sectional area of the cable tray based on a max 3 in. cable loading depth within the cable tray.
- 4. Through Penetrants - One or more pipe, conduit or tube to be installed within the opening.
- 5. Pipe Covering\* - Nom 1-1/2 in. thick hollow cylindrical heavy density (min 3.5 pcf) glass fiber units jacketed on the outside with an all servicejacket.
- 6. Cables - Max 2 in. diam tight bundle of cables centered in opening and rigidly supported on both surfaces of floor and wall.
- 7. Firestop System - The firestop system shall consist of the following: A. Fill, Void or Cavity Material\* - Fire blocks installed with long dimension passed through the opening extending min 1-1/2 in. from each surface.

\*Bearing the UL Classification Marking

TOP OF WALL JOINT: 2-HR CONCRETE WALL OR BLOCK WALL ASSEMBLY

System No. HW-D-0080  
Assembly Rating - 2 Hr  
Nominal Joint Width - 3/4 in.  
Class II Movement Capabilities - 33% Compression or Extension




- 1. Floor Assembly - The fire-rated fluted steel floor unit/concrete floor assembly shall be constructed of the materials and in the manner described in the individual Floor-Ceiling Design in the UL Fire Resistance Directory and shall include the following construction features: A. Steel Floor and Form Units\* - Max 3 in. deep galv steel fluted floor units.
- 2. Wall Assembly - Min 5 in. thick reinforced lightweight or normal weight (100-150 pcf) structural concrete.
- 3. Joint System - Max separation between bottom of floor and top of wall is 3/4 in.

\*Bearing the UL Classification Marking


CAST IRON FLOOR SINK THROUGH CONCRETE WALL ASSEMBLY

UL/CUL SYSTEM NO. F-A-1135



F-RATING = 2-HR.  
T-RATING = 2 HR.  
L-RATING AT AMBIENT - LESS THEN 1 CFM / SQ FT  
L-RATING AT 400 DEGREES FAHRENHEIT = 4 CFM / SQ FT

- 1. LIGHTWEIGHT OR NORMAL WEIGHT CONCREE FLOOR ASSEMBLY ( MINIMUM 2-1/2" THICK) (2HR. FIRE-RATING)
- 2. MAXIMUM 12"x12"x10" DEEP CAST IRON FLOOR SINK CAST OR GROUTED INTO FLOOR. SINK FLANGES TO BEAR ON TOP PLANE OF FLOOR. CAST IRON FLOOR GRATING TO BE INSTALLED ON TOP OF SINK.METAL DOME STRAINER MAY BE USED IN SINK DRAIN.
- 3. MAXIMUM 4" NOMINAL DIAMETER CAST IRON PIPE SECURED TO OUTLET OF FLOOR SINK WITH NO-HUB COUPLING PIPE TO BE REGIFLY SUPPORTED BENEATH FLOOR AWAY FROM FLOOR SINK WITH SUITABLE HANGERS.
- 4. CORRUGATED STAINLESS STEEL "NO-HUB" CONNECTOR.
- 5. MINIMUM 1/2" BEAD HILI FS-ONE MAX OR FS-ONE INTUMESCENT FIRESTOP SEALANT APPLIED AROUND PERIPHERY OF FLOOR SINK AT FLOOR INTERFACE.
- 6. TWO LAYERS (NOMINAL 1-1/2" THICK) FACED OR UNFACED FIREMASTER FAST WRAP XL, FIREMASTER FASTRAP+, OR PYROSCAT DUCTWRAP XL ( MANUFACTURED BY THERMAL CERAMICS) TIGHTLY WRAPPED AROUND SINK AND DRAIN PIPE. BOTH LAYERS TO EXTEND MINIMUM 24" BEYOND THE BOTTOM SURFACE OF FLOOR AND HELD IN POSTION USING 16 GA. STEEL WITE TIES SPACED MAXIMUM 8" ON CENTER AND MAXIMUM 6" BELOW FLOOR AND HELD IN POSITION USING 16 GA. STEEL TIE WIRES SPACED MAXIMUM 11" FROM ENDS OF LAYER.



| REV                 | DATE              | DESCRIPTION |
|---------------------|-------------------|-------------|
| DESIGN DELIVERABLE: | ISSUED FOR PERMIT |             |
| ISSUE DATE:         | 08/16/2024        |             |

PROJECT NUMBER: 24017G  
DRAWN BY: RW, JR, PQ  
CHECKED BY: DJB


Copyright (c) by Environetcs, Inc. All Rights Reserved.

SHEET TITLE:  
**TYPICAL FIRESTOPPING DETAILS**


SHEET NUMBER:  
**A-452**

**PLASTIC PIPE THROUGH CONCRETE FLOOR WITH METAL DECK**

System No. F-A-2025  
F RATING = 2-HR.  
T RATING = 2 HR.



BOTTOM VIEW



SECTION A-A

SECTION B-B

- 1. Floor Assembly** - The fire-rated unprotected concrete and steel floor assembly shall be constructed of the materials and in the manner specified in the individual D900 Series designs in the UL Fire Resistance Directory and as summarized below:
  - A. Normal Weight Concrete - Normal weight concrete with carbonate siliceous aggregate, 145 to 155 pcf unit weight, min 3000 psi compressive strength.
  - B. Welded Wire Fabric - 6x6-W1.4xW1.4.
  - C. Steel Floor and Form Units\* - Composite or noncomposite 3 in. deep fluted galv units as specified in the individual Floor-Ceiling design. Max diam of opening core-drilled through floor assembly is 7 in.
- 2. Through Penetrants** - One nonmetallic pipe to be installed either concentrically or eccentrically within the firestop system. The annular space between pipe and periphery of opening shall be min 0 in. (point contact) to max 1/2 in. Pipe to be rigidly supported on both sides of floor assembly. The following types and sizes of nonmetallic pipes may be used:
  - A. Polyvinyl Chloride (PVC) Pipe - Nom 6 in. diam (or smaller) Schedule 40 solid core of cellular core PVC pipe for use in closed (process or supply) or vented (drain, waste or vent) piping system.
  - B. Chlorinated Polyvinyl Chloride (CPVC) Pipe - Nom 6 in. diam (or smaller) SDR17 CPVC pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems.
  - C. Acrylonitrile Butadiene Styrene (ABS) Pipe - Nom 6 in. diam (or smaller) Schedule 40 solid core or cellular core ABS pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems.
  - D. Flame Retardant Polypropylene (FRPP) Pipe - Nom 6 in. diam (or smaller) Schedule 40 FRPP pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems.
- 3. Metal Plate Enclosure** - Min 18 ga. steel. Width of plate to be min 12 in. Length of plate (transverse to steel floor unit direction) to extend to steel floor unit valley beyond each side of core-drilled hole with a min lap of 1-1/2 in. on the floor unit valley at each end. Both ends of plate perpendicular to floor unit valleys to be cut to permit the ends to be bent upwards 90 F to follow the contour of the floor unit, enclosing the packing material (item 4) within the areas of the flutes. The contoured plate ends shall be such that the gap between the floor unit and the plate ends is no greater than 1/4 in. Circular cutout in plate to tightly follow circumference of nonmetallic pipe with side edges of plate at least 3 in. from circular cutout on all sides. Silt made in plate to permit installation around the nonmetallic pipe to be located at end of plate beneath floor unit valley nearest to the circular cutout. Plate secured to valleys of floor unit using min 1/4 in. diam by 1-3/4 in. long steel expansion bolts, or equivalent, in conjunction with min 3/4 in. diam steel washers. Fasteners to be located approx 1 in. from edges of plate at each corner, at each plate/valley intersection and at both sides of slit made to permit installation around nonmetallic pipe. Spacing of fasteners not to exceed 10 in. OC.

- 4. Packing Material** - Mineral wool batt insulation having min density of 4 pcf, firmly packed into flutes of steel floor units above metal plate enclosure (Item 3) to completely fill cavities.
- 5. Fill, Void or Cavity Material\* - Sealant** - Nom 1/2 in. bead of fill material applied around the perimeter of the metal plate enclosure at the interface of the enclosure and steel deck.  
HILTI, Inc. - FS601, FS611A or FS-ONE Sealant
- 6. Firestop Device\* - Firestop Collar** - Firestop collar shall be installed in accordance with the accompanying installation instructions. Collar to be installed and latched around the pipe and secured to the valley of the steel deck and to the metal plate enclosure using the anchor hooks provided with the collar. (Minimum 2 anchor hooks for 1-1/2 and 2 in. diam pipes, 3 anchor hooks for 3 and 4 in. diam pipes, and 6 anchor hooks for 6 in. diam pipes). Where the anchor hooks are beneath the valley of the steel floor unit, the anchor tabs are to be secured with 1/4 in. diam by min 1-1/2 in. long steel expansion bolts, or equivalent, in conjunction with steel nuts and min 3/4 in. diam steel washers with one anchor bolt in each anchor hook. Where the anchor hooks are beneath the crest of the steel deck, the anchor hooks are to be secured to the metal enclosure with No. 10 by min 1/2 in. long self-drilling, self-tapping steel screws and washers.  
HILTI, Inc. - CP 643 50/1.5", CP 643 63/2", CP 643 90/3", CP 643 110/4", or CP 642 160/6" Firestop Collar

\*Bearing the UL Classification Marking


**TOP OF WALL JOINT: 1-HR OR 2-HR GYPSUM WALL ASSEMBLY**

System No. HW-D-0049

Assembly Ratings - 1 and 2 Hr (See Items 2 and 3B)

Nominal Joint Width - 1 In.

Class II Movement Capabilities - 50% Compression or Extension



SECTION A-A

- 1. Floor Assembly** - The fire-rated fluted steel deck/concrete floor assembly shall be constructed of the materials and in the manner described in the individual Floor-Ceiling Design in the UL Fire Resistance Directory and shall include the following construction features:
  - A. Steel Floor and Form Units\* - Max 3 in. deep galv fluted units.
  - B. Concrete - Min 2-1/2 in. thick reinforced concrete, as measured from the top plane of the floor units.
- 2. Wall Assembly** - The 1 or 2 hr fire-rated gypsum wallboard/steel stud assembly shall be constructed of the materials and in the manner described in the individual U400-Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following construction features:
  - A. Steel Floor and Ceiling Runners - Floor and ceiling runners of wall assembly shall consist of min 25 gauge galv steel channels sized to accommodate steel studs (Item 2B). Ceiling runner to be provided with 2 in. flanges. Ceiling runner secured to valleys of steel floor units (Item 1A) with steel fasteners spaced max 12 in. OC.
  - B. Studs - Steel studs to be min 2-1/2 in. wide. Studs cut 5/8 to 3/4 in. less in length than assembly height with bottom nesting in and resting on floor runner and with top nesting in ceiling runner without attachment. Stud spacing not to exceed 24 in. OC.
  - C. Wallboard, Gypsum\* - Wallboard sheets installed to a min total thickness of 5/8 or 1-1/4 in. on each side of wall, for 1 and 2 hr. rated assemblies, respectively. Wall to be constructed as specified in the individual Wall and Partition Design in the UL Fire Resistance Directory, except that a nom 1 in. gap shall be maintained between the top of the wallboard and the bottom of the steel floor units and the top row of screws shall be installed into the studs 3-1/2 to 4 in. below the lower surface of the floor.
- 3. Joint System** - Max separation between bottom of floor and top of wall at time of installation of joint system is 1 in. The joint system is designed to accommodate a max 50 percent compression or extension from its installed width. The joint system consists of forming material and a fill material, as follows:
  - A. Forming Material\* - Nom 5/8 to 1-1/4 in. wide by 1-1/2 in. high strips of min 8 pcf mineral wool batt insulation are to be cut to fill the 1 in. gap between the top of the wallboard and bottom of the steel floor units. The strips of mineral wool are compressed and firmly packed, cut edge first, into the gap between the top of the wallboard and bottom of the steel floor units on both sides of the wall.  
Rock Wool Mfg. Co. - Delta-8
  - B. Fill, Void or Cavity Material\* - Min 1/8 in. wet thickness of fill material sprayed or troweled on each side of the wall to completely cover mineral wool forming material and to overlap a min of 1/2 in. onto wallboard and steel deck on both sides of wall.  
HILTI, Inc. - CP672 Firestop Spray


\*Bearing the UL Classification Marking

**SPINE CABLE TRAY THROUGH 2-HR CONCRETE WALL OR CONCRETE BLOCK WALL**

System No. W-J-4016

F Rating - 2 Hr

T Rating - 0 Hr




SECTION A-A

- 1. Wall Assembly** - Min 5 in. thick reinforced lightweight or normal weight (100-150 pcf) concrete. Wall may also be constructed of any UL Classified Concrete Blocks\*. Max area of opening is 216 in. with a max dimension of 24 in.  
See Concrete Blocks (CAZT) category in the Fire Resistance Directory for names of manufacturers.
- 2. Cable Tray\*** - Max 18 in. wide by 6 in. deep "spine" cable tray. The 1-1/2 in. wide by 2-3/4 in. deep tubular spine formed of 0.121 in. thick aluminum. The 6 in. deep "U" shaped rungs space 6 in. OC formed from 1/2 in. by 1/2 in. extruded aluminum tube. One cable tray to be installed in the opening. The max annular space between the periphery of the opening shall be min 1 in. to 2-5/8 in. max. Cable tray to be rigidly supported on both sides of wall assembly.
- 3. Cables** - Aggregate cross-sectional area of cables in cable tray to be max 22 percent of the cross-sectional area of the cable tray based on a max 6 in. cable loading depth within the cable tray. Any combination of the following types and sizes of cables may be used:
  - A. 6 pair - No. 24 AWG telephone cable with polyvinyl chloride (PVC) insulation and PVC jacket.
  - B. 24 fiber optic cable with polyvinyl chloride (PVC) outer and subunit jacket.
  - C. 3 pair No. 24 AWG CMP computer cable with polyvinyl chloride (PVC) insulation and jacket.
  - D. Type RG/U59 coaxial cable with polyethylene (PE) insulation and polyvinyl chloride (PVC) jacket.
  - E. The 2/C No. 10 AWG cable with ground with polyvinyl chloride (PVC) insulation and jacket.
  - F. 3/C No. 12 AWG MC cable with polyvinyl chloride (PVC) insulation in a nominal 1/2 in. flexible metal conduit.
- 4. Electrical Nonmetallic Tubing (ENT)** - One nom 2 in. diam (or smaller) corrugated wall ENT constructed of polyvinyl chloride.  
See Electrical Nonmetallic Tubing (EKHU) category in the Electrical Construction Materials Directory for names of manufacturers.
- 5. Firestop System** - The firestop system shall consist of the following:
  - A. Fill, Void or Cavity Material\* - Fire blocks - Fire blocks installed with min. 5 in. dimension passing through the opening. Blocks to completely fill the entire opening.  
HILTI, Inc. - FS-Fire Block
  - B. Fill, Void or Cavity Material\* - Sealant - Fill material to be forced into interstices of cables, between cables and cable tray and in obvious openings between blocks and between blocks and the periphery of the opening to the max extent possible on both surfaces of wall.  
HILTI, Inc. - FS-ONE Sealant

\*Bearing the UL Classification Marking

\*Bearing the UL Listing Marking



**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA



| REV                 | DATE              | DESCRIPTION |
|---------------------|-------------------|-------------|
| DESIGN DELIVERABLE: | ISSUED FOR PERMIT |             |
| ISSUE DATE:         | 08/16/2024        |             |

|                 |            |
|-----------------|------------|
| PROJECT NUMBER: | 24017G     |
| DRAWN BY:       | RW, JR, PQ |
| CHECKED BY:     | DJB        |

Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE:  
**TYPICAL FIRESTOPPING DETAILS**

SHEET NUMBER:  
**A-453**



**PLASTIC PIPE THROUGH 1-HR OR 2-HR GYPSUM WALL ASSEMBLY**  
 System No. W-L-2078  
 F Ratings - 1 & 2 Hr (See Item 1)  
 T Ratings - 1 & 2 Hr (see Item 1)

1. Wall Assembly - The fire-rated gypsum wallboard/stud wall assembly shall be constructed of the materials and in the manner specified in the individual U300 or U400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the construction features noted below. The hourly F Rating and T Rating of the firestop system is equal to the hourly fire rating of the wall assembly in which it is installed:

A. Studs - Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. lumber spaced 16 in. OC. Steel studs to be min 2-1/2 in. wide and spaced max 24 in. OC.

B. Wallboard, Gypsum\* - Nom 5/8 in. thick gypsum wallboard, as specified in the individual Wall and Partition Design. Max diam of opening is 7 in.

2. Through-Penetrants - One nonmetallic pipe, conduit or tubing to be installed within the firestop system. The annular space between pipe and periphery of opening shall be min 0 in. (point contact) to max 1/2 in. Pipe or conduit to be rigidly supported on both sides of the wall assembly. The following types and sizes of nonmetallic pipes may be used:

A. Polyvinyl Chloride (PVC) Pipe - Nom 6 in. diam (or smaller) Schedule 40 solid-core or cellular core PVC pipe for use in closed (process or supply) or vented (drain, waste or vent) piping system.

B. Chlorinated Polyvinyl Chloride (CPVC) Pipe - Nom 6 in. diam (or smaller) SDR17 CPVC pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems.


C. Acrylonitrile Butadiene Styrene (ABS) Pipe - Nom 6 in. diam (or smaller) Schedule 40 solid-core or cellular core ABS pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems

D. Flame Retardant Polypropylene (FRPP) Pipe - Nom 6 in. diam (or smaller) Schedule 40 FRPP pipe for use in closed (process or supply) or vented (drain, waste or vent) piping system.

3. Firestop Device\* - Firestop Collar - Firestop collar shall be installed in accordance with the accompanying installation instructions. Collar to be installed and latched around the pipe and secured to both sides of the wall using the anchor hooks provided with the collar. (Minimum 2 anchor hooks for 1-1/2 and 2 in. diam pipes, 3 anchor hooks for 3 and 4 in. diam pipes, and 6 anchor hooks for 6 in. diam pipes). The anchor hooks are to be secured to the surface of wall with 3/16 2-1/2 in. long toggle bolts along with washers.

HILTI, Inc. CP 643 50/1.5", CP 643 63/2", CP 643 90/3", CP 643 110/4" or CP 642 160/6" Firestop Collar

\*Bearing the UL Classification Marking



**CABLE BUNDLE THROUGH 1-HR OR 2-HR GYPSUM WALL ASSEMBLY**  
 System No. W-L-3111  
 F Ratings - 1 and 2 Hr  
 T Rating - 0 Hr

1. Wall Assembly - The fire-rated gypsum wallboard/stud wall assembly shall be constructed of the materials and in the manner specified in the individual U300 or U400 Series Wall and Partition Designs in the Fire Resistance Directory and shall include the following construction features:

A. Studs - Wall framing shall consist of either wood studs or channel shaped steel studs. Wood studs to consist of 2 by 4 in. lumber spaced 16 in. OC. Steel studs to be min 2-1/2 in. wide, fabricated from min 25 MSG galvanized steel, spaced max 24 in. OC.

B. Wallboard, Gypsum\* - 5/8 in. 4 ft wide with square or tapered edges. The gypsum wallboard type, number of layers and sheet orientation shall be as specified in the individual U300 or U400 Series Designs in the UL Fire Resistance Directory. Max diam of opening is 4 in.

2. Metallic Sleeve - The nominal 4 in. diam steel electrical metallic tubing (EMT) or Schedule 5 steel pipe friction fit into wall assembly and installed flush with wall surfaces.

3. Cables - Aggregate cross-sectional area of cables to be max 25 percent of the cross-sectional area of the opening. The annular space between the cable bundle and the periphery of the opening to be min 1/8 in. to max 3/4 in. Cables to be rigidly supported on both sides of the wall assembly. Any combination of the following types and sizes of cables may be used:

A. 6 pair - No. 24 AWG telephone cable with polyvinyl chloride (PVC) insulation and PVC jacket.

B. 24 fiber optic cable with polyvinyl chloride (PVC) outer and subunit jacket.

C. Type RGU/59 coaxial cable with polyethylene (PE) insulation and polyvinyl (PVC) jacket.


D. The 2/C No. 10 AWG cable with ground with polyvinyl (PVC) insulation and jacket.

E. 3/C No. 12 AWG cable with polyvinyl chloride (PVC) insulation in a nominal 1/2 in. flexible metal conduit.

4. Fill, Void or Cavity Material\* - Min 5/8 in. thickness of fill material applied within annulus flush with both surfaces of wall. Fill material to be forced into interstices of cable bundle to the max extent possible on both surfaces of wall. Additional fill material to be installed such that a min 1/4 in. crown is formed around the cable bundle and lapped over the steel sleeve.

HILTI, Inc. - CP618 Firestop Putty Stick

\*Bearing the UL Classification Marking



**CABLE TRAY THROUGH 1-HR OR 2-HR GYPSUM WALL ASSEMBLY**  
 System No. W-L-4011  
 F Rating - 1 and 2 Hr (See Item 1)  
 T Rating - 0 Hr  
 L Rating At Ambient - 5 CFM/Sq Ft  
 L Rating At 400 F - 2 CFM/Sq Ft

1. Wall Assembly - The 1 or 2 hr fire-rated gypsum wallboard/stud wall assembly shall be constructed of the materials and in the manner described in the individual U300 or U400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following construction features:

A. Studs - Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. lumber spaced 16 in. OC. Steel studs to be min 2-1/2 in. wide and spaced max 24 in. OC. Additional framing member shall be installed in stud cavity containing through-penetrating item to form a rectangular box around penetrant.

B. Wallboard, Gypsum\* - 5/8 in. thick, 4 ft wide with square or tapered edges. The gypsum wallboard type, thickness, number of layers, fastener type and sheet orientation shall be as specified in the individual U300 or U400 Series Design in the UL Fire Resistance Directory. Max size of opening 9 in. by 30 in.

C. Cable Tray\* - Max 24 in. wide by max 4 in. deep open-ladder cable tray with channel-shaped side rails formed of 0.10 in. thick aluminum or 0.060 in. thick steel and with 1-1/2 in. wide by 1 in. channel shape rungs spaced 9 in. OC. The annular space between the cable tray and the periphery of the opening shall be min 1 in. to max 4 in. Cable tray to be rigidly supported on both sides of floor or wall assembly.

3. Cables - Aggregate cross-sectional area of cables in cable tray to be max 40 percent of the cross-sectional area of the cable tray. Any combination of the following types and sizes of copper conductor cables may be used:

A. 1/C, 500 kcmil with thermoplastic insulation and PVC jacket.

B. 300 pair - No. 24 AWG cable with PVC insulation and jacket.

C. Twenty-four fiberoptic cable with PVC subunit and jacket.

D. Max three 1/C, No. 12 AWG wire, insulated with polyvinyl chloride, in a nom 3/4 in. Flexible Metal Conduit+.

4. Firestop System - The firestop system shall consist of the following:

A. Fill, Void or Cavity Material\* - For walls 5 in. thick or less. Fire blocks centered within depth of opening with the long dimension placed horizontally. For walls greater than 5 in. thick, fire blocks installed with long dimension passed through the opening. In both cases, blocks to completely fill the entire volume of the opening in the wall assembly.


HILTI, Inc. - FS-Fire Block

B. Fill, Void or Cavity Material\* - Fill material to be forced into interstices of cables and between cables and cable trays to max extent possible on both surfaces of the penetration.

HILTI, Inc. - FS-ONE Sealant

+Bearing the UL Listing Mark

\*Bearing the UL Classification Marking



**INSULATED METAL PIPE THROUGH 1-HR OR 2-HR GYPSUM WALL ASSEMBLY**  
 System No. W-L-5028  
 F Ratings - 1 and 2 Hr (See Item 1)  
 T Ratings - 1/2 and 3/4 Hr

1. Wall Assembly - The 1 or 2 hr fire-rated gypsum wallboard/stud wall assembly shall be constructed of the materials and in the manner specified in the individual U300 or U400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following construction features:

A. Studs - Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. lumber spaced 16 in. OC. Steel studs to be min 2-1/2 in. wide and spaced max 24 in. OC.

B. Wallboard, Gypsum\* - 5/8 in. thick, 4 ft wide with square or tapered edges. The gypsum wallboard type, thickness, number of layers, fastener type and sheet orientation shall be as specified in the individual Wall and Partition Design. Max diam of opening is 7-1/2 in. The hourly F Rating of the firestop system is equal to the hourly fire rating of the wall assembly in which it is installed.

2. Through Penetrants - One metallic pipe, conduit or tubing to be centered within the firestop system. Pipe, conduit or tubing to be rigidly supported on both sides of wall assembly. The following types and sizes of metallic pipes, conduits or tubing may be used:

A. Steel Pipe - Nom 4 in. diam (or smaller) Schedule 40 (or heavier) steel pipe.

B. Conduit - Nom 4 in. diam (or smaller) electrical metallic tubing or steel conduit.

C. Copper Tubing - Nom 2 in. diam (or smaller) Type L (or heavier) copper tubing.

D. Copper Pipe - Nom 2 in. diam (or smaller) Regular (or heavier) copper pipe.

3. Tube Insulation - Plastics+ - Nom 3/4 in. thick acrylonitrile butadiene/polyvinyl chloride (AB/PVC) flexible foam furnished in the form of tubing. An annular space of min 0 in. (point contact) to max 1-1/2 in. is required within the firestop system.

See Plastics+ (QM/FZ2) category in the Recognized Component Directory for names of manufacturers. Any Recognized Component tube insulation material meeting the above specifications and having a UL 94 Flammability Classification of 94-5VA may be used.

The hour T Rating of the firestop system is dependent on the hourly fire rating of the wall assembly in which it is installed, the size and type of through penetrant and the pipe covering thickness, as shown in the table below:


| Wall Assembly Rating | Through Penetrant Type+ | Max Diam In. | T Rating Hr |
|----------------------|-------------------------|--------------|-------------|
| 1                    | A or B                  | 4            | 1/2         |
| 1                    | A, B, C or D            | 2            | 3/4         |
| 2                    | A or B                  | 4            | 1/2         |
| 2                    | A, B, C or D            | 2            | 3/4         |

+Indicates penetrant type as itemized in Item 2.

4. Fill, Void or Cavity Material\* - Sealant - Min 5/8 in. or 1-1/4 in. thickness of fill material applied within the annulus, flush with both surfaces of wall for 1 or 2 hr walls, respectively. At the point contact location between pipe covering and gypsum wallboard, a min 1/2 in. diam bead of fill material shall be applied at the pipe covering/gypsum wallboard interface on both surfaces of wall.

HILTI, Inc. - FS611A or FS-ONE Sealant

\*Bearing the UL Classification Marking



**FIRE-RATED JOINT THROUGH CONCRETE FLOOR ASSEMBLY**  
 System No. FW-D-1012  
 Assembly Rating - 2 Hr  
 Nominal Joint Width - 3-3/4"  
 Class II Movement Capabilities - 7% Compression or Extension

1. Wall Assembly - Min 4-1/2 in. thick reinforced lightweight or normal weight (100-150 pcf) structural concrete. Wall may also be constructed of any UL Classified Concrete Blocks\*.

2. Floor Assembly - Min 4-1/2 in. thick reinforced lightweight or normal weight (100-150 pcf) structural concrete.

3. Joint System - Max separation between edge of floor and face of wall (at time of installation of joint system) is 3-3/4 in. The joint system is designed to accommodate a max 7 percent in compression or extension from its installed width. The joint system shall consist of the following:

A. Packing Material - Min 4 pcf mineral wool batt insulation installed in joint opening as a permanent form. Pieces of batt cut to min width of 3 in. and installed edge-first into joint opening, parallel with joint direction, such that batt sections are compressed min 17 percent in thickness and that the compressed batt sections are recessed from top surface of the floor. A 1 in. thickness of packing material is placed horizontally over the installed lower layers and recessed from the top surface as required to accommodate the required thickness of fill material. Adjoining lengths of batt to be tightly-butted with butted seams spaced min 24 in. apart along the length of the joint.

B. Fill, Void or Cavity Material\* - Sealant - Min 1/2 in. thickness of fill material applied within the joint, flush with top surface of floor.

HILTI, Inc. - CP606 Flexible Firestop Sealant

\*Bearing the UL Classification Marking

1. Wall Assembly - Min 4-1/2 in. thick reinforced lightweight or normal weight (100-150 pcf) structural concrete. Wall may also be constructed of any UL Classified Concrete Blocks\*.

2. Floor Assembly - Min 4-1/2 in. thick reinforced lightweight or normal weight (100-150 pcf) structural concrete.

3. Joint System - Max separation between edge of floor and face of wall (at time of installation of joint system) is 3-3/4 in. The joint system is designed to accommodate a max 7 percent in compression or extension from its installed width. The joint system shall consist of the following:

A. Packing Material - Min 4 pcf mineral wool batt insulation installed in joint opening as a permanent form. Pieces of batt cut to min width of 3 in. and installed edge-first into joint opening, parallel with joint direction, such that batt sections are compressed min 17 percent in thickness and that the compressed batt sections are recessed from top surface of the floor. A 1 in. thickness of packing material is placed horizontally over the installed lower layers and recessed from the top surface as required to accommodate the required thickness of fill material. Adjoining lengths of batt to be tightly-butted with butted seams spaced min 24 in. apart along the length of the joint.

B. Fill, Void or Cavity Material\* - Sealant - Min 1/2 in. thickness of fill material applied within the joint, flush with top surface of floor.

HILTI, Inc. - CP606 Flexible Firestop Sealant

\*Bearing the UL Classification Marking

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: ISSUED FOR PERMIT  
 ISSUE DATE: 08/16/2024


PROJECT NUMBER: 24017G  
 DRAWN BY: RW, JR, PQ  
 CHECKED BY: DJB

Copyright (c) by Environetics, Inc. All Rights Reserved.


SHEET TITLE:  
**TYPICAL FIRESTOPPING DETAILS**

SHEET NUMBER:  
**A-454**


REVIT 2023




SUSPENDED CEILING BRACING  
1 1/2" = 1'-0" 1




PARTITION LATERAL BRACING AT DECK  
1/2" = 1'-0" 2




PARTITION LATERAL BRACING AT DECK  
1/2" = 1'-0" 3




A.C.T. GRID ATTACHMENT TO ADJ. WALL  
3" = 1'-0" 4




GYP. BD. ATTACHMENT TO ADJ. WALL  
3" = 1'-0" 5




FIXTURE ATTACHMENT DETAIL  
3" = 1'-0" 6




PIPE ATTACHMENT DETAIL  
3" = 1'-0" 7



DUCTWORK ATTACHMENT DETAIL  
3" = 1'-0" 8



SPRINKLER BRACING DETAIL  
3" = 1'-0" 9



EXPANSION ANCHOR DETAIL  
3" = 1'-0" 10

**A. GENERAL**  
 1. IT IS SOLELY THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE ERECTION PROCEDURE AND SEQUENCE AND TO INSURE THE SAFETY OF THE BUILDING AND ITS COMPONENT PARTS DURING CONSTRUCTION.  
 2. IT IS SOLELY THE CONTRACTOR'S RESPONSIBILITY TO FOLLOW ALL APPLICABLE SAFETY CODES AND REGULATIONS DURING ALL PHASES OF CONSTRUCTION.  
 3. CONTRACTOR SHALL COORDINATE NEW FRAMING WITH EXISTING MECHANICAL, ELECTRICAL CONDUITS, AND LIGHTING.  
 4. SHOULD ANY OF THE DETAILED INSTRUCTIONS SHOWN ON THE PLANS CONFLICT WITH THESE STRUCTURAL NOTES, THE SPECIFICATIONS, OR WITH EACH OTHER, THE STRICTEST PROVISION SHALL GOVERN.  
 5. ALL DIMENSIONS AND ELEVATIONS SHOWN ON STRUCTURAL DRAWINGS SHALL BE VERIFIED BY THE CONTRACTOR AND SHALL CONFORM TO THOSE SHOWN ON THE ARCHITECTURAL DRAWINGS.

**D. STRUCTURAL STEEL**  
 1. MATERIALS:  
 A. HIGH STRENGTH BOLTS: ASTM A325 OR A490; ANCHOR BOLTS: ASTM A307 OR A36B.  
 B. EXPANSION ANCHORS: HILTI DROP IN OR APPROVED EQUAL.  
 C. ELECTROSTROBES: SERIES E70XX.

IF DIAGONAL WIRE TIES INSTALLED AT 12'-0" O/C  
 MAX. HOR. FORCE = 12(12)1.8sf.) = 115#  
 STRUT FORCE = 115# IF WIRES AT 45°  
 WIRE FORCE = 115(2) = 163#/WIRE

**SEISMIC DESIGN NOTES**  
 1. SEISMIC USE GROUP = 2  
 2. SITE CLASS = D (ASSUMED)  
 3. SDS = 0.417  
 4. SDI = 0.152  
 5. SEISMIC DESIGN CATEGORY = C

**SUSPENDED CEILING AND LIGHT FIXTURES**  
 1. COMPONENT RESPONSE MODIFICATION FACTOR RP = 2.5  
 2. COMPONENT AMPLIFICATION FACTOR AP = 1.0  
 3. SEISMIC FORCE = 0.80# PER SQ. FT. OF CEILING.  
 4. CEILING AND LIGHT FIXTURES SHALL BE DESIGNED AND INSTALLED IN ACCORDANCE WITH CISCA-02 PUBLISHED BY THE CEILING AND INTERIOR SYSTEMS CONSTRUCTION ASSOCIATION EXCEPT THE SEISMIC FORCE INDICATED IN NOTE #4 ABOVE SHALL BE USED.  
 5. ALL CEILING COMPONENTS FASTENERS, AND ATTACHMENTS TO THE BUILDING STRUCTURE SHALL BE SUBMITTED TO THE ARCHITECT FOR APPROVAL.

**D. STRUCTURAL STEEL (CONTINUED)**  
 2. SPECIFICATIONS:  
 A. WELDING PERSONNEL AND PROCEDURES ARE TO BE QUALIFIED PER AWS D1.1 UNLESS SPECIFICALLY SHOWN OTHERWISE. DESIGN, FABRICATION AND ERECTION TO BE GOVERNED BY:  
 B. AISC ASD SPECIFICATION FOR STRUCTURAL STEEL BUILDINGS  
 C. AISC CODE OF STANDARD PRACTICE  
 D. STRUCTURAL WELDING CODE, AWS D1.1-2002 OF THE AMERICAN WELDING SOCIETY  
 E. SPECIFICATIONS FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS (JUNE 23, 2000).  
 3. CONNECTIONS:  
 A. FOLLOW INSTRUCTIONS ON DRAWINGS FOR GENERAL ARRANGEMENT OR PARTICULAR DETAILS. FIELD CONNECTIONS NOT OTHERWISE NOTED TO BE BOLTED.

**E. DIMENSIONAL LUMBER**  
 1. PROPERTIES:  
 A. VISUALLY GRADED LUMBER SHALL HAVE THE FOLLOWING MIN. BASE DESIGN VALUES:  
 1. 850 PSI IN BENDING, F<sub>b</sub>  
 2. 1350 PSI IN COMPRESSION PARALLEL WITH GRAIN F<sub>c</sub>  
 3. 90 PSI IN HORIZONTAL SHEAR, F<sub>v</sub>  
 4. E = 1,200,000 PSI  
 2. SPECIFICATIONS:  
 A. DETAILS, FABRICATION SPECIFICATIONS FOR WOOD CONSTRUCTION (1997 ED.).  
 3. MOISTURE CONTENT:  
 A. MAXIMUM FOR ALL STRUCTURAL MEMBERS SHALL NOT EXCEED 19%.  
 4. MISCELLANEOUS:  
 A. NO STRUCTURAL MEMBER SHALL BE CUT OR NOTCHED UNLESS SPECIFICALLY SHOWN, NOTED OR APPROVED BY THE ENGINEER.  
 B. ALL DIMENSIONAL LUMBER TO DIMENSIONAL LUMBER CONNECTIONS SHALL BE AS MANUFACTURED BY "SIMPSON COMPANY" OR APPROVED EQUAL.

**F. LIGHTGAGE METAL FRAMING**  
 1. MATERIALS:  
 A. STUDS AND TRACKS: 18 AND 16 GAGE, ASTM A446 GRADE D, F<sub>y</sub> @ 33 KSI. SHOT PINS W/ WASHERS: HILTI BRAND (ICBO NO. ER-2388) OR APPROVED EQUAL.  
 2. SPECIFICATIONS:  
 A. WELDING PERSONNEL AND PROCEDURES ARE TO BE QUALIFIED PER AWS. DESIGN, FABRICATION AND ERECTION TO BE GOVERNED BY LATEST REVISIONS OF:  
 1. AISC SPECIFICATIONS OF THE DESIGN OF COLD FORMED STEEL STRUCTURAL MEMBERS  
 2. STRUCTURAL WELDING CODE, AWS D1.3-98 OF THE AMERICAN WELDING SOCIETY.


**CEILING AND LIGHT FIXTURE ATTACHMENT NOTES**

- GENERAL NOTES:
- HORIZONTAL RESTRAINT POINTS SHALL BE PALCED 12'-0" OR UNDER IN BOTH DIRECTIONS WITH THE POINT WITHIN 6'-)" FROM EACH WALL.
  - LIGHT FIXTURES SHALL HAVE NO.8 SEISMIC SAFETY. SAFTEY WIRES TIED TO STRUCTURE:  
 2 EA. AT OPPOSITE ENDS OF FLUORESCENT FIXTURES  
 1 EA. INCANDESCENT FIXTURES  
 4'-0" O.C. FOR LIGHT TRACKS
  - LIGHT FIXTURES SHALL BE SUPPORTED BY NO.12 GAGE HANGERS ATTACHED TO THE GRID MEMBERS WITHIN 3" OF EACH CORNER OF EACH FIXTURE.
  - SPLICES AND INTERSECTIONS OF RUNNERS RUNNERS SHALL BE ATTACHED WITH MECHANICAL INTERLOCKING CONNECTORS SUCH AS POP RIVETS, SCREWS, PIN PLATES WITH BENT TABS OR OTHER APPROVED CONNECTIONS FOR 2X DESIGN LEAD OR ULTIMATE AXIAL TENSION OR COMPRESSION (MINIMUM 60 LBS.) OR CROSS FURRING SHALL BE SECURLY ATTACHED TO THE MAIN RUNNER BY SADDLE. TYING WITH NOT LESS THAN ONE STRAND OF NO. 8 US GAUGE TIE WIRE OR TWO STRANDS OF NO. 8 US GAUGE TIE WIRE OR APPROVED EQUIVALENT ATTACHMENT, RUNNERS AND FURRING.



CLIENT:  
**SSP AMERICA**  
 20408 BASHAN DRIVE  
 SUITE 300  
 ASHBURN, VA 20147

PROJECT TEAM:  
 ARCHITECT:  
 ENVIRONETICS GROUP ARCHITECTS  
 180 SYLVAN AVE.  
 ENGLEWOOD CLIFFS, NJ 07632  
 MEP ENGINEER  
 GUTH DECONZO CONSULTING  
 ENGINEERS, PC  
 520 8TH AVENUE, SUITE 2201  
 NEW YORK, NY 10001



**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: ISSUED FOR PERMIT  
 ISSUE DATE: 08/16/2024


PROJECT NUMBER: 24017G  
 DRAWN BY: RW, JR, PQ  
 CHECKED BY: DJB

Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE:  
**TYP. SEISMIC DETAILS & NOTES**

SHEET NUMBER:  
**A-461**





**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: PERMIT  
 ISSUE DATE: 09/03/2024


PROJECT NUMBER: 24017G  
 DRAWN BY:  
 CHECKED BY:

Copyright (c) by Environment, Inc. All Rights Reserved.

SHEET TITLE:

**FOODSERVICE EQUIPMENT PLAN**

SHEET NUMBER  
**K1**



**FOODSERVICE EQUIPMENT PLAN**  
 SCALE: 1/4" = 1'-0"

**EQUIPMENT SCHEDULE**


| ITEM  | QTY | CATEGORY                                  | EQUIPMENT REMARKS      | MFR                      | MODEL              |
|-------|-----|---|------------------------|--------------------------|--------------------|
| K1    | 1   | EXHAUST HOOD                              |                        | ACCUREX                  | CUSTOM             |
| K3    |     | SPARE NUMBER                              |                        |                          |                    |
| K4    | 1   | GRIDDLE, GAS, COUNTERTOP                  | GRILL ADV. PACKAGE     | SOUTHBEND                | HDG-60             |
|       | 1   | PLATE LANDING SHELF                       |                        | SOUTHBEND                | SPSS-60            |
|       | 1   | GRIDDLE PAN HOLDER SHELF                  | SIZED FOR GRIDDLE      | SPG                      | CUSTOM             |
| K5    | 1   | EQUIPMENT STAND, REFRIGERATED BASE        |                        | CONTINENTAL REFRIGERATOR | D60GN              |
| K6    | 1   | SHELVING, WALL MOUNTED                    | 60" L X 21" D          | SPG                      | CUSTOM             |
| K7    | 2   | FRYER BATTERY, GAS                        | TRIPLE BASKETS (6)     | PITCO                    | SSH60W-1FD         |
| K8    | 1   | REACH-IN FREEZER                          | HINGE RIGHT            | HOSHIZAKI                | F1A-FS             |
| K9    | 1   | HAND SINK                                 |                        | JOHN BOOS                | PBHS-W-1410-P-SSLR |
| K10   |     | SPARE NUMBER                              |                        |                          |                    |
| K11   | 1   | REACH-IN FREEZER                          | HINGE LEFT             | HOSHIZAKI                | F1A-FSL            |
| K12   | 1   | REACH-IN REFRIGERATOR                     |                        | HOSHIZAKI                | R2A-FS             |
| K13   | 1   | WORK TABLE W/ HAND SINK                   | 34" W X 36" D X 36"    | SPG                      | CUSTOM             |
| K14   | 1   | MEGA TOP PREPARATION REFRIGERATOR         |                        | CONTINENTAL REFRIGERATOR | D72N27M-D          |
| K15   |     | SPARE NUMBER                              |                        |                          |                    |
| K16   | 1   | TOASTER, CONTACT GRILL, CONVEYOR TYPE     | 120V                   | ANTUNES                  | VCT-1000-9210700   |
| K17   |     | SPARE NUMBER                              |                        |                          |                    |
| K18   | 1   | COFFEE / TEA BREWER                       |                        | CURTIS                   | G4CBHS             |
| K19   | 2   | WALL SHELF W/ INVERTED WALL BRACKETS      | 60" L X 18" D          | SPG                      | WALL SHELF         |
| K20   | 1   | WORK TABLE W/SLIDES & CUTTING BOARD       | "L SHAPE" PER PLAN     | SPG                      | WORK TABLE         |
| K21   | 1   | FRENCH FRY WARMER, DROP IN                |                        | CARTER-HOFFMANN          | CNH28LP            |
| K22   | 1   | WARMING DRAWER, FREE STANDING             |                        | WINSTON                  | HBB0D2             |
| K23   | 1   | DBL PASS SHELF, ENCLOSURE END PANELS      | 84" LONG               | CUSTOM                   | CUSTOM             |
| K23.1 | 1   | HEAT LAMP                                 | 120/208V               | HATCO                    | GRAHL-66           |
|       | 1   | REMOTE CONTROL ENCLOSURE                  |                        | HATCO                    | RMB-7P             |
| K23.2 | 1   | WALL SHELF W/ INVERTED WALL BRACKETS      | 84" L X 18" D          | SPG                      | WALL SHELF         |
| K24   | 1   | PRE-RINSE FAUCET W/ADD ON FAUCETER        |                        | T&S BRASS                | B-0133-12-CR-BC    |
| K25   | 1   | THREE (3) COMPARTMENT SINK                | 102" W X 30" D X 34" H | SPG                      | CUSTOM             |
| K26   |     | SPARE NUMBER                              |                        |                          |                    |
| K28   | 1   | WORK TABLE, PREP SINK                     | 60" W X 30" D X 36" H  | SPG                      | WT-PS              |
|       | 1   | DECK MOUNT FAUCET                         |                        | T&S BRASS                | B-0220-061X-WH4    |
| K29   | 2   | OVERSHELF, WALL-MOUNTED WITH POT RACK     | 14" D X 36" L          | SPG                      | WS-PR14            |
| K30   | 3   | INTERMEDIATE SHELVING, WALL MOUNTED       | 16" D X 36" L          | SPG                      | WS-16              |
| K31   | 3   | HIGH SHELVING, WALL MOUNTED               | 18" D X 36" L          | SPG                      | WS-18              |
| K32   | 2   | POINT-OF-SALE SYSTEMS                     |                        | CUSTOM                   | POS                |
| K33   | 1   | MOP SINK                                  |                        | SPG                      | MOP-20-B           |
|       | 1   | MOP BROOM HOLDER                          |                        | SPG                      | MH-3               |
|       | 1   | SERVICE FAUCET                            |                        | T&S BRASS                | B-0660-BSTP        |
| K34   | 1   | SODA ICE & BEVERAGE DISPENSER, IN-COUNTER | BY OWNERS VENDOR       | CORNELIUS                | 631100049          |
| K36   | 1   | DISHWASHER, UNDERCOUNTER - LOW TEMP       | BY OWNER               | CMA DISHMACHINES         | L-1X W/HEATER      |
| K37   | 1   | BAG-N-BOX/CO2 TANK                        | BY OWNERS VENDOR       |                          |                    |
| K38   | 1   | WIRE SHELVING RACK UNIT                   | 2 TIER                 | QUANTUM                  | 2436P              |
| K39   | 1   | ICE MAKER, CUBE-STYLE                     |                        | HOSHIZAKI                | KM-1100MWJ         |
| K40   | 1   | ICE BIN FOR ICE MACHINES                  |                        | KLOPPENBERG              | 705-SS             |
| K41   | 1   | STORAGE CABINET, W/ HAND SINK             | 12'-0" X 24" X 34" H   | SPG                      | CUSTOM             |
|       | 1   | DECK MOUNT FAUCET                         |                        | T&S BRASS                | B-1141-04-CR       |
| K42   | 2   | DISPOSABLE CUP DISPENSER                  | COUNTER TOP            | DISPENSE-RITE            | STL-SL-2BT         |

**BAR EQUIPMENT SCHEDULE**


| ITEM | QTY | CATEGORY  | EQUIPMENT REMARKS    | MFR              | MODEL       |
|------|-----|---|----------------------|------------------|-------------|
| B1   | 1   | GLASSWASHER, UNDERCOUNTER / UNDERBAR            | BY OWNER             | CMA DISHMACHINES | GW-100      |
| B2   | 1   | HAND SINK                                       |                      | KROWNE           | KR24-S12C   |
| B3   |     | SPARE NUMBER                                    |                      |                  |             |
| B4   | 1   | BACK BAR CABINET, NON-REFRIGERATED              |                      | KROWNE           | BD48        |
| B5   | 1   | REACH-IN UNDERCOUNTER FREEZER                   |                      | TURBO AIR        | JUF-60S-N   |
| B6   | 1   | BACK BAR CABINET, REFRIGERATED                  |                      | KROWNE           | BS60        |
|      | 1   | CASTERS   |                      | KROWNE           | BC-130      |
| B7   | 1   | BACK BAR CABINET, REFRIGERATED                  |                      | KROWNE           | BS60        |
|      | 1   | CASTERS   |                      | KROWNE           | BC-130      |
| B8   | 1   | ICE BIN WITH SINK COMBO UNIT                    |                      | KROWNE           | KR24-S74-10 |
|      |     | BOTTLE STORAGE, W/ LOCKING COVER                | PART OF STATION      | KROWNE           | KR24-1BRD   |
|      |     | SODA GUN HOLDER                                 | PART OF STATION      | KROWNE           | KR19-4SH-L  |
|      |     | SPEED RAIL / RACK W/ LOCKING COVER              | PART OF STATION      | KROWNE           | RS-42       |
|      |     | UNDERBAR DUMP SINK UNITS                        | PART OF STATION      | KROWNE           | KR24-MS14   |
| B9   | 1   | WORK CENTER                                     |                      | KROWNE           | KR24-PC24   |
| B10  | 1   | POINT-OF-SALE SYSTEMS                           |                      | CUSTOM           | POS         |
| B11  | 2   | DRAINBOARD                                      |                      | KROWNE           | KR24-SD24   |
| B12  | 1   | DRAFT BEER COOLER                               | KEGS (3) 1/2 (1) 1/6 | KROWNE           | DB72        |
| B13  | 1   | DISPENSING HEAD, DRAFT BEER, W/BEER DRAINER PAN | 3 TAP ENGINEERED     | CUSTOM           | CUSTOM      |

**SSP AMERICA**  
 20408 BASHAN DRIVE  
 SUITE 300  
 ASHBURN, VA 20147

PROJECT TEAM:  
 ARCHITECT:  
 ENVIRONMENTAL GROUP ARCHITECTS  
 180 SYLVAN AVE.  
 ENGLEWOOD CLIFFS, NJ 07632  
 MEP ENGINEER:  
 GUTH DECONZO CONSULTING  
 ENGINEERS, P.C.  
 520 8TH AVENUE, SUITE 2201  
 NEW YORK, NY 10001  
 FOODSERVICE:  
 Kitchen Concepts  
 Foodservice Design  
 8300 Crystal Lane, Tx 76182



**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA



**FOODSERVICE EQUIPMENT DRAIN PLAN**  
 SCALE: 1/4" = 1'-0"




### PLUMBING NOTES

NOTES

- A PLUMBER TO PROVIDE BACKFLOW PREVENTERS IN WATER SUPPLY LINES AS REQUIRED BY LOCAL CODES
- B PLUMBER TO SPECIFY AND LOCATE EQUIPMENT AND UTILITIES FOR THESE LOCATIONS.
- C PLUMBER TO CONNECT ALL WATER LINES, GAS LINES, WASTE LINES, ETC. TO FULLY CONNECT ALL EQUIPMENT AND RUN CONDENSATE LINES FROM UNITS TO DRAINS AND THESE LINES TO BE NO SMALLER THAN THE STUB-OUT OF THE FIXTURE. PLUMBER TO PROVIDE GATE VALVES, CUT-OFFS, TRAPS, HYDROSTATIC SHOCK ELIMINATORS, PRESSURE REGULATORS AND MATERIALS NECESSARY TO CONNECT ALL LINES UNLESS OTHERWISE SPECIFIED IN THE ITEM SPECIFICATIONS. FAUCETS, DRAIN OUTLET FITTINGS IN FIXTURES AND SPECIALTY ITEMS ARE TO BE FURNISHED BY THE KITCHEN EQUIPMENT SUPPLIER AS OUTLINED IN THE ITEM SPECIFICATIONS. ALL WORK TO BE PERFORMED IN FULL ACCORDANCE WITH THE APPLICABLE CODES RELATING TO INSTALLATION AND HOOK-UP OF EQUIPMENT. OMISSIONS OR ERRORS ON THE SCHEDULE DO NOT RELIEVE THE PLUMBING CONTRACTOR FROM COMPLETE FINAL PLUMBING RESPONSIBILITY.
- D ALL OUTLETS AND CONNECTIONS SHOWN RELATE TO KITCHEN EQUIPMENT ONLY. REFER TO ARCHITECTURAL/ENGINEERING PLANS FOR ADDITIONAL REQUIREMENTS.
- E ALL DIMENSIONS GIVEN ARE FROM COLUMN CENTERLINES AND/OR FINISHED WALLS AND ARE IN INCHES TO 4'-0". ELEVATIONS GIVEN ARE FROM FINISHED FLOORS. ALL FINISHES SHOWN ARE TO BE RUN INSIDE WALLS (EXCEPT STUB-UPS) LOCATIONS INDICATE POINT OF EXIT FROM WALLS, CEILINGS OR FLOORS.
- F ALL FLOOR DRAINS TO SET 1/2" BELOW FINISHED FLOOR UNLESS OTHERWISE NOTED. DO NOT SLOPE FLOORS SO CLOSE TO DRAINS AS TO CREATE "TIPS" OR "DIPS" IN FLOOR. MINIMUM RADIUS OF SLOPE TO BE 24" FROM CENTERLINE OF DRAIN.
- G PLUMBER TO RUN HARD COPPER DRAINLINE HIGH AS POSSIBLE IN WALK-IN VAULT FROM BLOWER COIL TO WALL THEN SLOPING DOWN TO A POINT 18" ABOVE FLOOR THEN THRU WALL FORMING A "P" TRAP FLAT AGAINST WALL ABOVE DRAIN THEN EXTENDING TO DRAIN. SECURE LINES IN A NEAT MANNER AND FINISH WITH CHROMATONE PAINT - SEAL ALL PENETRATIONS.

### DRAIN SYMBOLS

| SYMBOLS | ABBREVIATIONS  |
|---------|--|
| Ⓢ       | FS FLOOR SINK  |
| ○       | FFD FUNNEL DRAIN                                     |
| Ⓢ       | HD HUB DRAIN   |
| Ⓢ       | EL ELEVATION ABOVE FINISHED FLOOR                    |
| Ⓢ       | SU STUB UP ABOVE FINISHED FLOOR                      |
| Ⓢ       | AFF ABOVE FINISHED FLOOR                             |
| Ⓢ       | BFF BELOW FINISHED FLOOR                             |
| DR      | DFA DOWN FROM ABOVE                                  |
| FD      | BTC BRANCH TO CONNECTION POINT AND CONNECT EQUIPMENT |
| DD      |  |




### DRAIN SCHEDULE

| NO. | UTILITY            | SIZE       |            | HEIGHT A.F.F. |         |     | CONNECTED TO/REMARKS  |
|-----|--------------------|------------|------------|---------------|---------|-----|---|
|     |                    | ROUGH-IN   | CONNECTION | FLOOR         | WALL    | DFA |   |
| FTD | FLOOR TROUGH DRAIN | 3"         | 3"         | -7            | 1/4"    |     |   |
| FD  | FLOOR DRAIN        | 3"         | 3"         | -1/2          |         |     | PLUMBER TO RUN INDIRECT WASTES FROM EQUIPMENT TO DRAIN IN FLOOR AS REQ'D, OR IS TO BE USED FOR GENERAL CLEAN-UP |
| HD  | HUB DRAIN          | 3"         | 3"         | 6"            |         |     | PLUMBER TO RUN INDIRECT WASTE FROM FIXTURE  |
| FS  | FLOOR SINK         | 3"         | 3"         | FLUSH         |         |     | 12" SQUARE -1/2 GRATE (PLUMBER TO RUN INDIRECT DRAIN LINES FROM FIXTURES)                                       |
| HSD | HAND SINK DRAIN    | 1 1/2"     | 1 1/2"     |               | 24 1/2" |     | BTC ON HAND SINK WASTE  |
| MSD | MOP SINK DRAIN     | 3"         | 3"         | -2            |         |     | BTC ON MOP SINK WASTE (VERIFY WITH PLUMBER)   |
| FFD | FUNNEL FLOOR DRAIN | 3"         | 3"         | FLUSH         |         |     | 4" HIGH FUNNEL (PLUMBER TO RUN INDIRECT DRAIN LINES FROM FIXTURES)  |
| IW  | INDIRECT WASTE     | L.D. WASTE |            | EQUIP         |         |     | INDIRECT WASTE FROM EQUIPMENT TO DRAIN LOCATIONS.   |
| DD  | DIRECT DRAIN       | 1 1/2"     | 1 1/2"     |               | 18"     |     | BTC ON HAND SINK WASTE  |


NOTE: NOT ALL DRAIN APPLICATIONS WILL BE USED.

SSP AMERICA 20408 BASHAN DRIVE SUITE 300 ASHBURN, VA 20147

PROJECT TEAM: ARCHITECT: ENVIRONETICS GROUP ARCHITECTS 180 SYLVAN AVE. ENGLEWOOD CLIFFS, NJ 07632 MEP ENGINEER: GUTH DECONZO CONSULTING ENGINEERS, PC 520 8TH AVENUE, SUITE 2201 NEW YORK, NY 10001 FOODSERVICE: Kitchen Concepts Foodservice Design 8300 Crystal Lane, Tx 76182



B-FB4 - WAHLBURGERS SARASOTA BRADENTON INTERNATIONAL 6000 AIRPORT CIRCLE SARASOTA, FL 34243 CLIENT: SSP AMERICA




KITCHEN WATER SCHEDULE table with columns: ITEM, QTY, CATEGORY, COLD, HOT, LOC, AFF, PLUMBING REMARKS. Includes items for hand sinks, coffee/tea brewer, pre-rinse faucet, three-compartment sink, work table prep sink, mop sink, soda dispenser, dishwasher, ice maker, and carbonator.

BAR WATER SCHEDULE table with columns: ITEM, QTY, CATEGORY, COLD, HOT, LOC, AFF, PLUMBING REMARKS. Includes items for dishwasher, hand sink, faucet, rinser, and dipper well.

GAS SCHEDULE table with columns: ITEM, QTY, GAS SIZE CONIN., LOCATION, AFF, SERVICE, BTU TOTAL, REMARKS. Includes items for natural gas service to foodservice equipment, griddle, and fryer battery.

PLUMBING NOTES table with columns: NOTES, A through G. Contains detailed instructions for water supply, equipment location, gas line connections, and floor drains.



PLUMBING SYMBOLS table with columns: SYMBOLS, ABBREVIATIONS. Lists symbols for hot/cold water, drains, connections, floor drains, funnels, floor sinks, hubs, hot water, cold water, and down from above.



FOODSERVICE EQUIPMENT WATER & GAS PLAN SCALE: 1/4" = 1'-0"


GAS QUICK-DISCONNECT INSTALLATION DETAIL SCALE: NONE (TYPICAL INSTALLATION)

Revision table with columns: REV, DATE, DESCRIPTION. Design deliverable: 08/16/2024. Project number: 24017G. Checked by: [blank]. Sheet title: FOODSERVICE EQUIPMENT WATER & GAS PLAN. Sheet number: K3.



FOODSERVICE EQUIPMENT ELECTRICAL PLAN SCALE: 1/4" = 1'-0"

BAR ELECTRICAL PLAN and KITCHEN ELECTRICAL PLAN tables listing items, quantities, categories, voltages, phases, and electrical remarks.



REMOTE FIRE PULL DETAIL - A SCALE: NONE

ELECTRICAL SYMBOLS AND ABBREVIATIONS table listing symbols for receptacles, outlets, switches, and other components.

ELECTRICAL NOTES table containing instructions for installation, wiring, and equipment requirements.

Revision table with columns for REV, DATE, and DESCRIPTION.

DESIGN DELIVERABLE: PERMIT ISSUE DATE: 08/16/2024


PROJECT NUMBER: 24017G CHECKED BY: Copyright (c) by Environetcs, Inc. All Rights Reserved.

FOODSERVICE EQUIPMENT ELECTRICAL PLAN

SHEET NUMBER: K4



**SSP AMERICA**  
 20408 BASHAN DRIVE  
 SUITE 300  
 ASHBURN, VA 20147

PROJECT TEAM:  
 ARCHITECT:  
 ENVIRONMENTAL GROUP ARCHITECTS  
 180 SYLVAN AVE.  
 ENGLEWOOD CLIFFS, NJ 07632  
 MEP ENGINEER:  
 GUTH DECONZO CONSULTING  
 ENGINEERS, PC  
 520 8TH AVENUE, SUITE 2201  
 NEW YORK, NY 10001  
 FOODSERVICE:  
 Kitchen Concepts  
 Foodservice Design  
 8300 Crystal Lane, Tx 76182





**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA

NOTE: ALL SODA/BEER CONDUIT LINE RUNS ARE GEOGRAPHICALLY LOCATED TO INDICATED WHERE CONDUIT LINES WILL START AND TERMINATE.



**SECTION AT DBL. PASS SHELF - AA**  
 SCALE: NONE

**FOODSERVICE EQUIPMENT WALL BLOCKING & BUILDING CONDITIONS PLAN**  
 SCALE: 1/4" = 1'-0"




**WALL BLOCKING SECTIONS**  
 NO BLOCKING AT CMU WALLS  
 NOTE: SOME APPLICATIONS MAY NOT BE USED

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: PERMIT  
 ISSUE DATE: 08/16/2024  
 PROJECT NUMBER: 24017G  
 DRAWN BY:  
 CHECKED BY:

Copyright (c) by Environmental, Inc. All Rights Reserved.  
 SHEET TITLE:  
**FOODSERVICE EQUIPMENT WALL BLOCKING & BUILDING CONDITIONS PLAN**

SHEET NUMBER:  
**K5**




| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: ISSUED FOR PERMIT  
 ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G  
 DRAWN BY:  
 CHECKED BY:  
 Copyright (c) by Environmental, Inc. All Rights Reserved.


SHEET TITLE:  
**FOODSERVICE EQUIPMENT ELEVATIONS AND SECTIONS**

SHEET NUMBER:  
**K6**




**ELEVATION VIEW - 1**  
 SCALE: 1/2" = 1'-0"


**ELEVATION VIEW - 2**  
 SCALE: 1/2" = 1'-0"




**ELEVATION VIEW - 3**  
 SCALE: 1/2" = 1'-0"




**ELEVATION VIEW - 4**  
 SCALE: 1/2" = 1'-0"




**ELEVATION VIEW - 5**  
 SCALE: 1/2" = 1'-0"




**ELEVATION VIEW - 6**  
 SCALE: 1/2" = 1'-0"



**ELEVATION VIEW - 7**  
 SCALE: 1/2" = 1'-0"





**ELEVATION VIEW - 8**  
 SCALE: 1/2" = 1'-0"




**ELEVATION VIEW - 9**  
 SCALE: 1/2" = 1'-0"

**SSP AMERICA**  
 20408 BASHAN DRIVE  
 SUITE 300  
 ASHBURN, VA 20147


PROJECT TEAM  
 ARCHITECT:  
 ENVIRONMENTALS GROUP ARCHITECTS  
 180 SYLVAN AVE.  
 ENGLEWOOD CLIFFS, NJ 07632  
 MEP ENGINEER  
 GUTH DECONZO CONSULTING  
 ENGINEERS, PC  
 520 8TH AVENUE, SUITE 2201  
 NEW YORK, NY 10001  
 FOODSERVICE:  
 Kitchen Concepts  
 Foodservice Design  
 8300 Crystal Lane, Tx 76182




**ELEVATION VIEW - 10**  
 SCALE: 1/2" = 1'-0"




**SECTION - BB**  
 SCALE: NONE




**SECTION - CC**  
 SCALE: NONE



**SECTION - DD**  
 SCALE: NONE



**SECTION - EE**  
 SCALE: NONE



**SECTION - FF**  
 SCALE: NONE

**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: ISSUED FOR PERMIT  
 ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G  
 DRAWN BY:  
 CHECKED BY:

Copyright (c) by Environetcs, Inc. All Rights Reserved.

SHEET TITLE:  
**FOODSERVICE EQUIPMENT ELEVATIONS AND SECTIONS**

SHEET NUMBER:  
**K7**

MECHANICAL ABBREVIATIONS AND SYMBOL LIST

Table with columns for Abbreviation, Description, Unit, and Symbol. Includes entries for AC (Air Conditioning), ACCU (Air-Cooled Condensing Unit), AD (Access Door), AFF (Above Finished Floor), AL (Acoustically Lined), ALU (Aluminum), AP (Access Panel), BDD (Back Draft Damper), BHP (Brake Horsepower), BI (Black Iron), BTU (British Thermal Unit), BTUH (BTU per Hour), CHW (Chilled Water), CD (Ceiling Diffuser), CFM (Cubic Feet per Minute), CG (Ceiling Grille), CLG (Ceiling), CR (Ceiling Register), CU (Copper), CU FT (Cubic Feet), CU IN (Cubic Inches), CV (Constant Volume), D (Drop), DB (Dry Bulb), DIAM (Diameter), DN (Down), DWG (Drawing), DX (Direct Expansion), EAT (Entering Air Temperature), EDB (Entering Dry Bulb Temperature), EF (Exhaust Fan), ELEC (Electric), ERHC (Electric Reheat Coil), EQ (Equal), EWB (Entering Wet Bulb), EWT (Entering Water Temperature), EXH (Exhaust), EX (Existing), F (Filter), F (Degree Fahrenheit), FC (Flexible Connection), FD (Fire Damper), FA (Free Area), F.A. (Face Area), FLA (Full Load Amperes), FPM (Feet per Minute), FLDR (Floor Drain), FIN FL (Finished Floor), FSD (Fire Smoke Damper), FT (Feet), FTR (Finned Tube Radiation), GPH (Gallons per Hour), GPM (Gallons per Minute), H (Height), HW (Hot Water), HWC (Hot Water Coils), L (Length), LAT (Leaving Air Temperature), LBS (Pounds), LDB (Leaving Dry Bulb Temperature), LIN FT (Linear Feet), LWB (Leaving Wet Bulb), LWT (Leaving Water Temperature), MAX (Maximum), MBH (Thousand BTU per Hour), MCC (Motor Control Center), MER (Mechanical Equipment Room), MHP (Motor Horsepower), MIN (Minimum), MOT (Motor), NC (Normally Closed), NIC (Not in Contract), NO (Normally Open), NO. (Number), NTS (Not to Scale), OAI (Outside Air Intake), OD (Outside Diameter), OV (Outlet Velocity), PD (Pressure Drop), PHC (Preheat Coil), PSIA (Psi Absolute), PSIG (Psi Gauge), R (Rise), RA (Return Air), RF (Return Fan), RM (Room), RPM (Revolution per Minute), RH (Relative Humidity), RHC (Reheat Coil), SD (Smoke Damper), SDR (Smoke Detector), SLD (Stripline Linear Diffuser), SP (Static Pressure), SPEC (Specification), SS (Stainless Steel), T (Throat), TEMP (Temperature), TG (Top Grille), TR (Top Register), TRF (Transfer Fan), TRF (Transfer Fan), TT (Top Throat), TYP (Typical), TX (Toilet Exhaust), UH (Unit Heater), V (Volts), W (Width), W/ (With), W/O (Without), WQ (Wet Bulb), WC (Water Column), WG (Water Gauge), WMS (Wire Mesh Screen).

NOTE: ALL ABBREVIATIONS AND SYMBOLS LISTED ABOVE ARE FOR REFERENCE AND NOT NECESSARILY USED IN THIS PROJECT.

GENERAL NOTES

- 1. THE CONTRACTOR SHALL VISIT THE PREMISES TO DETERMINE EXISTING CONDITIONS AND COMPARE SAME WITH CONTRACT DRAWINGS AND SPECIFICATIONS. THE CONTRACTOR IS TO SATISFY THEMSELVES OF ALL CONDITIONS PRIOR TO THE SUBMISSION OF A BID PROPOSAL. NO ALLOWANCE WILL BE MADE FOR FAILURE TO COMPLY WITH THESE REQUIREMENTS AND A BID PROPOSAL SHALL BE CONSTRUED AS EVIDENCE THEY HAVE DONE SO.
2. ALL HVAC WORK SHALL BE COORDINATED WITH ALL TRADES INVOLVED. OFFSETS IN PIPING AND DUCTS (INCLUDING DIVIDED DUCTS) AND TRANSITIONS AROUND OBSTRUCTIONS SHALL BE PROVIDED AT NO ADDITIONAL COST TO THE OWNER.
3. COORDINATE DUCTWORK WITH APPROVED SUBMISSION OF SUPPLY, RETURN & EXHAUST AIR TERMINAL UNIT SIZES AND ASSOCIATED INLET AND OUTLET CONNECTIONS.
4. PROVIDE ACCESS AS REQUIRED FOR DUCT SMOKE DETECTORS INSTALLED IN DUCTWORK.
5. DUCT SMOKE DETECTORS SHALL BE FURNISHED AND WIRED BY THE ELECTRICAL CONTRACTOR. MECHANICAL CONTRACTOR IS RESPONSIBLE FOR MOUNTING THE SMOKE DETECTORS IN DUCTWORK AS REQUIRED AND SHOWN ON PLANS. MECHANICAL CONTRACTOR IS RESPONSIBLE TO CONDUCT AND PROVIDE THE RESULTS THE DUCT SMOKE DETECTOR PRESSURE DIFFERENTIAL TO THE ENGINEER AND ANY OTHER AUTHORITY HAVING JURISDICTION.
6. PROVIDE ACCESS PANELS UPSTREAM OF ALL ELBOWS WITH TURNING VANES. ALL ACCESS DOORS AND ACCESS PANELS ARE TO BE LABELED. ALL VALVES ARE TO BE LOCATED IN THE HORIZONTAL POSITION AND BE EASILY REACHABLE WITHOUT CLIMBING UP INSIDE THE CEILING OR A REMOTE METHOD OF OPERATION AT CEILING HEIGHT IS TO BE PROVIDED.
7. PROVIDE ACCESS PANELS IN DUCTWORK FOR OPERATION, ADJUSTMENT AND MAINTENANCE OF ALL FANS, VALVES AND MECHANICAL EQUIPMENT.
8. ACCESS DOORS INTO DUCTWORK SHALL NOT BE SMALLER THAN 18"x18" UNLESS DUCT SIZE DOES NOT PERMIT. INDICATE SIZE AND LOCATIONS OF ALL ACCESS DOORS.
9. PROVIDE VOLUME DAMPERS IN ALL SUPPLY AND RETURN BRANCH DUCTWORK. PROVIDE ONE VOLUME DAMPER FOR EACH SUPPLY DIFFUSER AND RETURN GRILLE. PROVIDE MANUAL DAMPERS IN EACH SPLIT OR TAP CONNECTION TO TRUNK DUCTS FOR BALANCING PURPOSES. EACH PROVIDED WITH OPERATOR AND LOCKING DEVICE. INSTALL DIVERTING VANES AT BRANCHES CONNECTED INTO THE MAIN WITHOUT A NECK.
10. ALL AIR OUTLETS (DIFFUSERS, GRILLES, REGISTERS, LINEAR SLOTS, ETC.) SHALL BE COORDINATED WITH THE ARCHITECTURAL CEILING PLAN (LIGHTS, SPRINKLER HEADS, CEILING GRID), ELECTRICAL PLANS, SPRINKLER PLANS, AND WITH REVIEWED AND APPROVED AIR OUTLET SUBMITTAL.
11. ARCHITECT TO REVIEW AND APPROVE FACE SIZE AND EXACT LOCATION OF ALL AIR OUTLETS (DIFFUSERS, GRILLES, REGISTERS, ETC.) AND COORDINATE WITH EQUIPMENT MFR. REQUIREMENT.
12. ARCHITECT & OWNER TO REVIEW AND APPROVE LOCATION OF ALL THERMOSTATS IN CONJUNCTION WITH FINAL EQUIPMENT LAYOUT.
13. SHEET-METAL SHOP DRAWING CAN BE RELEASED FOR FABRICATION ONLY AFTER SHEET-METAL SHOP STANDARDS HAVE BEEN REVIEWED AND APPROVED.
14. SHEET-METAL SHOP DRAWINGS MUST BE COORDINATED WITH ALL TRADES (MECHANICAL, ELECTRICAL, PLUMBING, FIRE PROTECTION, STRUCTURAL ETC.) BEFORE FABRICATION.
15. CONTRACTOR TO COORDINATE DUCT LOCATIONS WITH STRUCTURAL STEEL AND ARCHITECTURAL DRAWINGS OF THE AREA.
16. PROVIDE BRANCH CONNECTION TAPS AS INDICATED IN DETAIL ON DETAIL DRAWINGS. ANY OTHER TAP BRANCH CONNECTIONS ARE NOT ACCEPTABLE.
17. ALL DUCT SIZES, SHOWN ARE INSIDE CLEAR DIMENSIONS.
18. ALL CONDENSATE DRAIN LINES FROM EACH UNIT WILL BE PIPED FULL SIZE OF THE DRAIN OUTLET WITH P-TRAP AND TERMINATED AT THE NEAREST DRAIN OR SLOP SINK. PROVIDE A CONDENSATE PUMP SIMILAR TO LITTLE GIANT VCC-20ULS IF GRAVITY DRAINAGE CANNOT BE UTILIZED. COORDINATE WITH ELECTRICAL CONTRACTOR AS REQUIRED.
19. ALL EQUIPMENT, PIPING, DUCTWORK, ETC. SHALL BE INDEPENDENTLY SUPPORTED AS DETAILED AND SPECIFIED. ADDITIONAL SUPPORT SHALL BE PROVIDED AS REQUIRED TO PROVIDE VIBRATION-FREE INSTALLATION.
20. ALL CONTROL WIRE AND CONDUIT SHALL COMPLY WITH ELECTRICAL PROJECT SPECIFICATIONS.
21. PROVIDE AS REQUIRED BY CODE (LOCAL OR NATIONAL) ANY ADDITIONAL ACCESS PANELS, OR SPECIAL SUPPORTS NOT SHOWN ON PLANS AT NO ADDITIONAL COST TO OWNER.
22. ANY ABANDONED EXISTING EQUIPMENT, DUCTWORK, ETC. WHICH IS NOT SHOWN TO BE REMOVED, BUT INTERFERES WITH THE NEW CONSTRUCTION IS TO BE REMOVED BY THE CONTRACTOR.
23. THE CONTRACTOR SHALL REMOVE, RELOCATE, REPLACE, ADJUST, ADAPT AND MODIFY EXISTING EQUIPMENT AND/OR SYSTEM AS REQUIRED BY THE DRAWINGS OR SPECIFICATIONS AND AS MAY BE REQUIRED WHEN SUCH WORK IS UNCOVERED AND FOUND TO INTERFERE WITH THE COMPLETION OF WORK IN THE CONTRACT WITHOUT ADDITIONAL COST TO THE OWNER.
24. THE CONTRACTOR IS TO BALANCE ALL DUCT SYSTEMS AND PROVIDE ALL NECESSARY BELTS, PULLEYS, SHEAVES, ETC TO ACHIEVE THE DESIGN AIR QUANTITIES. NEWLY DESIGNED AREAS SHALL BE BALANCED TO THE INDICATED AIR QUANTITIES ON THE DRAWINGS. ALL EXISTING AREAS SHALL BE RE-BALANCED TO THE ORIGINAL DESIGN REQUIREMENTS. ALL BALANCED AIR QUANTITIES ARE TO BE WITHIN 5% OF DESIGN AIR QUANTITIES.
25. ALL SQUARE ELBOWS ON DUCTWORK ARE TO HAVE DOUBLE THICK TURNING VANES.
26. UL LISTED FIRESTOP ASSEMBLIES SHALL BE INSTALLED AT ALL PENETRATIONS OF FIRE RATED CONSTRUCTION.
27. AFTER FINAL TESTS AND ADJUSTMENTS, FULLY INSTRUCT OWNER'S OPERATING PERSONNEL IN ALL DETAILS OF OPERATION FOR EQUIPMENT INSTALLED. A SIGNED RECEIPT WHICH SHALL BE OBTAINED FROM THE OPERATOR SHALL BE CONSTRUED AS EVIDENCE THAT INSTRUCTIONS WERE SATISFACTORY.
28. FURNISH TWO (2) COPIES OF WRITTEN DESCRIPTIONS OF ALL SYSTEMS COVERING ALL MANUAL OPERATING PROCEDURE, AUTOMATIC CONTROL DESCRIPTIONS AND AUTOMATIC CONTROL TEMPERATURE AND PRESSURE SETTINGS. WRITTEN DESCRIPTIONS SHALL INCLUDE LUBRICATION SCHEDULES, PARTS LISTS, PERFORMANCE SERVICES FOR EQUIPMENT, FILTER SIZE / QUANTITY SCHEDULE, ETC. WHEN MANUFACTURER'S STANDARD INSTRUCTIONS, ARE UTILIZED, THEY SHALL BE CLEARLY MARKED TO INDICATE APPLICABILITY.
29. CONTRACTOR IS RESPONSIBLE FOR THE TESTING & COMMISSIONING OF ALL HVAC SYSTEMS IN THE PRESENCE OF UNIT MANUFACTURER.
30. ALL DUCTWORK & PIPING TO BE LABELED AS REQUIRED BY BUILDING STANDARDS.

DRAWING LIST

Table with columns for Drawing ID and Description. Includes entries: M-001 MECHANICAL NOTES, SYMBOLS AND DRAWING LIST; M-011 MECHANICAL DEMOLITION PLAN; M-101 MECHANICAL PLAN; M-401 MECHANICAL DETAILS (SHEET 1 OF 2); M-402 MECHANICAL DETAILS (SHEET 2 OF 2); M-501 MECHANICAL HOOD DRAWINGS (SHEET 1 OF 4); M-502 MECHANICAL HOOD DRAWINGS (SHEET 2 OF 4); M-503 MECHANICAL HOOD DRAWINGS (SHEET 3 OF 4); M-504 MECHANICAL HOOD DRAWINGS (SHEET 4 OF 4); M-601 MECHANICAL SPECIFICATIONS (SHEET 1 OF 3); M-602 MECHANICAL SPECIFICATIONS (SHEET 2 OF 3); M-603 MECHANICAL SPECIFICATIONS (SHEET 3 OF 3).

COORDINATION NOTES

- 1. COORDINATE ALL WORK WITH THE ARCHITECTURAL DRAWINGS. VERIFY LOCATION OF ALL VISIBLE DEVICES WITH ARCHITECT OR OWNER PRIOR TO INSTALLATION, INCLUDING THERMOSTATS, DIFFUSERS, GRILLES, REGISTERS, ETC. RECEIVE APPROVAL FROM THE ARCHITECT OR OWNER FOR FINISH COLOR AND MOUNTING FRAME PRIOR TO PURCHASE. RECEIVE APPROVAL FROM THE ARCHITECT FOR ALL DEVICES PRIOR TO PURCHASE.
2. SHOP DRAWING NOTES:
A. ALL MECHANICAL SHOP DRAWINGS SHALL BE SUBMITTED TO DESIGN ENGINEER
B. SUBMIT CAD AS-BUILT SHEETMETAL DRAWINGS (UPDATED WITH COMMENTS) FOR THE RECORD AT COMPLETION OF INSTALLATION TO DESIGN ENGINEER
C. SUBMIT AIR BALANCING REPORT TO DESIGN ENGINEER

CODES, PERMITS, AND INSPECTIONS

- 1. ALL WORK SHALL MEET OR EXCEED LATEST REQUIREMENT OF THE LATEST EDITION OF THE 2023 FLORIDA BUILDING CODE, 2023 FLORIDA MECHANICAL CODE, 2023 SARASOTA CDM, 2023 FLORIDA ENERGY CONSERVATION CODE AND OTHER AUTHORITIES EXERCISING JURISDICTION OF THE WORK OF THIS PROJECT.
2. SECURE PERMITS AND INSPECTION CERTIFICATES AND TRANSMIT SAME TO THE OWNER AT THE COMPLETION OF THE WORK.
3. CONTRACTOR SHALL BE RESPONSIBLE FOR FILING ALL DOCUMENTS WITH ALL RESPONSIBLE AGENCIES. CONTROLLED INSPECTION SHALL BE DONE BY CONTRACTOR.


ENV ARCHITECTURE + DESIGN

180 SYLVAN AVENUE, SUITE 3 ENGLEWOOD CLIFFS, NJ 07632 TEL 201 | 894 | 1000 ENV-team.com

CLIENT: SSSP AMERICA 20408 BASHAN DRIVE SUITE 300 ASHBURN, VA 20147

PROJECT TEAM: ARCHITECT: ENVIRONETICS GROUP ARCHITECTS 180 SYLVAN AVE. ENGLEWOOD CLIFFS, NJ 07632

MEP ENGINEER: GUTH DECONZO CONSULTING ENGINEERS, PC 520 8TH AVENUE, SUITE 2201 NEW YORK, NY 10018 CERTIFICATE OF AUTHORIZATION CA LIC. NO. 27747



John J. Guth, PE FL LIC# 60427

B-FB4 - WAHLBURGERS SARASOTA BRADENTON INTERNATIONAL 6000 AIRPORT CIRCLE SARASOTA, FL 34243 CLIENT: SSP AMERICA

Table with columns: REV, DATE, DESCRIPTION. Includes entry: DESIGN DELIVERABLE: ISSUE DATE: 08/16/2024 ISSUED FOR PERMIT

PROJECT NUMBER: 24017G DRAWN BY: CHECKED BY:

Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE:

MECHANICAL NOTES, SYMBOLS AND DRAWING LIST


SHEET NUMBER: M-001



CLIENT:  
**SSP AMERICA**  
20408 BASHAN DRIVE  
SUITE 300  
ASHBURN, VA 20147

PROJECT TEAM:  
ARCHITECT:  
ENVIRONETICS GROUP ARCHITECTS  
180 SYLVAN AVE.  
ENGLEWOOD CLIFFS, NJ 07632


MEP ENGINEER  
GUTH DECONZO CONSULTING  
ENGINEERS, PC  
520 8TH AVENUE, SUITE 2201  
NEW YORK, NY 10018  
CERTIFICATE OF AUTHORIZATION  
CA LIC. NO. 2747





**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA

### DEMOLITION NOTES

1. THE CONTRACTOR SHALL VISIT THE PREMISES TO DETERMINE EXISTING CONDITIONS AND COMPARE SAME WITH CONTRACT DRAWINGS AND SPECIFICATIONS. THE CONTRACTOR IS TO SATISFY HIMSELF OF ALL CONDITIONS PRIOR TO THE SUBMISSION OF A BID PROPOSAL FOR DEMOLITION. NO ALLOWANCE WILL BE MADE FOR FAILURE TO COMPLY WITH THESE REQUIREMENTS AND A BID PROPOSAL SHALL BE CONSTRUED AS EVIDENCE HE HAS DONE SO.
2. ANY EXISTING EQUIPMENT, DUCTWORK, AC UNITS, ETC. WHICH IS NOT SHOWN TO BE REMOVED, BUT INTERFERES WITH THE NEW CONSTRUCTION IS TO BE REMOVED BY THE CONTRACTOR AT NO ADDITIONAL COST.
3. THE CONTRACTOR, PRIOR TO THE REMOVAL AND DEMOLITION WORK IS TO INFORM THE OWNER OF THE ITEMS BEING REMOVED AND TO DETERMINE IF THE OWNER WOULD LIKE TO TAKE POSSESSION OF IT.
4. CONTRACTOR SHALL DEMOLISH ALL HVAC EQUIPMENT, DUCTWORK AND APPURTENANCES IN THE SPACE & ASSOCIATED CONDENSING UNITS AS INDICATED ON THESE PLANS.
5. SHOULD ANY QUESTION ARISE AS TO WHETHER OR NOT ANY PIPING, EQUIPMENT OR OTHER ITEM SHOULD BE REMOVED, OR REMAIN AS PRESENTLY INSTALLED, THIS CONTRACTOR SHALL REQUEST, IN WRITING, CLARIFICATION FROM THE ARCHITECT.
6. ANY DEMOLITION OF EXISTING EQUIPMENT SHALL INCLUDE THE REMOVAL OF THEIR RELATED CONTROLS AND CONTROL WIRING, SUPPORTS, DUCTWORK, PIPING, ALL CORRESPONDING ACCESSORIES AND PARTS, DUCTWORK AND ELECTRICAL POWER SUPPLY.
7. REMOVAL SHALL INCLUDE TAKING FROM THE PREMISES AND DISPOSAL OF REMOVED ITEMS TO THE LOCATION INDICATED BY THE OWNER OR BUILDING, UNLESS OTHERWISE NOTED.
8. THIS CONTRACTOR SHALL CAP ALL REMAINING DUCTS, AT ALL POINTS OF DISCONNECTION, AIRTIGHT.
9. THIS CONTRACTOR SHALL BE RESPONSIBLE FOR HIS WORK WITH ITS COMPLETION AND FINAL ACCEPTANCE AND SHALL REPLACE ANY OF THE SAME WHICH MAY BE DAMAGED, LOST OR STOLEN WITHOUT ADDITIONAL COST TO THE OWNER.
10. BEFORE PROCEEDING WITH ANY WORK IN OCCUPIED OR USED AREAS, THE CONTRACTOR SHALL APPLY TO THE OWNER OF BUILDING FACILITY ENGINEERS FOR PERMISSION TO ENTER SUCH AREAS. THE CONTRACTOR IS OBLIGED TO PERFORM HIS WORK ONLY AT THE TIME OR TIMES DESIGNATED BY THE OWNER OR BUILDING FACILITY ENGINEERS. THERE WILL BE NO ADDITIONAL COMPENSATION FOR THE WORK PERFORMED AFTER HOURS OR ON OFF-DAYS WITHOUT PRIOR WRITTEN APPROVAL.
11. THIS CONTRACTOR SHALL BE RESPONSIBLE FOR THE FAILURE OF ANY DUCTWORK SYSTEM OR EQUIPMENT TO FUNCTION PROPERLY UPON COMPLETION OF HIS WORK UPON SAID SYSTEM OR EQUIPMENT.
12. DEMOLITION AND OTHER WORK WHICH CREATES DIRT AND/OR DISTURBING NOISE, MUST BE PERFORMED AT THE TIME AND MANNER DIRECTED BY THE OWNER OR BUILDING FACILITY ENGINEERS. THE DELIVERY, HANDLING AND INSTALLING OF MATERIALS, EQUIPMENT AND DEBRIS MUST BE ARRANGED TO AVOID ANY INCONVENIENCE AND ANNOYANCE TO THE BUILDING AND OPERATION. CLEANING MUST BE CONTROLLED TO PREVENT DIRT AND DUST FROM INFILTRATING INTO ADJACENT TENANT OR MECHANICAL AREAS. WELDING OR BURNING MUST BE PERFORMED ONLY DURING TIMES SPECIFICALLY APPROVED BY THE FACILITIES AND MAINTENANCE ENGINEERS.
13. ALL RETURN AIR DUCT OPENINGS SHALL BE COVERED WITH TEMPORARY FILTERS (MIN MERV-8) DURING THE DEMOLITION. FILTERS TO BE CHECKED AND REPLACED PERIODICALLY, CONTRACTOR TO LOG DATES OF FILTER REPLACEMENT.
14. PROVIDE PLUGS FOR ALL PIPING TAKE-OFFS WHERE THE BRANCH PIPING IS TO BE REMOVED.
15. CONTRACTOR RESPONSIBLE TO REPAIR/REPLACE ANY MISSING OR DAMAGED INSULATION ON ANY EXISTING DUCT OR PIPING IN THE SPACE WHETHER UTILIZED IN THIS DESIGN OR NOT.
16. PATCH ALL SURFACES DISTURBED OR LEFT UNFINISHED BY THIS WORK TO MATCH ADJACENT SURFACES.



**MECHANICAL DEMOLITION PLAN**  
SCALE: 1/4" = 1'-0




|  |  |
|--|--|
|  |  |
|  |  |
|  |  |
|  |  |
|  |  |
|  |  |
|  |  |
|  |  |

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: DESIGN  
ISSUE DATE: 08/16/2024  
ISSUED FOR PERMIT  
PROJECT NUMBER: 24017G  
DRAWN BY:  
CHECKED BY:

Copyright (c) by Environetix, Inc. All Rights Reserved.  
SHEET TITLE:  
**MECHANICAL DEMOLITION PLAN**

SHEET NUMBER:  
**M-011**



John J. Guth, PE  
FL LIC# 60427

**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA

**MECHANICAL PIPING PLAN NOTES**

- VERIFY SUFFICIENT ACCESS TO ALL PIPING ACCESSORIES.
- FIRESTOP ALL PENETRATIONS OF RATED CONSTRUCTION AS REQUIRED TO MAINTAIN RATING.
- PROVIDE HIGH POINT VENTS AND LOW POINT DRAINS
- AT ALL CONNECTIONS TO EXISTING WORK, CONTRACTOR TO PROVIDE AN ADDITIONAL VALVED AND CAPPED PIPE FULL SIZE OF NEW CONNECTION FOR FUTURE USE.
- PROVIDE ISOLATION VALVE FOR ALL BRACH TAKEOFFS OF MAIN PIPING AS WELL AS ON EACH SIDE OF EQUIPMENT OR ACCESSORIES AS REQUIRED FOR SERVICING.
- FOR COIL PIPING CONNECTIONS, REFER TO COIL PIPING DETAIL ON DRAWING M-402.
- FOR CONNECTION TO EXISTING SYSTEM, CONTRACTOR TO VERIFY WATER CHEMISTRY OF EXISTING SYSTEM AND FILL NEW PIPING TO MATCH. CONTRACTOR TO PERFORM WATER CHEMISTRY TEST TO VERIFY AMOUNT OF GLYCOL, ETC AS REQUIRED.

**MECHANICAL PLAN NOTES**

- CONTRACTOR RESPONSIBLE TO REPAIR/REPLACE ANY MISSING OR DAMAGED INSULATION ON ANY EXISTING DUCTWORK OR PIPING IN THE SPACE WHETHER UTILIZED IN THIS DESIGN OR NOT.
- REFER TO ARCHITECTURAL PLANS FOR EXACT LOCATION OF ALL AIR OUTLETS.
- PROVIDE FIRE DAMPER/FIRE SMOKE DAMPER AS REQUIRED ON ALL NEW DUCTWORK PENETRATIONS OF RATED PARTITIONS. COORDINATE WITH ARCHITECTURAL DRAWINGS. PROVIDE FIRE DAMPER/FIRE SMOKE DAMPER AS REQUIRED ON ALL EXISTING DUCTWORK PENETRATIONS OF NEW RATED CONSTRUCTION, SIZE TO MATCH EXISTING DUCT. REPLACE EXISTING DUCT AND PROVIDE DUCT TRANSITION AS REQUIRED FOR DAMPER INSTALLATION PERPENDICULAR TO RATED CONSTRUCTION.
- NEW WORK TO BE INSTALLED SO AS TO NOT IMPAIR ACCESS TO EXISTING CONDITIONS. PROVIDE ACCESS DOOR IN FINISHED CONSTRUCTION AS REQUIRED.
- ALL EQUIPMENT SHOWN AS EXISTING TO REMAIN IS TO BE REFURBISHED TO FULL WORKING ORDER. CONTRACTOR TO VERIFY OPERATION OF UNIT, ALL ASSOCIATED COMPONENTS, CONTROLS INTEGRATION, ETC. AND REPAIR/REPLACE AS REQUIRED TO BRING UNIT TO FULL WORKING ORDER.
- ALL BMS CONNECTIONS SHALL BE COORDINATED WITH SMAA PRIOR TO CONNECTION.

**AIR OUTLETS**

| SQUARE SUPPLY DIFFUSERS<br>(DESIGNATED "CD-A" ON PLAN) |  |
|--|--|
| MANUFACTURER   | - TITUS  |
| MODEL NO.  | - OMNI   |
| FINISH   | - AS PER ARCHITECTURAL REQUIREMENTS.   |
| FRAME TYPE   | - TO COORDINATE WITH LATEST ARCHITECTURAL REFLECTING CEILING AND CEILING GRID PLANS. |
| SIZE   | - 24x24  |
| SQUARE RETURN GRILLE<br>(DESIGNATED "RG-A" ON PLAN)    |  |
| MANUFACTURER   | - TITUS  |
| MODEL NO.  | - 350-RL   |
| FINISH   | - AS PER ARCHITECTURAL REQUIREMENTS.   |
| FRAME TYPE   | - TO COORDINATE WITH LATEST ARCHITECTURAL REFLECTING CEILING AND CEILING GRID PLANS. |
| SIZE   | - SEE PLANS  |
| SQUARE RETURN GRILLE<br>(DESIGNATED "RG-B" ON PLAN)    |  |
| MANUFACTURER   | - TITUS  |
| MODEL NO.  | - PAR  |
| FINISH   | - AS PER ARCHITECTURAL REQUIREMENTS.   |
| FRAME TYPE   | - TO COORDINATE WITH LATEST ARCHITECTURAL REFLECTING CEILING AND CEILING GRID PLANS. |
| SIZE   | - SEE PLANS  |

**DESIGN OUTSIDE AIR VENTILATION RATE**

BASED ON 2023 FLORIDA MECHANICAL CODE TABLE 403.3.1.1


| SPACE   | TOTAL AREA (SQ FT) | OCCUPANT DENSITY (#/SQ FT) | OCCUPANTS (PEOPLE) | PEOPLE OA RATE (CFM/PERSON) | OCCUPANTS REQUIRED OA (CFM) | AREA OA RATE (CFM/SQ FT) | AREA REQUIRED OA (CFM) | TOTAL REQUIRED OA (CFM) | TOTAL OA PROVIDED (CFM) |
|---------|--------------------|----------------------------|--------------------|-----------------------------|-----------------------------|--------------------------|------------------------|-------------------------|-------------------------|
| FOH     | 525                | -                          | 22                 | 7.5                         | 165                         | 0.18                     | 94.5                   | 260                     | 260                     |
| BOH     | 140                | -                          | 2                  | 7.5                         | 15                          | 0.18                     | 25.2                   | 40.2                    | 41                      |
| KITCHEN | 125                | -                          | 2                  | 7.5                         | 112.5                       | 0.12                     | 117                    | 229.5                   | 230                     |

OUTSIDE AIR PROVIDED AT 14% OF TOTAL SUPPLY AIR.  
KITCHEN VENTILATION PROVIDED VIA TRANSFER AIR.


**FAN COIL UNIT SCHEDULE**

| DESIGNATION | CFM H/M/L    | NOMINAL TONS | COOLING DATA        |                        |           |          |     |              | MOTOR POWER HP | ESP IN WG | ELEC. HT KW | STAGES | VOLTS/PHASE/HZ | FLA (A) | MCA (A) | OPERATING WEIGHT, LBS | MODEL NO. | MNFN    | DIMENSIONS (W"xH"xD")   |
|-------------|--------------|--------------|---------------------|------------------------|-----------|----------|-----|--------------|----------------|-----------|-------------|--------|----------------|---------|---------|-----------------------|-----------|---------|-------------------------|
|             |              |              | CAPACITY, MBH TOTAL | CAPACITY, MBH SENSIBLE | COIL ROWS | EWTL/LWT | GPM | W/PD FT. H2O |                |           |             |        |                |         |         |                       |           |         |                         |
| FCU-BOH     | 1000/900/800 | 3.0          | 36.3                | 25.7                   | 6         | 44/58    | 5.2 | 5.8          | 1/2            | 0.5       | 4           | 2      | 208/3/60       | 13.1    | 16.3    | 285                   | 42DHE10   | CARRIER | 37" x 21-1/2" x 37-1/2" |
| FCU-FOH/BAR | 1000/900/800 | 3.0          | 28.3                | 21.2                   | 6         | 44/58    | 4.0 | 3.9          | 1/2            | 0.5       | 4           | 2      | 208/3/60       | 13.1    | 16.3    | 285                   | 42DHE10   | CARRIER | 37" x 21-1/2" x 37-1/2" |

- NOTES:
- CONTRACTOR TO PROVIDE LEAK DETECTOR WITHIN OVERFLOW DRAIN/ INTERLOCK OVERFLOW SWITCH WITH BMS FOR SHUT DOWN.
  - ACCESS TO BE PROVIDED RH/LH BASED ON FIELD ACCESS. ACCESS SHOWN ON PLAN TO BE CONFIRMED PRIOR TO RELEASE.
  - PROVIDE ECM MOTOR WITH VARIABLE SPEED.
  - PROVIDE THERMOSTAT CAPABLE OF INTERLOCK WITH EXISTING JOHNSON CONTROLS SYSTEM.
  - PROVIDE MIN. MERV8 FILTER.




**MECHANICAL PLAN**  
SCALE: 1/4" = 1'-0"



PROVIDE 2" PVC DIRECT VENT INTAKE/FLUE FOR HWH-1. TERMINATE AT ROOF LEVEL PER MANUFACTURERS INSTALLATION. MAINTAIN MIN. 24" BETWEEN INTAKE AND FLUE.

KITCHEN EXHAUST DUCT CONNECTION TO HOOD. PROVIDE FULL SIZE COLLAR CONNECTION.

KITCHEN EXHAUST DUCT UP TO ROOF MOUNTED EF. NEW FAN SHALL BE LOCATED ON EXISTING BASE BUILDING PROVIDED CURB. EXISTING CURB TO BE MODIFIED AS REQUIRED TO ACCOMMODATE NEW FAN. EXACT LOCATION TO BE VERIFIED IN FIELD. COORDINATE ROOF WORK WITH HOLDER OF WARRANTY SO AS TO NOT VOID SAID WARRANTY.



DESIGN DELIVERABLE: ISSUED FOR PERMIT  
ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G  
DRAWN BY:  
CHECKED BY:

Copyright (c) by Environetix, Inc. All Rights Reserved.  
SHEET TITLE:  
**MECHANICAL PLAN**  
SHEET NUMBER:  
**M-101**


3M FURE BARRIER DUCT WRAP

NOT TO SCALE

3M<sup>™</sup> Fire Barrier Duct Wrap 615+ Commercial Kitchen Grease Duct Systems (Figure 3)

Field-Fabricated 2-Hour Access Door System

1. Access hole
2. 1/4" (6.35mm) dia. by a minimum 6" (152.4mm) all-threaded rods
3. Access door cover – 16 gauge
4. Insulation pins (impaling pins) – welded (optional)
5. First layer 3M<sup>™</sup> Fire Barrier Duct Wrap 615+ cut same size as cover
6. Second layer 3M<sup>™</sup> Fire Barrier Duct Wrap 615+ with 1" (25.4mm) overlap on all sides
7. Third layer 3M<sup>™</sup> Fire Barrier Duct Wrap 615+ with 1" (25.4mm) overlap on all sides
8. Speed clips (optional)
9. Aluminum tape covering all exposed edges
10. 4" (102mm) long steel hollow tubing to fit threaded rods
11. 1/4" (6.35mm) diameter wings nuts and 1/4" (6.35mm) washers




*Note: System integrity is limited by quality of installation. Consult current independent testing laboratories (e.g., Intertek, UL) for Design or System Details. In all four overlap techniques the perimeter overlap can occur at any location on the duct.*


3M<sup>™</sup> Fire Barrier Duct Wrap 615+ Hanging Support Details for Fire-Rated Ductwork (Figure 10)

Note: To facilitate the application of 3M Fire Barrier Duct Wrap 615+ so that the rods & trapeze hangers are outside the wrap envelope, the following dimensions are recommended:

- |                                   | 1-layer    | 2-layer    |
|-----------------------------------|------------|------------|
| 1. Rod-to-bare duct clearance (Y) | 4" (102mm) | 6" (152mm) |
| 2. Added rod length (X)           | 2" (51mm)  | 4" (102mm) |




*Note: System integrity is limited by quality of installation. Consult current independent testing laboratories (e.g., Intertek, UL) for Design or System Details.*



METHOD OF HANGING DUCTWORK


NOT TO SCALE



- NOTE:**
- DISTANCE BETWEEN DUCT HANGERS SHALL BE IN ACCORDANCE WITH RS-13-3 OF THE NYC BUILDING CODE.
  - ALL FIREPROOFING WHICH HAS BEEN DAMAGED OR REMOVED DUE TO SCOPE OF WORK SHALL BE REPAIRED AND REPLACED.

BRANCH DUCT VOLUME DAMPERS


NOT TO SCALE



- NOTES:**
1. PROVIDE ALL BRANCH DUCTS WITH MANUALLY OPERATED VOLUME DAMPERS FOR BALANCING AIR SYSTEMS. THESE DAMPERS SHALL BE INDEPENDENT OF DAMPERS FURNISHED WITH DIFFUSERS AND REGISTERS, WHICH SHALL ONLY BE UTILIZED FOR TRIM BALANCING WITHOUT GENERATING NOISE.
  2. FOR DUCTS WIDER THAN 48" USE MULTIPLE SINGLE LEAF DAMPERS OR OPPOSED-ACTION MULTI-BLADE DAMPERS; EACH WITH LOCKING QUADRANT REGULATOR.

FIRE DAMPER INSTALLATION TYPE "B" FOR MAIN OR BRANCH DUCT

NOT TO SCALE




- FIRE DAMPER NOTES:**
1. FIRE RESISTANCE RATING OF FIRE DAMPERS SHALL COMPLY WITH NFPA 90A, AND UL 555 FIRE DAMPERS SHALL BE RATED TO MAINTAIN THE RATING OF THE FIRE SEPARATION.
  2. FIRE DAMPERS SHALL BE APPROVED FOR THIS INSTALLATION BY ALL AUTHORITIES WITH JURISDICTION AND LABELED BY UNDERWRITERS LABORATORIES (UL). THE DAMPER SHALL BE SUBMITTED TO ENGINEER FOR REVIEW.
  3. FIRE DAMPERS MUST BE DYNAMIC RATED TYPE.
  4. FIRE DAMPERS PLACED IN VERTICAL POSITION SHALL BE GRAVITY-OPERATED. FIRE DAMPERS PLACED IN HORIZONTAL POSITION SHALL BE PROVIDED WITH ALL NECESSARY SPRINGS AND LATCHES.
  5. TEMPERATURE RATING OF FUSIBLE LINK SHALL BE 165°F UNLESS OTHERWISE NOTED
  6. FOR WALL/PARTITIONS HAVING A FIRE RESISTANCE RATING OF LESS THAN 2 HOURS: FIRE DAMPERS SHALL BE RUSKIN MODEL D-18D2: STYLE A, B & C, GREENHECK MODEL DFD-150, TYPE A, B, C & CR, DFD-155, TYPE C & CR, IMPERIAL IDL MODEL FD 110, FD 150, TYPE A, B, C & CR, PREFCO/HUGH RICHARDS INC. MODEL UL 75A, OR APPROVED EQUAL. THEY SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURERS APPROVED INSTALLATION INSTRUCTIONS. SEE ARCHITECTURAL DWG.
  7. FOR WALL/PARTITIONS HAVING A FIRE RESISTANCE RATING OF 2 HOURS: FIRE DAMPERS SHALL BE RUSKIN MODEL D-18D23: STYLE A, B & C, GREENHECK MODEL DFD-350, TYPE A, B, C & CR, DFD-355, TYPE C & CR, IMPERIAL IDL MODEL FD 310, FD 350, TYPE A, B, C & CR, PREFCO/HUGH RICHARDS INC. MODEL UL 75L, OR APPROVED EQUAL. THEY SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURERS APPROVED INSTALLATION INSTRUCTIONS.
  8. FIRE DAMPER SLEEVE SHALL BE 16 GAUGE FOR DAMPERS WITH DIMENSIONS NOT EXCEEDING 24 IN. IN HEIGHT OR 36 IN. IN WIDTH, AND 14 GAUGE FOR LARGER SIZES. SLEEVE THICKNESS MUST NOT BE LESS THAN THE GAUGE OF THE CONNECTING DUCT. FIRE DAMPER SLEEVES THROUGH HOLLOW FIRE-RATED CONSTRUCTION BE MADE OF AT LEAST 14 GAUGE SHEET METAL.
  9. DUCT TO DAMPER SLEEVE CONNECTIONS SHALL BE BREAKAWAY STYLE. RECTANGULAR DUCTS MUST USE ONE OR MORE OF THE FOLLOWING CONNECTIONS: "S" SLIP, OR OTHER SLIP TYPE, MODIFIED DUCTMATE TYPES (PLASTIC CLEATS, NO CORNER BOLTS), OR MODIFIED PROPRIETARY TDC BY LOCKFORMER, OR TDF BY EAGLE FLANGE SYSTEM (NO CORNER BOLTS). ROUND AND OVAL DUCTS MUST USE A 4 IN. WIDE DRAWBAND CONNECTION. ALL THE CONNECTIONS SHALL BE LISTED IN UL 555 AND DEPICTED IN THE SMACNA FIRE, SMOKE AND RADIATION DAMPER INSTALLATION GUIDE.
  10. DAMPER SLEEVES SHALL NOT EXTEND MORE THAN 6 IN. BEYOND THE FIRE WALL OR PARTITION UNLESS FIRE DAMPER IS EQUIPPED WITH A FACTORY INSTALLED ACCESS DOOR. SLEEVE MAY EXTEND UP TO 16 IN. BEYOND THE FIRE WALL OR PARTITION ON SIDES EQUIPPED WITH FACTORY INSTALLED ACCESS DOOR.
  11. MOUNTING ANGLES SHALL BE A MINIMUM OF 1-1/2"x1-1/2"x14 GAUGE AND FASTENED TO SLEEVE WITH NO. 10 SHEET METAL SCREWS, 1/4" BOLTS AND NUTS, 1/2" LONG WELDS, OR 3/16" STEEL POP RIVETS. SECURE SLEEVES BY PERIMETER ANGLES ON FOUR SIDES OF THE SLEEVE ON BOTH SIDES OF OPENING.
  12. PROVIDE ACCESS DOORS ON EITHER SIDE OF THE SLEEVE ONLY TO PERMIT INSPECTING, TESTING AND RESETTING THE DAMPERS.
  13. CEILING FIRE DAMPERS SHALL BE SUITABLE FOR INSTALLATION INSIDE DUCT AND SURFACE MOUNTING OF DIFFUSERS OR GRILLES. CEILING FIRE DAMPERS SHALL BE RUSKIN CFD, CFDR, GREENHECK MODEL CRD-1, CRD-2, IMPERIAL IDL MODEL 410, 420, 420R, PREFCO MODEL 5680, 5680 OR APPROVED EQUAL FOR WALL/PARTITIONS HAVING A FIRE RESISTANCE RATING OF LESS THAN 3 HOURS. CEILING FIRE DAMPERS SHALL BE RUSKIN CFD, CFDR, GREENHECK MODEL CRD-1, CRD-2, IMPERIAL IDL MODEL 410, 420, 420R, PREFCO MODEL 5610, 5680, OR APPROVED EQUAL FOR WALL/PARTITIONS.

- NOTE:**
- ALL FIRE DAMPERS SHALL BE UL LISTED AND INSTALLED PER MANUFACTURERS INSTALLATION INSTRUCTIONS.


UPBLAST POWER FAN KITCHEN EXHAUST - ROOF CURB

NOT TO SCALE



PROVIDE FIRE SAFING FOR 18\"/>

- NOTES:**
1. UNIT TO BE PROVIDED WITH FACTORY WIRED DISCONNECT SWITCH.
  2. PROVIDE SOUND ATTENUATING ROOF CURBS IF INDICATED IN SPECIFICATIONS OR DRAWINGS.



John J. Guth, PE FL LIC# 60427

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: PERMIT ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G DRAWN BY:


CHECKED BY: Copyright (c) by Environetix, Inc. All Rights Reserved.

SHEET TITLE: MECHANICAL DETAILS (SHEET 1 OF 2)

SHEET NUMBER: M-401


TYPICAL AUXILIARY DRIP PAN DETAIL

NOT TO SCALE



CHILLED WATER FAN COIL UNIT PIPING


NOT TO SCALE



INTERPRETATION OF SINGLE LINE DUCTWORK

NOT TO SCALE

| WHERE DUCTWORK IS SHOWN SINGLE LINE, FOLLOWING SHALL APPLY FOR ACTUAL DUCT CONSTR. |  |
|--|--|
| SINGLE LINE  | ACTUAL CONSTRUCTION  |
| TEE<br>CONVERGING<br>AIR DIVERGING   | VOLUME DAMPER<br>TURNING VANES   |
| ELBOW  | TURNING VANE (EITHER TYPE ELBOW AT CONTR. OPTION-SUBJECT TO SPACE CONDITIONS). VANES SHALL BE WELDED TO RUNNERS. USE LARGE RADIUS VANES. MAXIMUM UNSUPPORTED VANE LENGTH SHALL NOT EXCEED 36". |
| (BRANCH AIR FLOW 25% OR HIGHER)<br>SPLIT OR TAKE-OFF                               | TURNING VANES<br>VOLUME DAMPER IN SHORTER BRANCH.<br>SQUARE THROAT ELBOW OPTION  |
| (BRANCH TAP 25% OR OR LESS AIR FLOW)<br>TAP TAKE-OFF                               | SIDE TAP BRANCH SHALL BE LIMITED TO 25% OF MAIN AIR FLOW<br>VOLUME DAMPER<br>45°   |
| RISE OR DROP   | OFFSET IN VERTICAL PLANE SHALL BE MADE WITH SMOOTH FITTINGS AND HAVE EQUAL CROSS SECTIONAL AREAS.  |
| HORIZONTAL OFFSET  | OFFSET IN HORIZONTAL PLANE SHALL BE MADE WITH SMOOTH FITTINGS AND HAVE EQUAL CROSS SECTIONAL AREAS.  |
| FD&AD<br>FIRE RATED WALL<br>FIRE DAMPER  | ACCESS DOOR IN DUCT<br>FIRE DAMPER<br>SEE DETAILS AND SPECIFICATIONS.  |



John J. Guth, PE  
FL LIC# 60427

**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**

6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |

DESIGN DELIVERABLE: ISSUED FOR PERMIT  
ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G  
DRAWN BY:  
CHECKED BY:

SHEET TITLE:  
**MECHANICAL  
DETAILS  
(SHEET 2 OF 2)**


SHEET NUMBER:  
**M-402**

| HOOD INFORMATION |           |            |  | HOOD DIMENSIONS (IN.) |       |        | COOKING LOAD / DUTY RATING |       | EXHAUST COLLAR(S) |      |      |      | SUPPLY  |        | HANGING WEIGHT |     | SECTION |          |
|------------------|-----------|------------|--|-----------------------|-------|--------|----------------------------|-------|-------------------|------|------|------|---------|--------|----------------|-----|---------|----------|
| HOOD NO.         | MARK      | MODEL      |  | LENGTH                | WIDTH | HEIGHT | TOTAL CFM                  | WIDTH | LENGTH            | DIA. | CFM  | S.P. | MUA CFM | AC CFM | CFM            | CFM | WEIGHT  | LOCATION |
| 1                | K1 - HOOD | XXEW-131-S |  | 131                   | 66    | 24     | 430 SS HEAVY               | 2456  | 9                 | 24   | 2456 | 0.58 |         |        |                |     | 457     | SINGLE   |

| HOOD INFORMATION |           |  |  | LIGHTING DETAILS |     | GREASE FILTRATION DETAILS |  |     | UTILITY CABINET(S) |          |             |      |       |          |
|------------------|-----------|--|--|------------------|-----|---------------------------|--|-----|--------------------|----------|-------------|------|-------|----------|
| HOOD NO.         | MARK      |  |  | FIXTURE TYPE     | QTY | FOOT CANDLES              | TYPE / MODEL                                     | QTY | SIZE (IN.)         | LOCATION | FIRE SYSTEM | SIZE | MODEL | CONTROLS |
| 1                | K1 - HOOD |  |  | ROUND LED        | 3   | 72.29                     | X-TRACTOR (SPARK ARRESTOR INCL.) STAINLESS STEEL | 7   | 16                 | 20       |             |      |       |          |


**HOOD OPTIONS**  
UL 710 LISTED W/ OUT EXHAUST FIRE DAMPER - UL #R25625  
BACK INTEGRAL AIR SPACE - 3 IN WIDE  
LEFT NON-INTEGRAL AIR SPACE - 1 IN THICK - ZERO CLEARANCE  
RIGHT NON-INTEGRAL AIR SPACE - 1 IN THICK - ZERO CLEARANCE  
18 IN HIGH CEILING ENCLOSURES - FRONT LEFT - FIELD INSTALLED  
FACTORY MOUNTED EXHAUST COLLAR(S)  
PERFORMANCE ENHANCING LIP (PEL) TECHNOLOGY  
STANDING SEAM CONSTRUCTION FOR SUPERIOR STRENGTH

**SSP NATIONAL PROGRAM**  
PLEASE CONTACT:  
**PAUL WILKERSON**  
PAUL.WILKERSON@ACCUREX.COM  
(209)275-4425






PROJECT: 7/19/2024  
MARK: K1 - HOOD  
SSP - SRQ - WAHLBURGERS  
UL NSF  
ACCUREX NORTHERN CA - 2789  
PAUL WILKERSON  
PAUL.WILKERSON@ACCUREX.COM  
(209)275-4425

**ACCUREX**



Fire (piping/drops/nozzles/etc.) subject to change. As built's can be provided at time of order and included with product shipment



**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA

| REV                 | DATE              | DESCRIPTION |
|---------------------|-------------------|-------------|
| DESIGN DELIVERABLE: | ISSUED FOR PERMIT | 08/16/2024  |
| PROJECT NUMBER:     | 24017G            |             |
| CHECKED BY:         |                   |             |

SHEET TITLE:  
**MECHANICAL HOOD DRAWINGS (SHEET 1 OF 4)**  
SHEET NUMBER:  
**M-501**



ARCHITECTURE + DESIGN

180 SYLVAN AVENUE, SUITE 3  
ENGLEWOOD CLIFFS, NJ 07632  
TEL 201 | 894 | 1000

ENV-team.com

ENVIRONETICS GROUP ARCHITECTS, P.C.  
COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS  
RESERVED

CLIENT:


**SSP AMERICA**

20408 BASHAN DRIVE  
SUITE 300  
ASHBURN, VA 20147

PROJECT TEAM:

ARCHITECT:  
ENVIRONETICS GROUP ARCHITECTS  
180 SYLVAN AVE.  
ENGLEWOOD CLIFFS, NJ 07632

MEP ENGINEER  
GUTH DECONZO CONSULTING  
ENGINEERS, PC  
520 8TH AVENUE, SUITE 2201  
NEW YORK, NY 10018  
CERTIFICATE OF AUTHORIZATION  
CA LIC. NO. 27747



John J. Guth, PE  
FL LIC# 60427

**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**

6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA

FIRE SYSTEM INFORMATION


| MARK | MODEL                       | LOCATION       | FLOW POINTS |              | SUPPLY LINE | DETECTION    | MARK(S) PROTECTED BY FIRE SYSTEM |
|------|-----------------------------|----------------|-------------|--------------|-------------|--------------|----------------------------------|
|      |                             |                | HOODS       | PCU          |             |              |                                  |
| FS-1 | ANSUL R-102<br>WET CHEMICAL | REMOTE MOUNTED | 14 UTILIZED | 22 AVAILABLE | CONTINUOUS  | FUSIBLE LINK | K1 - HOOD SECTION 1              |

FIRE SYSTEM OPTIONS AND ACCESSORIES

- PRE-PIPE WITH FACTORY PARTS (INCLUDES PRE-PIPED HOOD(S) WITH DETECTION AND DISTRIBUTOR SUPPLIED PARTS)
- CHROME SLEEVES FOR FACTORY PROVIDED APPLIANCES DROPS - INCLUDED
- METAL BLOW-OFF CAPS - INCLUDED
- GAS VALVE - INCLUDED - MECHANICAL SHUTOFF VALVE, 2", (ANSUL) - PART# ANSULMECHSHUTOFFVALVE200
- HOOD SUPPRESSION TANK - INCLUDED - 6 GAL. - ((2) 3.0 TANK(S))
- REMOTE PULL STATION - STANDARD - FIELD INSTALLATION AT SINGLE POINT OF EGRESS

SSP NATIONAL PROGRAM  
PLEASE CONTACT:  
PAUL WILKERSON  
PAUL.WILKERSON@ACCUREX.COM  
(209)275-4425

ANSUL R102 (WET CHEMICAL) FIRE PROTECTION SYSTEM - MODEL FSSC



**NOTES:**

WET CHEMICAL FIRE PROTECTION SYSTEM TO BE ANSUL R-102, DESIGNED IN COMPLIANCE WITH UL 300 REQUIREMENTS.

VERIFICATION OF ALL COOKING EQUIPMENT MAKE, MODEL AND LOCATION REQUIRED FOR ALL FIRE PROTECTION SYSTEMS.

ALL FIRE SYSTEM PIPING IS STANDARDLY TO THE RIGHT END OF THE HOOD. JUNCTIONS SHALL BE LOCATED ON THE RIGHT END.


ANSUL AUTOMAN RELEASE TO BE LOCATED WITHIN 60" OF HOOD.

THE BASIC FIRE SYSTEM WILL INCLUDE THE FOLLOWING:

- GAS SHUT-OFF VALVE, IF REQUIRED, TO BE SUPPLIED BY MANUFACTURER (UP TO 2" DIAMETER AS STANDARD) AND INSTALLED BY A LICENSED PLUMBER.
- MICRO SWITCH TO BE SUPPLIED BY MANUFACTURER FOR CONNECTION TO, BUT NOT LIMITED TO, BUILDING ALARM SYSTEMS, EXHAUST AND SUPPLY FANS AND ELECTRICAL POWER SHUT-DOWN. FIELD WIRING AND CONNECTIONS TO BE PERFORMED BY A LICENSED ELECTRICIAN.

THE BASIC FIRE SYSTEM DOES NOT INCLUDE THE FOLLOWING:

- FULL DUMP TEST OTHER THAN THAT SPECIFIED FOR THE INSTALLATION MANUAL, OR TO SATISFY A STATE OR LOCAL CODE. PERMIT AND TESTING FEES ARE NOT INCLUDED UNLESS NOTED UNDER THE EQUIPMENT SCHEDULE FOR THE FIRE SYSTEM.
- MORE THAN TWO TRIPS TO THE JOBSITE OR SPECIAL TRANSPORTATION, OR OVERTRUCKING LOADS REQUIREMENTS IN REMOTE AREAS. NORMAL TRAVEL DISTANCE IS FIRST 50 MI. (50 KM) FROM OFFICE.
- SPECIAL CLASSES OR ADDITIONAL LABOR FOR ACCESS TO SECURITY SENSITIVE AREAS.
- INSTALLATION OF GAS SHUT-OFF VALVE.
- SPECIAL DRAWINGS REQUIRED TO SATISFY STATE OR LOCAL CODE, PLAN EXAMINATION FEES, PE OR FS APPROVAL STAMP.
- LINCOLN LABEL, GOVERNMENT LABEL, OR PREVAILING WAGES REQUIRED FOR FINAL FIELD HOOK-UP.
- ANY AND ALL ELECTRICAL COMPONENTS/CONNECTIONS REQUIRED TO SHUT DOWN FANS, SHUT-OFF DEVICE FOR ELECTRIC COOKING EQUIPMENT (SHUT-Trip BREAKERS, OR ACTIVATE AN ALARM SYSTEM, ETC).
- ANY DISMANTLING OR REASSEMBLY REQUIRED TO GAIN ACCESS TO THE FIRE SUPPRESSION PIPING LOCATED ON THE TOP OF THE HOOD.
- ROUGH-IN HIDDEN CONDUIT FOR REMOTE PULL STATION OR GAS VALVE (FLUSH MOUNTED PULL STATION).
- INSTALLATION OF MORE THAN (1) REMOTE PULL STATIONS OR DISTANCES GREATER THAN 30 FT (9.1 M).
- PARTS OR LABOR REQUIRED TO CORRECT PIPING DUE TO COOKING EQUIPMENT CHANGES OR DEVIATION FROM PLANS, OR ANY CHARGES FOR MISSING OR ADDITIONAL PARTS OTHER THAN THOSE INDICATED ON THE FIRE SUPPRESSION DETAIL.




**NOTES:**

- 1 DENOTES FIELD INSTALLATION.
- 2 DENOTES FACTORY INSTALLATION.
- 3 DO NOT USE BLACK WIRE OR SHUT-ACTION SWITCH IN NORMAL INSTALLATION. BLACK WIRE TO BE USED ONLY FOR EXTRANEOUS ALARM LIGHT CIRCUITS, ETC.

PROJECT: 7/19/2024  
SSP - SRQ - WAHLBURGERS  
MARK: FS-1

UL NSF  
Listed for use in commercial kitchens

ACCUREX NORTHERN CA - 2789  
PAUL WILKERSON  
PAUL.WILKERSON@ACCUREX.COM  
(209)275-4425



| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |


DESIGN DELIVERABLE: ISSUED FOR PERMIT  
ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G  
DRAWN BY:  
CHECKED BY:

Copyright (c) by Environetix, Inc. All Rights Reserved.

SHEET TITLE:  
**MECHANICAL HOOD DRAWINGS (SHEET 2 OF 4)**

SHEET NUMBER:  
**M-502**






| MARK |                     | ELECTRICAL CONTROL PACKAGE |                        | USER INTERFACE                |       | FANS CONTROLLED |     |           |      |      |          |            |       |             |                        |              |
|------|---------------------|----------------------------|------------------------|-------------------------------|-------|-----------------|-----|-----------|------|------|----------|------------|-------|-------------|------------------------|--------------|
| MARK | MODEL               | LOCATION                   | TYPE                   | LOCATION                      | FAN # | TYPE            | FAN | FAN MARK  | ZONE | CFM  | MOTOR HP | MOTOR VOLT | CYCLE | MOTOR PHASE | MOTOR STARTER IN PANEL | VFD IN PANEL |
| CC-1 | XKC-DCV-SB-10-1-1-0 | SHIP LOOSE ENCLOSURE       | FULL COLOR TOUCHSCREEN | FACE MOUNT ON CONTROL PACKAGE | 1     | EXHAUST         | E1  | K1.1 - EF | 1    | 2456 | 2        | 208        | 48    | 3           | NO                     | YES          |

**CONTROL FEATURES**  
HOOD LIGHT CONTROL  
TEMP SENSORS (FACTORY INSTALLED) - QTY: 1  
DRY FIRE CONTACTS - QTY: 1  
LIGHTS OFF DURING FIRE  
EXHAUST MAX DURING FIRE  
SUPPLY OFF DURING FIRE  
BMS INTEGRATION - BACNET MSTP




DOC NUMBER: ----  
CAUTION: UNIT MUST BE GROUNDED IN ACCORDANCE WITH N.E.C. POWER MUST BE OFF WHILE WIRING.  
ATTENTION: L'APPAREIL DOIT ÊTRE MIS À LA TERRE COMME EXIGÉ PAR LE CODE C.E. L'ALIMENTATION DOIT ÊTRE COUPÉE AVANT TOUTES OPÉRATIONS.  
COMMERCIAL APPLIANCE OUTLET CENTER  
ELECTRICAL RATINGS: 110-240V/1PHASE, 50-60HZ/2, 15A  
BASE FILE #E200016, NL FILE #E313951

WIRING DIAGRAM CODE: WDC#  
JOB NAME: SSP - SRQ - WAHLBURGERS REV2  
MODEL: XKC-DCV-SB-10-1-1-0  
SERIAL NUMBER: WDSNM  
MARK: CC-1



| ZONE CONFIGURATION |         |                     |           |         |         |                 |            |  |          | WIRING DIAGRAM CODE: WDC#                                     |                              |          |  |                            |  |  |  |  |  |
|--------------------|---------|---------------------|-----------|---------|---------|-----------------|------------|--|----------|---|------------------------------|----------|--|----------------------------|--|--|--|--|--|
| ZONE #             | ZONE    | ROOM TEMP           |           |         |         |                 |            |  |          | JOB NAME:   | SSP - SRQ - WAHLBURGERS REV2 |          |  | MODEL: XKC-DCV-SB-10-1-1-0 |  |  |  |  |  |
| 1                  | Z1      | PRESET              |           |         |         |                 |            |  |          | SERIAL NUMBER:  | WDSNM                        |          |  | MARK: CC-1                 |  |  |  |  |  |
| HOOD CONFIGURATION |         |                     |           |         |         |                 |            |  |          | PARAMETERS (PAR DEFALT)                                       |                              |          |  |                            |  |  |  |  |  |
| HOOD #             | HOOD    | HOOD MARK           | ZONE      | EXHAUST | SUPPLY  | MB-TEMP SENSORS | NCB        | FACTORY SETTINGS / CONFIGURATION: STANDARD |          |   | ZONE: 1                      |          |  | HOODS: 1                   |  |  |  |  |  |
| 1                  | H1      | K1 - HOOD SECTION 1 | Z1        | E1      |         | TS1             | NO         | EXHAUST FANS: 1                            |          |   | SUPPLY FANS: 0               |          |  | MB ROOM SENSORS: NO        |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | ZONE SETTINGS   |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | SEE ZONE CONFIGURATION IN TABLE ON LEFT                       |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | HOOD SETTINGS   |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | SEE HOOD CONFIGURATION IN TABLE ON LEFT                       |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | EXHAUST FAN SETTINGS  |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | SEE FAN CONFIGURATION IN TABLE ON LEFT                        |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | SUPPLY FAN SETTINGS   |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | SEE FAN CONFIGURATION IN TABLE ON LEFT                        |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | SENSOR SETTINGS   |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | SEE HOOD CONFIGURATION IN TABLE ON LEFT                       |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | USER INTERFACE SETTINGS (BMS, FAN & LIGHT BUTTONS - SEPARATE) |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | USER INTERFACE SETTINGS (BMS)                                 |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | GENERAL SETTINGS  |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | TIME ZONE: CENTRAL, DAYLIGHT (DEFAULT)                        |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | PREFABRISET SETTINGS  |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | POWER OFF DURING FIRE: MAX                                    |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | SUPPLY DURING FIRE: OFF                                       |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | LIGHTS DURING FIRE: OFF                                       |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | BMS SETTINGS  |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | BAUD RATE: 9600   |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | MAC ADDRESS: 0  |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | MAX MASTER: 127   |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | MAX IFC/FAN/RES: 20   |                              |          |  |                            |  |  |  |  |  |
|                    |         |                     |           |         |         |                 |            |  |          | FAN CONFIGURATION   |                              |          |  |                            |  |  |  |  |  |
| FAN #              | TYPE    | FAN                 | FAN MARK  | ZONE    | MIN CFM | MAX CFM         | MODBUS VFD | VFD ADDRESS                                | MIN FREQ | MAX FREQ  | MIN VOLT                     | MAX VOLT |  |                            |  |  |  |  |  |
| 1                  | EXHAUST | E1                  | K1.1 - EF | Z1      | 1028    | 2408            | YES        | 1  | 24       | 48  |                              |          |  |                            |  |  |  |  |  |



PROJECT: 8/15/2024  
SSP - SRQ - WAHLBURGERS REV2  
CC-1  
ACCUREX NORTHERN CA - 2799  
PAUL.WILKERSON@ACCUREX.COM  
(209)275-4425  
**ACCUREX**


| REV   | DATE              | DESCRIPTION |
|---|-------------------|-------------|
| DESIGN DELIVERABLE:                                     | ISSUED FOR PERMIT | 08/16/2024  |
| PROJECT NUMBER:   | 24017G            |             |
| DRAWN BY:   |                   |             |
| CHECKED BY:   |                   |             |
| Copyright (c) by Environetis, Inc. All Rights Reserved. |                   |             |

SHEET TITLE:  
**MECHANICAL HOOD DRAWINGS (SHEET 3 OF 4)**  
SHEET NUMBER:  
**M-503**

**ENV**  
 ARCHITECTURE + DESIGN  
 180 SYLVAN AVENUE, SUITE 3  
 ENGLEWOOD CLIFFS, NJ 07632  
 TEL 201 | 894 | 1000  
 ENV-team.com  
 ENVIRONETICS GROUP ARCHITECTS, P.C.  
 COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED

CLIENT:  
**SSP AMERICA**  
 20408 BASHAN DRIVE  
 SUITE 300  
 ASHBURN, VA 20147

PROJECT TEAM:  
 ARCHITECT:  
 ENVIRONETICS GROUP ARCHITECTS  
 180 SYLVAN AVE.  
 ENGLEWOOD CLIFFS, NJ 07632  
 MEP ENGINEER  
 GUTH DECONZO CONSULTING  
 ENGINEERS, PC  
 520 8TH AVENUE, SUITE 2201  
 NEW YORK, NY 10018  
 CERTIFICATE OF AUTHORIZATION  
 CA LIC. NO. 27747



**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA

|  |  |  |
|--|--|--|
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |

DESIGN DELIVERABLE: ISSUED FOR PERMIT  
 ISSUE DATE: 08/16/2024

PROJECT NUMBER: **24017G**  
 DRAWN BY:  
 CHECKED BY:

**MECHANICAL HOOD DRAWINGS (SHEET 4 OF 4)**

SHEET NUMBER: **M-504**

**SSP NATIONAL PROGRAM**  
 PLEASE CONTACT:  
**PAUL WILKERSON**  
**PAUL.WILKERSON@ACCUREX.COM**  
**(209)275-4425**

| MARK INFORMATION |           | FAN INFORMATION |              |                           |         |                      | MOTOR INFORMATION |           |          |           |           |          |          |
|------------------|-----------|-----------------|--------------|---------------------------|---------|----------------------|-------------------|-----------|----------|-----------|-----------|----------|----------|
| QTY              | MARK      | MODEL           | VOLUME (CFM) | TOTAL EXTERNAL SP (IN WG) | FAN RPM | OPERATING POWER (HP) | WEIGHT (LB.)      | SIZE (HP) | V/CP     | ENCLOSURE | MOTOR RPM | WINDINGS | NEC FLA* |
| 1                | K1.1 - EF | XCUE-160-A      | 2,456        | 1.4                       | 1,369   | 0.96                 | 115               | 2         | 208/60/3 | OP        | 1725      | 1        | 7.5      |

\*NEC FLA - Based on table 430.250 or 430.248 of National Electrical Code 2020. Actual motor FLA may vary for sizing thermal overload, consult factory"

**K1.1 - EF : SELECTED OPTIONS AND ACCESSORIES**

Motor VFD Rated without Shaft Grounding Protection  
 One piece fully welded windband  
 Tapered bushing wheel hub  
 Breather tube outlet area min. 4.4 sq. in. (sizes 99-480), 2.0 sq. in. (sizes 60-95)  
 Min. windband material thickness: 0.051" aluminum (060-240), 0.064" aluminum (240HP, 240XP), 0.080" aluminum (sizes 300-480)  
 Larger Curb Cap Size - 26 Square  
 UL/cUL 705 Listed - Supplement SC - "Power Ventilators for Restaurant Exh. Appliances" (Formerly UL 762)  
 Switch, NEMA-3R, Toggle.  
 Hinge, Factory Installed  
 High Temp Curb Seal Rated for Continuous Duty at 1500 F (Factory Attached)  
 Grease Trap (PN 475538)  
 Conduit Chase Qty 1

| DUCT TYPE    | SIZE  |
|--------------|-------|
| STANDARD     | 18 SQ |
| FIRE-WRAPPED | 12 SQ |

DUCT DIMENSIONS ARE LARGEST POSSIBLE DUCT TO FIT THROUGH CURB. CONSULT SYSTEM DESIGN ENGINEER FOR RECOMMENDED DUCT SIZE.  
 OVERALL HEIGHT MAY BE GREATER DEPENDING ON MOTOR, ADAPTER, AND/OR HINGE BASE.

ACCUREX

PROJECT: 7/19/2024  
 SSP - SRQ - WAHLBURGERS  
 ACCUREX NORTHERN CA - 2789  
 PAUL.WILKERSON@ACCUREX.COM  
 (209)275-4425  
 MARK: K1.1 - EF

UL 1876







MECHANICAL SPECIFICATIONS

21. PIPING SYSTEMS - PIPING AND ACCESSORIES

- A. PROVIDE PIPING SYSTEMS SHOWN ON DRAWINGS COMPLETE INCLUDING PIPE, FITTINGS, VALVES, STRAINERS, MOTORIZED VALVES OPERATORS, HANGERS, SUPPORTS, SLEEVES, AND ACCESSORIES.
B. HOT WATER PIPING SHALL BE BLACK STEEL PIPE, SCHEDULE 40, GRADE B, STANDARD WEIGHT, CONFORMING TO ASTM A53, FITTINGS SHALL HAVE A RATED WORKING PRESSURE OF 300 PSIG.
C. CONDENSATE DRAIN PIPING SHALL BE COPPER HARD TEMPER TYPE "L", CONFORMING TO ASTM B-88 WITH WROUGHT COPPER SOLDER JOINT, CONFORMING TO ANSI B 16.18.
D. INSTALL DRAIN VALVES AT ALL LOW POINTS OF PIPING AND AIR VENTS AT ALL HIGH POINTS.
E. PROVIDE MANUAL AIR VENTS LINE SIZE AIR CHAMBER WITH 1" GLOBE VALVE AT HIGH POINTS AND WHERE FLOW DIRECTION CHANGES FROM HORIZONTAL TO DOWNWARD.
F. ALL PIPING CONNECTIONS TO EQUIPMENT SHALL BE INSTALLED WITH UNION FOR EASY REMOVAL. UNIONS FOR 3 IN. OR LESS SHALL BE SIMILAR AND EQUAL TO MALLEABLE IRON WITH BRASS SEATS, CLASS 300, AS MANUFACTURED BY STOCKHAM, GRINNEL, OR AN APPROVED EQUAL.
G. ALL NIPPLES 6 IN. OR LESS SHALL BE EXTRA HEAVY SHOULDER TYPE. CLOSENIPPLES SHALL NOT BE USED.
H. USE TEFLON TAPE ON MALE THREADS OF SCREWED PIPE.
I. WET TAP IS PERMITTED, ONLY IF APPROVAL IS OBTAINED FROM THE BUILDING'S FACILITY DEPARTMENT.
J. WHERE CHANGES OF SIZE OCCUR IN HORIZONTAL PIPING, PROVIDE ECCENTRIC TYPE REDUCING FITTINGS TO ATTAIN PROPER DRAINAGE AND VENTING OF PIPELINE.
K. PROVIDE DIELECTRIC COUPLINGS AT JUNCTIONS OF DIFFERING METALS SUCH AS COPPER AND STEEL OR GALVANIZED PIPING.
L. PROVIDE FOR EXPANSION AND CONTRACTION OF PIPING SYSTEMS IN THE INSTALLED SYSTEM.
M. PITCH WATER PIPING UNLESS OTHERWISE NOTED BACK TO PUMP, RISER, OR DRAIN:
1. UP TO 1 IN. DIA. - 1 IN. PER 40 FT.
2. 1-1/2 IN. DIA. AND LARGER - 1 IN. PER 100 FT..
N. Y-TYPE STRAINERS
1. PROVIDE SCREWED ENDS TO 2 IN. AND FLANGED 2-1/2 IN. AND LARGER WITH BODY AS FOLLOWS:
a. TO 100 PSIG: 125 LB WSP CLASS, CAST IRON.
b. 100 TO 250 PSIG: 250 LB WSP CLASS, CAST IRON.
c. OVER 250 PSIG: 300 LB WSP CLASS, FORGED STEEL OR CAST STEEL.
2. SCREENS SHALL BE 316 STAINLESS STEEL.
3. PROVIDE SCREWED WITH FACED CAP, STRAIGHT THREAD AND GASKET, SIMILAR TO MUELLER STEAM SPECIALTY MUESSCO NO. 11. PROVIDE FLANGED WITH BOLTED COVER SIMILAR TO MUELLER STEAM SPECIALTY MUESSCO NO. 751 OR NO. 752.

22. VALVES

- A. PROVIDE VALVES AS AND WHERE SHOWN ON THE CONTRACT DRAWINGS. THE SYSTEM SHALL BE SUPPLIED WITH VALVES IN ALL BRANCHES, MAINS AND RISERS, TANKS, REDUCING AND CONTROL ELEMENTS, RADIATION, HEATING AND COOLING SURFACES AND AT APPARATUS; SO LOCATED, ARRANGED AND OPERATED AS TO GIVE COMPLETE CONTROL. EXCEPT WHERE FLANGED VALVES ARE USED, EACH CONNECTION TO EQUIPMENT SHALL INCORPORATE AN UNION ON THE EQUIPMENT SIDE OF THE VALVE.
B. ALL VALVES SHALL BE CAREFULLY SELECTED TO MEET THE PRESSURE OF WORKING AND TESTING (1-1/2 TIMES THE RATED WORKING PRESSURE) REQUIREMENTS IN THAT PARTICULAR APPLICATION IN THE ZONE WHERE THE VALVES ARE SERVED.
C. PROVIDE TAG ON VALVES IN THE BASE BUILDING RISER CLOSET OR CEILING TAKE-OFF AREA INDICATING THE TENANT'S NAME, "SUPPLY" OR "RETURN", AND FLOOR SERVED. THE TAG SHALL BE MADE OF EITHER METAL OR PLEXIGLASS, 3 IN. X 6 IN. SIZE, WITH A GREEN BACKGROUND AND BLACK LETTERING.
D. PROVIDE DRAIN AND VENT VALVES THAT ARE NOT SHOWN ON THE CONTRACT DRAWINGS BUT ARE NECESSARY FOR THE PROPER OPERATION OF PIPING SYSTEMS, AS FOLLOWS:
1. PROVIDE ONE INCH DRAIN VALVES WITH THREADED ENDS FOR HOSE CONNECTIONS AT DRAIN POINTS, AT MAIN SHUTOFF VALVES, LOW POINTS OF PIPING SYSTEMS, BASES OF VERTICAL RISERS, AND AT EQUIPMENT.
2. DRAIN VALVES AT ALL WATER PIPING LOW POINTS, CONFORMING TO THE GATE VALVES SPECIFICATIONS FOR THE PARTICULAR SYSTEM.
3. MANUAL VENT VALVES AT HIGH POINTS OF PIPING AREAS THAT ARE DIFFICULT TO SERVICE, CONFORMING TO THE GLOBE VALVE SPECIFICATIONS FOR THE PARTICULAR SYSTEM.
E. BALL VALVES
1. SHUTOFF VALVES FOR 3 IN. & SMALLER SIZES SHALL BE BALL VALVES TWO PIECE, THREADED ENDS, BRONZE BODY/BRASS BODY, FURNISHED WITH SEAT & STEM SEALS OF REINFORCED TEFLON OR PTFE, SIMILAR TO STOCKHAM S-216, CRANE CAPRI NO. 9302, OR AN APPROVED EQUAL.
2. PROVIDE LEVER FOR QUARTER TURN OPERATION; LEVER TO INDICATE OPEN OR CLOSED POSITION.
3. WHEN USED AS DRAIN VALVES, PROVIDE WITH HOSE THREAD AND BRASS CAP WITH CHAIN. CAP TO BE RATED FOR FULL SYSTEM PRESSURE.
F. COMBINATION BALANCING & SHUTOFF VALVES
1. VALVE SHALL BE THE ECCENTRIC NON-LUBRICATED PLUG VALVE, WITH ADJUSTABLE MEMORY STOP AND PRESSURE TAP, AS MANUFACTURED BY DEZURIK RATED WORKING PRESSURE AND HYDROSTATIC TESTING PRESSURE (ONE AND ONE-HALF TIMES OF RATED WORKING PRESSURE) MUST BE SPECIFIED.
2. FOR WORKING PRESSURE UP TO 175 PSIG:
a. SIZES 1 IN. THROUGH 2-1/2 IN., DEZURIK SERIES 400, SCREWED CAST IRON CONFORMING TO ANSI CLASS 125 IRON CONFORMING TO ANSI CLASS 125.
b. SIZES 3 IN. AND UP, DEZURIK SERIES 100, FLANGED, CAST IRON CONFORMING TO ANSI CLASS 125.
3. FOR WORKING PRESSURE FROM 200 PSIG THROUGH 450 PSIG:
a. SIZES 2 IN. AND UNDER, DEZURIK SERIES 100, FIG.128/WG/SP SCREWED, CARBON STEEL CONFORMING TO ANSI CLASS 300.
b. SIZES 2-1/2 IN. AND UP, DEZURIK SERIES 100, FIG.128 DFX001, FLANGED, CARBON STEEL CONFORMING TO ANSI CLASS 300.
G. GATE VALVES
1. UP TO 3 IN., BRONZE THREADED ENDS, SOLID WEDGE, INSIDE SCREW, RISING STEM, UNION BONNET, SIMILAR TO STOCKHAM FIG. B-120 FOR CLASS 150, B-132 FOR CLASS 200, OR APPROVED EQUAL. BRONZE BODY AND TRIM WITH BRONZE, THREADED ENDS FOR STEEL PIPING AND TRIM AND SWEATED ENDS FOR COPPER PIPING.

- 2. ABOVE 3 IN., IRON BODY, FLANGED ENDS, RISING STEM, BOLTED BONNET, SOLID WEDGE DISC, OS&Y, SIMILAR TO STOCKHAM FIG. G-624 FOR CLASS 125, G667 FOR CLASS 250, OR APPROVED EQUAL. IRON BODY AND FLANGED END FOR STEEL PIPING. BRONZE BODY, BRONZE TRIM AND SWEATED ENDS FOR COPPER PIPING.
H. GLOBE VALVES
1. UP TO 3 IN., BRONZE THREADED ENDS, SOLID WEDGE OR PLUG TYPE DISC, INSIDE SCREW, RISING STEM, UNION BONNET, SIMILAR TO STOCKHAM FIG. B227 FOR CLASS 150, 8-32 FOR CLASS 200, OR AN APPROVED EQUAL. BRONZE BODY AND TRIM WITH BRONZE, THREADED ENDS FOR STEEL PIPING AND SWEATED ENDS FOR COPPER PIPING.
2. ABOVE 3 IN., FLANGED ENDS, RENEWABLE SEAT AND DISC, BOLTED BONNET, OS&Y, SIMILAR TO STOCKHAM FIG. G-512 FOR CLASS 125 (IRON ODY), STOCKHAM FIG. 15-GPFU-S/30-GPFU-S FOR CLASS 150/300 (CAST STEEL), OR AN APPROVED EQUAL. IRON BODY AND FLANGED END FOR STEEL PIPING. BRONZE BODY, BRONZE TRIM AND SWEATED ENDS FOR COPPER PIPING.
I. CHECK VALVES
1. SWING TYPE, BRONZE BODY & DISC, THREADED ENDS, THREADED CAP, REGRINDING, SUITABLE FOR BOTH HORIZONTAL AND VERTICAL LINES WITH UPWARD FLOW, SIMILAR TO STOCKHAM FIG. B-321 FOR CLASS 150, FIG. B-345 FOR CLASS 200 (UP TO 2 IN.), CRANE NO. 137 FOR CLASS 150, CRANE NO. 36 FOR CLASS 200 (UP TO 3 IN.), OR AN APPROVED EQUAL. SCREWED END FOR STEEL PIPING AND SWEATED END FOR COPPER PIPING.

23. METERS AND GAUGES

- A. THERMOMETERS
1. THERMOMETERS FOR PIPING SHALL BE OF THE "ALL ANGLE" (UNIVERSAL), SEPARATE SOCKET, INDUSTRIAL TYPE WITH # 304 STAINLESS STEEL EXTENSION NECK WELLS.
2. THE THERMOMETER FOR CONDENSER WATER SYSTEM SHALL OPERATE AT 0 - 160 DEG. F RANGE, AND SHALL INCLUDE A SUFFICIENT SAFETY MARGIN AT EITHER END.
3. THERMOMETER SHALL BE AS MANUFACTURED BY ALBERT A. WEISS, WEKSLER INSTRUMENT CO., ASHCROFT, OR AN APPROVED EQUAL.
B. PRESSURE GAUGES
1. PRESSURE GAUGES SHALL BE OF THE BOURDON TUBE SPRING TYPE WITH 4-1/2 DIAL SIZES. GAUGES SHALL HAVE BLACK ALUMINUM CASES WITH BLACK NUMBERS ON WHITE BACKGROUND. THE GAUGE SHALL BE AS MANUFACTURED BY ALBERT A. WEISS, WEKSLER INSTRUMENT CO., ASHCROFT, OR AN APPROVED EQUAL.
2. THE PRESSURE RANGE FOR THE AUXILIARY COOLING SHALL BE 0 - 500 PSI, AND THE BOURDON TUBE SHALL BE BRONZE.

24. PIPE HANGERS, SUPPORTS, ANCHORS AND GUIDES

- A. ALL REQUIRED SUPPORTS, HANGERS, ANCHORS AND GUIDES SHALL BE PROVIDED AND INSTALLED BY THIS CONTRACTOR AND SHALL BE SEISMICALLY DESIGNED.
B. ALL SUPPORTS AND PARTS SHALL CONFORM TO THE REQUIREMENTS OF THE FLORIDA BUILDING CODE, ANSI B 31.9 AS APPLICABLE FOR PRESSURE PIPING, AND MSS STANDARD PRACTICE SP-58 SP-69.
C. INSTALL HANGERS AND SUPPORTS TO ALLOW CONTROLLED THERMAL AND SEISMIC MOVEMENT OF PIPING SYSTEMS, TO PERMIT FREEDOM OF MOVEMENT BETWEEN PIPE ANCHORS, AND TO FACILITATE ACTION OF EXPANSION JOINTS, EXPANSION LOOPS, EXPANSION BENDS, AND SIMILAR UNITS.
D. DO NOT HANG PIPING FROM OTHER PIPING. IN NO CASE SHALL HANGERS BE SUPPORTED BY MEANS OF VERTICAL EXPANSION BOLTS.
E. WHEN REMOVAL OF EXISTING FIRE PROOFING IS REQUIRED FOR NEW INSTALLATION PURPOSES, SUCH REMOVAL SHALL BE PERFORMED BY THE CONTRACTOR AND SHALL BE KEPT TO A MINIMUM. THE CONTRACTOR SHALL REPLACE ALL REMOVED FIREPROOFING WITH NEW FIREPROOFING TO THE SATISFACTION OF THE ENGINEER AND AT NO ADDITIONAL COST TO THE AUTHORITY.
F. SUPPORT HANGERS FROM BUILDING STEEL FRAMING WITH AN APPROVED TYPE CLAMP INSERT. PROVIDE ANY ADDITIONAL STEEL SUPPORTS BETWEEN EXISTING FRAMING MEMBERS AS MAY BE REQUIRED. NO HANGERS SHALL BE SUPPORTED FROM METAL DECK FLOOR. WELDING TO THE BUILDING STRUCTURE MEMBERS WILL NOT BE PERMITTED UNLESS APPROVED BY THE BUILDING MANAGEMENT.
G. PIPE HANGERS, RODS, INSERTS AND CLAMPS SHALL BE UL APPROVED FOR THEIR RESPECTIVE USES.
H. UNLESS OTHERWISE SPECIFICALLY APPROVED, HANGER SIZE AND SPACING SHALL BE AS FOLLOWS:
COPPER TUBING
PIPE SIZE MAX. HANGER SPACING MIN. ROD SIZE
1/2" TO 1-1/4" 6 FT. O.C. 3/8"
NOTE: THE ABOVE HANGER SPACING APPLY TO STRAIGHT RUNS OF PIPE ONLY.
I. HANGERS AND SUPPORTS SHALL BE MANUFACTURED BY GRINNELL CORP, CARPENTER & PATTERSON INC., MICHIGAN HANGER CO. INC., OR AN APPROVED EQUAL.

25. EQUIPMENT SCHEDULE

- A. FURNISH AND INSTALL ALL ITEMS AS HEREIN SPECIFIED OR SHOWN ON DRAWINGS AND THOSE ITEMS OF LABOR OR MATERIALS NOT SPECIFICALLY INDICATED, BUT REQUIRED TO COMPLETE THE INTENDED INSTALLATIONS.

26. CONTROL SYSTEM

- A. FURNISH AND INSTALL ITEMS AS HEREIN SPECIFIED OR SHOWN ON DRAWINGS AND THOSE ITEMS OF LABOR OR MATERIALS NOT SPECIFICALLY INDICATED TO PROVIDE FULLY OPERATIONAL SYSTEMS.
B. FURNISH AND INSTALL A COMPLETE AUTOMATIC TEMPERATURE CONTROL SYSTEM OF THE ELECTRICAL TYPE CONSISTING OF BUT NOT LIMITED TO THE FOLLOWING:
1. THE CONTROL SYSTEM SHALL BE COMPLETE WITH ALL NECESSARY THERMOSTAT, HUMIDISTATS, DAMPERS, VALVES, AND ELECTRICAL RELAYS, SWITCHES, ETC. CONTROL INSTRUMENT WIRING AND CAPILLARIES ARE TO BE SECURED TO THE BUILDING STRUCTURE NOT TO DUCTWORK.
2. ALL MODULATING AUTOMATIC DAMPERS AND CONTROL VALVES SHALL OPERATE IN SLOW GRADUAL MANNER WITHOUT JERKING OR SLAMMING.
3. THERMOSTAT SHALL BE SEVEN DAY PROGRAMMABLE OF THE FULLY PROPORTIONING TYPE AND SHALL HAVE ADJUSTABLE SENSITIVITY OF THE THROTTLING RANGE. THERMOSTAT SHALL BE ABLE TO CONTROL WITHIN PLUS OF MINUS 1/2 DEG. F AND SHALL MATCH TO THE AC UNIT CONTROLS THERMOSTAT SHALL HAVE A OFF-FAN-HEAT-COOL SETTINGS.
4. ALL TRANSMITTERS SHALL BE CAPABLE OF MEASURING THE SPACE OR DUCT TEMPERATURE AND TRANSMITTING ELECTRICAL SIGNAL DIRECTLY PROPORTIONAL TO THE TEMPERATURE ACCURACY 1% SCALE RANGE.
5. SHOP DRAWING INDICATING THE WIRING DIAGRAM OF THE CONTROL SYSTEM WITH SEQUENCE OF OPERATION AND RANGE OF CONTROLS FOR BOTH SUMMER AND WINTER.
6. GUARANTEE TO KEEP THE CONTROL SYSTEM IN REPAIR AND ADJUSTMENT FOR A PERIOD OF ONE YEAR FROM THE DATE THE EQUIPMENT HAD BEEN PUT TO ACTUAL USE BY THE OWNER, FREE FROM ANY EXPENSES TO THE OWNER AND GIVE OWNER'S REPRESENTATIVE INSTRUCTION AT THE SITE TO ITS OPERATION AND MAINTENANCE.

26. SEQUENCE OF OPERATION

FCU-1

- A. AS THE TEMPERATURE RISES ABOVE THE SETPOINT, THE UNIT WILL TURN ON AND COOL THE SPACE UNTIL THE DESIRED TEMPERATURE IS ACHIEVED.
1. THE CHILLED WATER VALVES WILL OPEN TO ALLOW MORE WATER TO FLOW THROUGH THE COILS.
2. THE FAN WILL INCREASE IN RPM TO DELIVER MORE AIR TO THE SPACE.
3. ONCE THE TEMPERATURE IS ACHIEVED, THE FAN WILL START TO DECREASE IN RPM AND THE CHILLED WATER VALVES WILL START TO CLOSE TO REDUCE THE AMOUNT OF WATER FLOWING THROUGH THE COIL.
B. AS THE TEMPERATURE FALLS BELOW THE SETPOINT, THE ELECTRIC HEATER WILL TURN ON AND HEAT THE SPACE UNTIL THE DESIRED TEMPERATURE IS ACHIEVED.

ISOLATION VALVES



THE ISOLATION VALVES SHALL BE NORMALLY CLOSED (NC). WHEN FCU1 REQUIRES COOLING . THE VALVES SHALL OPEN TO ALLOW MORE CHILLED TO WATER TO PASS THROUGH THE COIL. WHEN FCU IS TURNED OFF, ALL VALVES SHALL RETURN TO NORMALLY CLOSED.

OUTSIDE AIR MOTORIZED DAMPER

MOTORIZED DAMPER SHALL BE NORMALLY CLOSED. UPON ACTIVATION OF EITHER FCU, DAMPER DURING OCCUPIED MODE SHALL OPEN TO SET POSITION TO DELIVER REQUIRED OUTDOOR AIR. UPON SHUT DOWN OF UNIT, DAMPER SHALL CLOSE.

KITCHEN GREASE HOOD EXHAUST FAN

KITCHEN EXHAUST FAN TO OPERATE BASED ON THE TEMPERATURE SENSOR INSTALLED BY HOOD SUPPLIER. KITCHEN HOOD EXHAUST FAN TO HAVE MANUAL OVERRIDE ON & OFF SWITCH TO BE CONTROLLED BY KITCHEN STAFF. EF STATUS SHALL BE MONITORED BY BAS.



DocuSigned by: John J. Guth, PE

FLORIDA PROFESSIONAL ENGINEER LICENSE No. 60427


John J. Guth, PE FL LIC# 60427

ENV ARCHITECTURE + DESIGN 180 SYLVAN AVENUE, SUITE 3 ENGLEWOOD CLIFFS, NJ 07632 TEL 201 | 894 | 1000 ENV-team.com ENVIRONETICS GROUP ARCHITECTS, P.C. COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED

SSP AMERICA CLIENT: 20408 BASHAN DRIVE SUITE 300 ASHBURN, VA 20147

PROJECT TEAM: ARCHITECT: ENVIRONETICS GROUP ARCHITECTS 180 SYLVAN AVE. ENGLEWOOD CLIFFS, NJ 07632

MEP ENGINEER GUTH DECONZO CONSULTING ENGINEERS, PC 520 8TH AVENUE, SUITE 2201 NEW YORK, NY 10018 CERTIFICATE OF AUTHORIZATION CA LIC. NO. 27747



B-FB4 - WAHLBURGERS SARASOTA BRADENTON INTERNATIONAL 6000 AIRPORT CIRCLE SARASOTA, FL 34243 CLIENT: SSP AMERICA

Table with 3 columns: REV, DATE, DESCRIPTION. Contains one row: DESIGN DELIVERABLE: ISSUED FOR PERMIT 08/16/2024

PROJECT NUMBER: 24017G DRAWN BY: CHECKED BY:

Copyright (c) by Environetics, Inc. All Rights Reserved.

MECHANICAL SPECIFICATIONS (SHEET 3 OF 3)

SHEET NUMBER: M-603

ELECTRICAL SYMBOLS

Table with 2 columns: Symbol and Description. Sections include: WIRING & CONDUIT SYSTEM, PANELBOARD, WIRING DEVICES, LIGHTING, and TELECOMMUNICATION.

ELECTRICAL GENERAL NOTES

- 1. BEFORE SUBMITTING THE BID PROPOSAL THE CONTRACTOR SHALL:
A. VISIT THE JOB SITE AND BECOME FULLY ACQUAINTED WITH JOB CONDITIONS.
B. REVIEW A FULL SET OF BID DOCUMENTS TO MAKE THEMSELVES AWARE OF THE TOTAL JOB BEFORE SUBMITTING THEIR PRICE.
C. VERIFY ALL EXISTING CONDITIONS IN THE FIELD AND INCLUDE IN BID PRICE ALL WORK REQUIRED TO ACCOMMODATE THE EXISTING INSTALLATION.
2. REFER TO ARCHITECTURAL DRAWINGS FOR THE FOLLOWING:
A. EXACT LOCATION OF ALL ELECTRICAL OUTLETS AND LIGHTING FIXTURES.
B. FINAL LOCATION OF CEILING MOUNTED EQUIPMENT.
C. CONNECTION POINTS AND SPECS FOR ELECTRIFIED WALL PANEL SYSTEMS.
D. ADDITIONAL ELECTRICAL REQUIREMENTS.
3. COORDINATE WITH OTHER TRADES TO DETERMINE THE EXACT LOCATION OF MOTORS, MOTOR TERMINAL BOXES, AND OTHER EQUIPMENT TO BE INSTALLED BY OTHER TRADES BEFORE CONDUIT WORK IS STARTED.
4. CONTRACTOR IS TO FURNISH, INSTALL AND CONNECT ALL RACEWAYS AND WIRING FROM EQUIPMENT, DEVICES AND LIGHTING FIXTURES TO ITS SOURCE OF POWER AND CONTROLS.
5. CONTRACTOR SHALL FIELD VERIFY DIMENSIONS OF FINISHED CONSTRUCTION PRIOR TO FABRICATION AND INSTALLATION OF FIXTURES AND EQUIPMENT.
6. ELECTRICAL CONTRACTOR SHALL VERIFY SWITCHES, RECEPTACLES AND PLATE FINISHES WITH THE ARCHITECT BEFORE PERFORMING THEIR INSTALLATION. ALL COVER PLATES SHALL BE AS SPECIFIED BY ARCHITECT.
7. PROVIDE LATEST DIRECTORY FOR PANEL BOARDS.
8. COORDINATE LOCATION OF OUTLETS AND SWITCHES WITH FURNITURE AND EQUIPMENT LAYOUTS AND WITH OWNERS REPRESENTATIVE.
9. ALL WORK REQUIRING ELECTRICAL SHUTDOWN WHICH WILL AFFECT OTHER AREAS OF THE BUILDING OR EVEN AFFECT THE NORMAL CONTINUATION OF CONSTRUCTION WORK ON THESE FLOORS, SHALL BE DONE ON OVERTIME HOURS, AND SHALL NOT DISTURB CONTINUITY OF ELECTRICAL SERVICE TO EXISTING TENANTS ON THE AFFECTED FLOORS.
10. WHERE MULTIPLE SWITCHES AND RECEPTACLES ARE INDICATED AT THE SAME LOCATION, THEY SHALL BE MOUNTED BEHIND A COMMON FACEPLATE.
11. WHERE EQUIPMENT, LIGHTING FIXTURES AND WIRING DEVICES ARE SHOWN WITH CIRCUIT NUMBERS ONLY, THE MINIMUM BRANCH CIRCUITING REQUIREMENTS SHALL BE AS FOLLOWS:
A. LIGHTING FIXTURES - 2 #12, #12 GRD. - 3/4" C.
B. RECEPTACLES - 2#12, #12 GRD. - 3/4" C.
C. BRANCH CIRCUIT BREAKERS (120 VOLT) - 1P, 20A
D. HOMERUNS TO PANELBOARDS SHALL CONTAIN NO MORE THAN (3) CIRCUITS.
E. WHERE LIGHTING SWITCH INDICATIONS ARE NOT SHOWN, SWITCHES SHALL BE CONNECTED TO CONTROL ALL SWITCHED FIXTURES WITHIN THE CORRESPONDING SPACE.
12. WHERE CONDUIT AND WIRING CONNECTIONS ARE NOT SHOWN ON THE PLANS, MAKE CONNECTIONS USE #10 AWG WIRE TO THE FIRST AND ANY OUTLET FOR BRANCH CIRCUIT RUNS MORE THAN 80 FEET (OF WIRING) FOR 120V AND 208V CIRCUITS, U.O.N.
13. WIRING IN AIR PLENUM HUNG CEILINGS INSTALLED WITHOUT CONDUIT OR EMT SHALL BE TEFLON JACKETED.
14. NO LOW VOLTAGE WIRING SHALL BE PERMITTED IN THE SAME RACEWAY AS POWER WIRING.
15. FOR WIRING IN METAL PARTITIONS WHERE EMT IS IMPRACTICAL, FLEXIBLE STEEL CONDUIT GALVANIZED, MINIMUM 3/4" SHALL BE USED.
16. PROVIDE DRAG LINES IN ALL EMPTY RACEWAYS.
17. ALL CONDUITS FOR BRANCH CIRCUITING AND/OR COMMUNICATIONS CABLING, INCLUDING THOSE RUN IN CEILING OF FLOOR BELOW SHALL BE IDENTIFIED AT EVERY 50 FEET OF LENGTH AND AT EACH OUTLET AND PULL BOX WITH PANEL AND CIRCUIT NUMBER OR SYSTEM NAME.
18. CONTRACTOR TO PROVIDE AN EMPTY CONDUIT SYSTEM WITH DRAG LINES AND OUTLET BOXES FOR INSTALLATION OF COMMUNICATIONS WIRING SYSTEMS. VERIFY EXACT REQUIREMENTS WITH SYSTEM VENDOR(S).
19. THE MINIMUM RATING OF DISCONNECT SWITCHES SHALL BE EQUAL TO OR GREATER THAN THE RATING OF THE PROTECTIVE DEVICE ON THE SUPPLY SIDE OF THE DISCONNECT SWITCH. MINIMUM DISCONNECT SWITCH SIZE IS 30 AMPERES. AND TOGGLE DISCONNECT SWITCHES SHALL BE 20 AMPERES.
20. PROVIDE UL LISTED FLOOR POKE-THRU AND FIRE STOPPING DETAILS FOR ALL CONDUIT PENETRATIONS THROUGH FIRE RATED WALL AND FLOOR CONSTRUCTION. FIRE STOPPING AT PENETRATIONS THROUGH RATED CONSTRUCTION SHALL COMPLY WITH THE LATEST FLORIDA BUILDING CODE.

ELECTRICAL KITCHEN NOTES

- 1. ALL ELECTRICAL WORK SHALL BE DONE IN ACCORDANCE WITH THE ELECTRICAL SPECIFICATIONS, ALL APPLICABLE CODES AND OTHER AUTHORITIES HAVING JURISDICTION.
2. ELECTRICAL CONTRACTOR SHALL COORDINATE ALL FINAL LOCATIONS AND POINTS OF ELECTRICAL SERVICE (JUNCTION BOX, DISCONNECT SWITCHES, RECEPTACLES, STUB-UPS, ETC.) WITH THE VENDOR INSTALLER AND OWNER BEFORE INSTALLATION.
3. ELECTRICAL CONTRACTOR SHALL PROVIDE THE FINAL CONNECTION TO ALL EQUIPMENT NOTED IN CONTRACT, AND SHALL PROVIDE RECEPTACLES WHERE INDICATED TO MATCH CORD-PLUG SET OF EQUIPMENT, FLEXIBLE POSITIONING OF EQUIPMENT OF TYPE INDICATED ON PLAN AND STUB-UPS AS REQUIRED FOR DIRECT CONNECTIONS. ELECTRICAL CONTRACTOR SHALL COORDINATE WITH OWNER AND ARCHITECT FOR THE EXACT MOUNTING HEIGHTS AND TYPES OF TERMINATION TO BE USED FOR EQUIPMENT TO BE INSTALLED.
4. WHERE INDICATED ON PLAN OR OTHERWISE REQUIRED BY HEATING OR COOKING EQUIPMENT, THE ELECTRICAL CONTRACTOR SHALL PROVIDE APPROVED TYPE HIGH TEMPERATURE WIRE AT TERMINALS OF CONTROL CABINETS OR HEATING ELEMENTS. THE INSULATION RATING SHALL BE EQUAL OR GREATER THAN THE AMBIENT TEMPERATURE OF THE ENCLOSURE IN WHICH IT IS TO BE TERMINATED.
5. ELECTRICAL CONTRACTOR SHALL PROVIDE A LOCAL MEANS OF DISCONNECT FOR ALL UNGROUNDED POWER CONDUCTORS FOR EQUIPMENT AS REQUIRED BY THE N.E.C. AND ALL OTHER AUTHORITIES HAVING JURISDICTION.
6. ELECTRICAL CONTRACTOR SHALL PROVIDE LIQUID TIGHT FINAL CONNECTION FOR ALL EQUIPMENT REQUIRING FLEXIBLE FINAL CONNECTIONS AND LOCATED IN AN AREA SUBJECT TO WATER DUE TO EQUIPMENT OR CLEANING REQUIREMENTS. ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR SEALING WATER PROOFING MEMBRANE OF FLOOR AROUND ALL CONDUIT PENETRATIONS OF THE MEMBRANE.
7. ELECTRICAL CONTRACTOR SHALL PROVIDE CONTROL WIRING AND PENETRATIONS FOR ALL EQUIPMENT AS REQUIRED BY THE KITCHEN EQUIPMENT CONTRACTOR. ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE TO COORDINATE AND PROVIDE CONTROL WIRING FOR ALL EQUIPMENT INCLUDING BUT NOT LIMITED TO REFRIGERATION SYSTEMS, HOOD PROTECTION AND CLEANING SYSTEM, HOT FOOD WELLS AND OTHER THERMOSTATIC CONTROLLED EQUIPMENT DISHWASHING UNIT INCLUDING REMOTE HOOD SWITCH.
8. ALL CIRCUIT HOME RUNS SHALL BE PROVIDED WITH A SEPARATE GROUND WIRE, AS PER N.E.C.
9. ALL CONDUITS FOR BRANCH CIRCUITS TO ALL THE KITCHEN EQUIPMENT SHALL BE RUN CONCEALED IN WALL EXCEPT AS NOTED AND INDICATED.
10. COORDINATE INTERCONNECTION OF RELATED EQUIPMENT WITH ARCHITECT AND KITCHEN EQUIPMENT
11. ELECTRICAL CONTRACTOR SHALL FURNISH AND INSTALL SEAL TIGHT FITTINGS AT ALL CONDUIT PENETRATIONS TO ALL FREEZER AND REFRIGERATION WALLS.
12. COORDINATE ALL LOCATIONS OF OUTLETS AND EQUIPMENT WITH KITCHEN CONSULTANT DRAWINGS AND WITH ARCHITECTURAL DRAWINGS.
13. ALL BRANCH WIRING SHALL BE CONCEALED IN WALLS AND ABOVE HUNG CEILING, U.O.N. WHERE THERE'S NO HUNG CEILING, CONDUIT SHALL BE RUN IN A NEAT AND ORDERLY MANNER, PARALLEL AND PERPENDICULAR TO HVAC DUCTWORK, NO FLEXIBLE CONDUIT IS PERMITTED IN AREAS WHERE IT WILL BE EXPOSED. COORDINATE WITH OTHER TRADES AND FIELD CONDITIONS FOR CONDUITS ROUTING AND ELECTRICAL CONNECTIONS TO OTHER TRADES' EQUIPMENT.
14. THE ELECTRICAL CONTRACTOR SHALL PATCH PAINT, AND RESTORE EXISTING CEILINGS, SOFFITS, WALLS, AND OTHER FINISHES THAT WERE DISTURBED AND/OR DAMAGED DUE TO THEIR WORK.
15. CONTRACTOR SHALL PROVIDE MATCHING NEMA PLUGS WITH ALL NEMA RECEPTACLES FOR KITCHEN EQUIPMENT. FURNISH 90° PLUGS WITH CORD WILL HANG IN THE DOWNWARDS POSITION.
16. ALL EQUIPMENT LOCATED UNDER COOKING HOODS ARE TO BE PROVIDED WITH SHUNT TRIP BREAKERS. SHUNT TRIP CIRCUIT BREAKERS SHALL BE EQUIPPED WITH 120V COILS.
17. E.C. TO FURNISH AND INSTALL ALL RECEPTACLES, SWITCHES AND JUNCTION BOXES WITH STAINLESS STEEL FACE PLATES.
18. ALL GENERAL PURPOSE AND COUNTER TOP RECEPTACLES (15A AND 20A, 120V) EQUIPMENT RECEPTACLES LOCATED WITHIN THE KITCHEN SHALL BE GFCI PROTECTED BY CIRCUIT BREAKER OR DEVICE AS REQUIRED PER CODE. CONTRACTOR SHALL PROVIDE GFCI BREAKER AS REQUIRED IN THE PANEL FOR ALL EQUIPMENT WITH 208V, 2 POLES WITH 20A, 30A CIRCUIT BREAKERS AS INDICATED ON THE PANEL SCHEDULE.
19. E.C. TO SUPPLY ALL NECESSARY CONTACTORS, STARTERS AND DISCONNECTS.
20. E.C. TO INTERWIRE HOOD FIRE EXTINGUISHING SYSTEM WITH EXHAUST FAN AND COOKING BATTERY TO CAUSE FAN TO TURN ON AND COOKING TO TURN OFF WHEN FIRE SYSTEM IS ACTIVATED. FURNISH AND INSTALL ADDITIONAL TWO RELAYS FOR CONTROLS AS NEEDED.
21. FOR 120V GFI OUTLETS THAT ARE LOCATED BEHIND EQUIPMENT, PROVIDED GFCI OUTLET DEVICE (HUBBLE GFBFST20W) LOCATED IN ACCESSIBLE LOCATION SO THAT THE EQUIPMENT CAN BE RESET WITHOUT REMOVING THE EQUIPMENT.
22. ALL LIGHTING FIXTURES IN SERVERY, KITCHEN, BAR AREA SHALL BE SHATTERPROOF AND/OR COMPLETELY COVERED.
23. ANY EXPOSED UTILITY SERVICE LINES AND PIPES (ELECTRICAL, PLUMBING, ETC.) SHALL BE INSTALLED IN A WAY THAT DOES NOT OBSTRUCT OR PREVENT THE CLEANING OF FLOORS - MINIMUM OF 6" OFF FLOORS.

DRAWING LIST table with 2 columns: Drawing Code and Description. Includes E-001 ELECTRICAL NOTES, SYMBOLS AND DRAWING LIST, E-101 ELECTRICAL POWER PLAN, E-102 ELECTRICAL COMMUNICATION PLAN, E-201 ELECTRICAL LIGHTING PLAN, E-301 ELECTRICAL RISER, E-401 ELECTRICAL DETAILS, E-501 ELECTRICAL SCHEDULES, E-601 ELECTRICAL SPECIFICATIONS-1, E-602 ELECTRICAL SPECIFICATIONS-2.

ABBREVIATIONS LIST


Table with 2 columns: Abbreviation and Full Name. Includes AC ABOVE COUNTER, AFF ABOVE FINISHED FLOOR, AWG AMERICAN WIRE GAUGE, C CONDUIT, C/B CIRCUIT BREAKER, ETR EXISTING TO REMAIN, EM EMERGENCY, EC ELECTRICAL CONTRACTOR, ERR,RR EXISTING TO BE REMOVED AND RELOCATED, ER EXISTING RELOCATED, R EXISTING TO BE DISCONNECTED AND REMOVED, KVA KILOVOLTAMP, MCB MAIN CIRCUIT BREAKER, MLO MAIN LUG ONLY, NIC NOT IN CONTRACT, NTS NOT TO SCALE, P POLES, PH PHASE, G/GRD/GND GROUND, TYP TYPICAL.



180 SYLVAN AVENUE, SUITE 3
ENGLEWOOD CLIFFS, NJ 07632
TEL 201 | 894 | 1000
ENV-team.com
ENVIRONETICS GROUP ARCHITECTS, P.C.
COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED

CLIENT:
SSP AMERICA
20408 BASHAN DRIVE
SUITE 300
ASHBURN, VA 20147

PROJECT TEAM:
ARCHITECT:
ENVIRONETICS GROUP ARCHITECTS
180 SYLVAN AVE.
ENGLEWOOD CLIFFS, NJ 07632
MEP ENGINEER
GUTH DECONZO CONSULTING
ENGINEERS, PC
520 8TH AVENUE, SUITE 2201
NEW YORK, NY 10018
CERTIFICATE OF AUTHORIZATION
CA LIC. NO. 27747



John J. Guth, PE
FL LIC# 60427

B-FB4 - WAHLBURGERS
SARASOTA BRADENTON INTERNATIONAL
6000 AIRPORT CIRCLE
SARASOTA, FL 34243
CLIENT: SSP AMERICA

Table with 3 columns: REV, DATE, DESCRIPTION. Contains revision history.



DESIGN DELIVERABLE: ISSUED FOR PERMIT
ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G
DRAWN BY:
CHECKED BY:



Copyright (c) by Environetix, Inc. All Rights Reserved.

SHEET TITLE:
ELECTRICAL
NOTES, SYMBOLS
AND DRAWING LIST


SHEET NUMBER:
E-001



**ELECTRICAL DEMOLITION PLAN**  
SCALE: 1/4" = 1'-0



**ELECTRICAL LIGHTING DEMOLITION PLAN**  
SCALE: 1/4" = 1'-0



**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |


DESIGN DELIVERABLE: ISSUED FOR PERMIT  
ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G  
DRAWN BY:  
CHECKED BY:

Copyright (c) by Environetix, Inc. All Rights Reserved.


SHEET TITLE:  
**ELECTRICAL DEMOLITION PLANS**

SHEET NUMBER:  
**E-011**



**POWER NOTES**

- FOR EXACT LOCATION AND MOUNTING HEIGHTS OF ALL RECEPTACLES, TELEPHONE AND DATA OUTLETS, SEE ARCHITECTURAL DRAWINGS AND KITCHEN CONSULTANT ELECTRICAL ROUGH-IN PLAN.
- CONTRACTOR SHALL FURNISH AND INSTALL ALL REQUIRED CONDUITS, WIRES, ARMORED CABLE AND BOXES TO ENERGIZE EQUIPMENT AND DEVICES INDICATED.
- ALL BRANCH WIRING SHALL BE CONCEALED IN WALLS AND ABOVE HUNG CEILING, U.O.N. WHERE THERE'S NO HUNG CEILING, CONDUIT SHALL BE RUN IN A NEAT AND ORDERLY MANNER, PARALLEL AND PERPENDICULAR TO HVAC DUCTWORK AND FIRE PROTECTION SPRINKLER PIPES. NO FLEXIBLE CONDUIT IS PERMITTED IN AREAS WHERE IT WILL BE EXPOSED.
- MAINTAIN CONTINUITY IN ALL EXISTING CIRCUITRY TO REMAIN WHICH IS AFFECTED BY THE SCOPE OF WORK. CONTRACTOR TO FURNISH AND INSTALL ALL NECESSARY WIRES, CONDUITS AND JUNCTION BOXES REQUIRED TO KEEP CONTINUITY.
- COORDINATE WITH OTHER TRADES AND FIELD CONDITIONS FOR CONDUITS ROUTING AND ELECTRICAL CONNECTIONS TO OTHER TRADES' EQUIPMENT.
- THE ELECTRICAL CONTRACTOR SHALL PATCH PAINT, AND RESTORE EXISTING CEILINGS, SOFFITS, WALLS, AND OTHER FINISHES THAT WERE DISTURBED AND/OR DAMAGED DUE TO THEIR WORK.
- CIRCUIT NUMBERS INDICATED ARE FOR GROUPING PURPOSES ONLY. CONTRACTOR SHALL VERIFY THE EXACT CIRCUIT NUMBER IN THE FIELD. CONTRACTOR SHALL RUN ALL CIRCUITS TO CORRESPONDING PANEL, UNLESS OTHERWISE NOTED IN TENANT SPACE.
- ALL RECEPTACLES LOCATED NOT DIRECTLY ATTACHED TO WALL SHALL BE CHASED TO CLOSEST ADJACENT WALL. EC SHALL PROVIDE DRAG LINE FOR EMPTY CONDUIT. CHASE SHALL CONSIST OF (1)-3/4" FOR POWER OUTLETS (1)-1" FOR DATA OUTLETS
- CONTRACTOR SHALL FOLLOW PROJECT CORE DRILLING APPROVAL PROCEDURE AND OBTAIN APPROVAL PRIOR TO EXECUTING WORK IN THE FIELD. CONFIRM CONDITIONS BELOW LEASE PREMISE AND COORDINATE CORE LOCATIONS.
- WALL MOUNTED OUTLETS (MOUNTED AT 18" ABOVE FINISHED FLOOR, (UNLESS OTHERWISE NOTED), SHALL BE INSTALLED PER LAYOUT AND EQUIPMENT REQUIREMENTS. PROVIDE STUB-UP CONDUITS, SIZED AS REQUIRED FOR ALL OUTLET LOCATIONS. FINISHES OF ALL COVER & SWITCHES PLATES, ETC TO MATCH WALL COLOR. PROVIDE CONVENIENCE OUTLETS AS REQUIRED. COORDINATE WITH ARCHITECT.
- CONTRACTOR SHALL PREPARE CHALK-LINE LAYOUT FOR EXACT LOCATION AND MOUNTING HEIGHTS OF ALL RECEPTACLES, SWITCHES, JUNCTION BOXES, DISCONNECT SWITCHES, AND ELECTRICAL EQUIPMENT FOR ARCHITECT AND OWNER REVIEW AND APPROVAL.
- ALL ELECTRICAL WORK FOR FABRICATED FOODSERVICE EQUIPMENT SHALL BE COMPLETELY WIRED BY THE FABRICATION CONTRACTOR TO A COMMON JUNCTION BOX, PULL BOX, OR CONTROL PANEL ON THE EQUIPMENT IN A ACCESSIBLE LOCATION. FINAL CONNECTIONS TO THE EQUIPMENT AND ALL ELECTRICAL WORK FROM THE MAIN PANEL BOARDS SHALL BE BY THE ELECTRICAL CONTRACTOR (E.C.).
- FINAL CONNECTIONS TO ALL FOODSERVICE EQUIPMENT SHALL BE BY THE ELECTRICAL CONTRACTOR, INCLUDING ALL MATERIALS.
- ALL GENERAL PURPOSE AND COUNTER TOP 120V 15A AND 20A RECEPTACLES IN PREPARATION AREAS AND AREA EXPOSED WITH IN 6FT OF OPEN WATER SOURCE SHALL BE GFCI PROTECTED BY BREAKER OR DEVICE.
- CATEGORY 6 CABLE AND CONDUIT (UNDER THE SLAB) FROM THE POS DEVICES TO THE A/V EQUIPMENT CABINET WILL BE REQUIRED.
- COORDINATION WITH THE TERMINAL OPERATOR FOR DATA/INTERNET ACCESS SUPPORTING THE EDGE SWITCH LOCATED IN THE A/V EQUIPMENT CABINET IS REQUIRED.
- ELECTRICAL CONTRACTOR OR EQUIVALENT SHALL FURNISH AND INSTALL THE FOLLOWING:
  - ALL JUNCTION BOXES, OUTLETS, COVER PLATES, SWITCHES, ETC... NOT BUILT INTO THE KITCHEN EQUIPMENT.
  - ALL JUNCTION BOXES, OUTLETS, COVER PLATES, ETC... IN DISHROOMS OR AS NOTED ON THE SCHEDULE SHALL BE MOISTURE PROOF.
  - ALL PLUGS AND CORDS AS NOTED ON THE SCHEDULE. ALL CORDS SHALL BE NEMA RATED AND UL APPROVED FOR MANUFACTURED AND FABRICATED EQUIPMENT.
  - SHUNT TRIP CIRCUIT BREAKERS OR DISCONNECTS FOR FIRE CONTROL SYSTEM SHUT-OFF OF FOODSERVICE EQUIPMENT BENEATH EXHAUST HOODS AS REQUIRED BY N.F.P.A.-96, LATEST EDITION AND LOCAL CODES.
  - DISCONNECTS OR OTHER DEVICES AS REQUIRED BY CODES.
  - STARTERS.
  - ALL CONTROL WIRING FOR KITCHEN EQUIPMENT SYSTEMS.
- FURNISH AND INSTALL ALL NECESSARY ELECTRICAL CONNECTIONS.
- REFER TO ARCHITECTURE AND FOOD SERVICE DRAWINGS FOR RECEPTACLE MOUNTING HEIGHT.



**ELECTRICAL POWER PLAN**  
 SCALE: 1/4" = 1'-0"





| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

|  |                   |
|--|-------------------|
| DESIGN DELIVERABLE:                                      | ISSUED FOR PERMIT |
| ISSUE DATE:  | 08/16/2024        |
| PROJECT NUMBER:  | 24017G            |
| DRAWN BY:  |                   |
| CHECKED BY:  |                   |
| Copyright (c) by Environetics, Inc. All Rights Reserved. |                   |

SHEET TITLE:  
**ELECTRICAL POWER PLAN**

SHEET NUMBER:  
**E-101**



CONTRACTOR TO PROVIDE INDIVIDUAL HOMERUNS IN 1" CONDUIT FROM EACH DATA OUTLET BACK TO PATCH PANEL. (TYP)

CONTRACTOR SHALL VERIFY EXACT LOCATIONS WITH ARCH DRAWINGS. PROVIDE DATA CABLING FOR SPEAKERS BACK TO TENANT PATCH PANELS IN INDIVIDUAL HOMERUNS (TYP)

CONTRACTOR TO PROVIDE (1) DATA CABLE FOR EACH CAMERA. EACH LOW VOLTAGE ITEM REQUIRES DATA CABLE + 12' ADDITIONAL SLACK IN INDIVIDUAL CONDUIT. RUN HOMERUNS BACK TO PATCH PANEL (TYP).

DVR, ALL CAMERA CABLES SHALL BE TERMINATED TO THIS LOCATION.

SERVER DATA RACK. COORDINATE LOCATED WITH ARCH AND OWNER. EC SHALL PROVIDE NEW DATA CABLES AS NEEDED FOR RELOCATION.

AUDIO AMP, ALL AUDIO CABLES SHALL BE TERMINATED TO THIS LOCATION

EC SHALL PROVIDE 2' X 5' X 3/4" PLYWOOD BACKBORD IN ACCORDANCE WITH OSHA STANDARDS. PAINTED WITH FIRE RETARDANT PAINT. COORDINATE WITH ARCHITECT ON FINAL LOCALION.

**DATA & COMMUNICATION SPECIFICATIONS**

DATA / COMMUNICATION CLOSET

- 1. PULL FOUR (4) CAT6 CABLES FOR [T1 CONNECTION / DSL CONNECTION / VOICE HANDOFF / 1 SPARE] BUILDING NEAREST EXISTING DATA/TELECOM ROOM TO DATA COMMUNICATION RACK PATCH PANEL INSIDE SPACE SHALL BE COORDINATED WITH BUILDING MANAGEMENT ON LOCATION OF NEAREST DATA/TELECOM ROOM. (PROVIDE 10FT OF ADDITIONAL SLACK COILED AT STORE TERMINATION SIDE)

CASH WRAP

- 1. PULL FOUR (4) CAT6 CABLES FROM THE 24 PORT PATCH PANEL TO EACH REGISTER AND TERMINATED BOTH ENDS WITH RJ45 JACKS CONNECTION INTO 4-PORT PLATE.
- 2. 4-PORT PLATE SHALL BE IN GANG BOX THAT SHALL BE SECURELY ATTACH TO MILL WORK.

GENERAL REQUIREMENTS

- 1. PROVIDE 5FT OF ADDITIONAL SLACK OF CAT6 CABLE COILED FOR FUTURE NEEDS; TYP FOR EACH RUN.
- 2. INDICATE WITH A LABEL EACH PORT ON THE WALL PLATE CORRESPONDING TO THE PORT IN THE PATCH PANEL CERTIFY CONTINUITY OF EACH PHONE LINE.
- 3. FOLLOW ALL LOCAL AND/OR BUILDING CODES AND ADJUST THE ABOVE INSTALLATION TO MEET THOSE CODES.
- 4. GC IS RESPONSIBLE TO COORDINATE ACCESS TO COMMUNICATIONS CLOSET WITH THE FACILITY COMMUNICATION MANAGER.
- 5. GC IS RESPONSIBLE TO PULL COMMUNICATION WIRING AND CONDUIT FROM EXISTING AND NEW IT/COMMUNICATION ROOMS INTO THE WAHLBURGERS SPACE AND TO TERMINATE ON BOTH SIDES.
- 6. PLENUM RATED CABLE IS ALLOWED ABOVE THE CEILING.

TENANT NOTE

- 1. EC SHALL CONNECT ALL DATA CABLES BACK TO TOGETHER BACK BONE RACK LOCATED IN STORE. COORDINATE WITH OWNER ON LOCATION PRIOR TO BID. HORIZONTAL CABLES OVER 290 LINEAR FEET WILL BE INTERCONNECTED WITH FIBER MULTIMODE CONNECTION EC SHALL PROVIDE ALL EQUIPMENT AS NEEDED FOR INSTALLATION.
- 2. EC SHALL FURNISH AND INSTALL ALL EQUIPMENT AS NEEDED FOR AUDIO VISUAL DATA DEVICES, WHICH ARE REQUIRED FOR COMPLETE INSTALLATION. PLEASE REFER TO VENDOR CUT SHEET AND DRAWINGS FOR ADDITIONAL INFORMATION.
- 3. EC SHALL COORDINATE WITH VENDOR PRIOR TO BID TO VERIFY ALL CONDUIT DROP LOCATIONS AND TERMINATIONS.
- 4. IN ADDITION TO ABOVE, EC SHALL PROVIDE BUSHING FOR DATA CONDUITS, CAT5E/CAT6 CABLING AND DRAG LINES FOR EMPTY CONDUIT.

NOTES:

- 1. ALL COMMUNICATIONS WIRING, FACEPLATES, JACKS, TERMINATIONS, ETC. SHALL BE FURNISHED AND INSTALLED BY THE ELECTRICAL CONTRACTOR. ALL CABLING MUST BE IN 3/4" CONDUIT MINIMUM. (U.O.N)
- 2. ALL EXISTING TO REMAIN LOW VOLTAGE CABLES LEFT IN SPACE TO BE SUPPORTED BY "J" HOOKS.
- 3. GC IS RESPONSIBLE TO RUN ALL CONDUITS, WIRING, AND CABLING. GC TO COORDINATE WITH ELEC, ARCH, AND IT/COMM DRAWINGS FOR COMPLETE INSTALLATION REQUIREMENT.

**ELECTRICAL COMMUNICATION PLAN**

SCALE: 1/4" = 1'-0



| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

|                     |                   |
|---------------------|-------------------|
| DESIGN DELIVERABLE: | ISSUED FOR PERMIT |
| ISSUE DATE:         | 08/16/2024        |


PROJECT NUMBER: 24017G  
DRAWN BY:  
CHECKED BY:

Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE:

**ELECTRICAL COMMUNICATION PLAN**

SHEET NUMBER:  
**E-102**




John J. Guth, PE  
FL LIC# 60427


**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA

**LIGHTING NOTES**

- FOR EXACT LOCATION AND MOUNTING HEIGHTS OF ALL LIGHTING FIXTURES AND SWITCHES SEE ARCHITECTURAL DRAWINGS.
- CIRCUIT NUMBERS INDICATED ARE FOR IDENTIFICATION PURPOSES ONLY. CONTRACTOR SHALL RUN ALL CIRCUITS TO CORRESPONDING PANEL (#), UNLESS OTHERWISE NOTED.
- CONTRACTOR SHALL FURNISH AND INSTALL ALL REQUIRED CONDUIT, WIRE AND BOXES AS WELL AS CEILING OUTLETS AND WHIPS TO ENERGIZE LIGHTING FIXTURES AS SHOWN.
- ALL BRANCH CIRCUIT WIRING SHALL BE RUN CONCEALED IN WALLS AND ABOVE HUNG CEILING. WHERE THERE IS NO HUNG CEILING CONDUIT SHALL BE RUN IN A NEAT AND ORDERLY MANNER PARALLEL AND PERPENDICULAR TO HVAC DUCTWORK AND FIRE PROTECTION SPRINKLER PIPING. NO FLEXIBLE CONDUIT IS PERMITTED IN AREAS WHERE IT WILL BE EXPOSED.
- CONTRACTOR SHALL MAINTAIN CONTINUITY IN ALL EXISTING CIRCUITRY TO REMAIN WHICH IS AFFECTED BY THE SCOPE OF WORK. CONTRACTOR TO FURNISH AND INSTALL ALL REQUIRED WIRES, CONDUIT AND JUNCTION BOXES REQUIRED TO KEEP CONTINUITY.
- REFER TO ARCHITECTURAL DRAWING FOR THE EXACT LOCATION OF SWITCH BOX. FINAL LOCATION TO BE COORDINATED WITH ARCHITECT.
- MULTIPLE SWITCHES AT A COMMON LOCATION SHALL BE INSTALLED IN A COMMON MULTIGANG BOX WITH A COMMON FACEPLATE. GROUP THEM AS REQUIRED TO MEET MANUFACTURER'S REQUIREMENT. COORDINATE WITH ARCHITECT FOR FINAL LOCATIONS OF SWITCHES.
- EC SHALL PROVIDE 90 MINUTE BATTERY PACKS FOR ALL LIGHTING FIXTURES DESIGNATED WITH "EM."
- ALL FIXTURES IN WORK ROOM, BACK AND FRONT LINE, ABOVE CONDIMENT CART, AND ANY OTHER AREAS WHERE EXPOSED FOOD, CLEAN EQUIPMENT OR UTENSILS, OR UNWRAPPED SINGLE SERVICE ITEMS WILL BE EXPOSED, SHALL HAVE SHATTERPROOF LAMPS IF THE FIXTURE IS NOT LENSED. ARCHITECT OF RECORD TO INCLUDE APPROPRIATE LAMPS / FIXTURES ON DRAWINGS AND SCHEDULES, AND COMPLY WITH ANY ADDITIONAL JURISDICTIONAL LIGHTING REQUIREMENT.
- ADJUST FOCUS OF ALL TRACK AND RECESSED DIRECTIONAL LIGHTING TO FULLY ILLUMINATE ALL ARTWORK, MENU BOARDS, AND MERCHANDISE BAYS. COORDINATE AIMING WITH OWNER.
- BALLAST BOXES, TRANSFORMERS, JUNCTION BOXES, AND WIRING FOR ALL LIGHT FIXTURES TO BE INSTALLED HIDDEN FROM VIEW.
- CONTRACTOR SHALL FURNISH AND INSTALL NEW DTS400B TIME CLOCK, NEW SE 8903LG1200V02 LIGHTING CONTACTOR, NEW SSA403 OVERRIDE SWITCH, (5) PILOT LIGHT DIMMER SWITCHES, ADJACENT TO ELECTRICAL PANEL. CIRCUITS 36 & 38 TO BE CONTROLLED VIA LIGHTING CONTACTOR ON CHANNEL 1. CIRCUIT 38 TO BE CONTROLLED VIA CHANNEL 2.
- CONTRACTOR TO PROTECT EXISTING BASE-BUILDING LIGHTING FIXTURES DURING CONSTRUCTION.



**ELECTRICAL LIGHTING PLAN**  
SCALE: 1/4" = 1'-0"



**COMcheck Software Version 4.1.5.5**  
**Interior Lighting Compliance Certificate**

**Project Information**  
Energy Code: 2018 IECC  
Project Title: B-FB4 - WAHLBURGERS  
Project Type: New Construction  
Owner/Agent: Designer/Contractor:  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243

**Additional Efficiency Package(s)**  
Credits: 1.0 Required 0.0 Proposed

**Allowed Interior Lighting Power**

| A Area Category                                       | B Floor Area (ft <sup>2</sup> ) | C Allowed Watts / ft <sup>2</sup> | D Allowed Watts (B X C)    |
|---|---------------------------------|-----------------------------------|----------------------------|
| 1-Common Space Types:Dining Area - Bar Lounge/Leisure | 1100                            | 0.93                              | 1023                       |
| Allowance: Other retail highlighting / Fix. ID: C     | 1100 (a)                        | 0.45                              | 198 (b)                    |
| Allowance: Other retail highlighting / Fix. ID: E     | 1000 (a)                        | 0.45                              | 203 (b)                    |
| Allowance: Other retail highlighting / Fix. ID: G     | 1000 (a)                        | 0.45                              | 35 (b)                     |
|   |                                 |                                   | Total Allowed Watts = 1459 |

(a) Allowance claims for "Merchandise Highlighting" exceed total activity area. Code official must verify claims are acceptable.  
(b) Allowance is (B x C) or the actual wattage of the fixtures given in Section 2, whichever is less.

**Proposed Interior Lighting Power**

| A Fixture ID - Description / Lamp / Wattage Per Lamp / Ballast | B Lamps/ Fixture | C # of Fixtures | D Watt. (C X D)             |
|--|------------------|-----------------|-----------------------------|
| 1-Common Space Types:Dining Area - Bar Lounge/Leisure          |                  |                 |                             |
| LED 1: A: 24"x24" LED TROFFER: Other:                          | 1                | 8               | 40                          |
| LED 2: B: 4" ROUND DOWNLIGHT: RECESSED: Other:                 | 1                | 31              | 20                          |
| LED 3: C: BULB PENDANT LIGHTS: Other:                          | 1                | 11              | 18                          |
| LED 4: E: LED TAPE LIGHT: Other:                               | 1                | 1               | 203                         |
| LED 5: G: CANOPY LIGHTING: Other:                              | 1                | 1               | 35                          |
|  |                  |                 | Total Proposed Watts = 1376 |

**Interior Lighting PASSES: Design 6% better than code**

**Interior Lighting Compliance Statement**  
Compliance Statement: The proposed interior lighting design represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed interior lighting systems have been designed to meet the 2018 IECC requirements in COMcheck Version 4.1.5.5 and to comply with any applicable mandatory requirements listed in the Inspection Checklist.

Name - Title: \_\_\_\_\_ Signature: \_\_\_\_\_ Date: \_\_\_\_\_

Project Title: B-FB4 - WAHLBURGERS  
Data filename: Vgd-myc-4s013Project17061.E011Drawings\CadDwg95Elect\Comcheck\_2024-07-23.cck  
Report date: 08/14/24  
Page: 2 of 9

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |

DESIGN DELIVERABLE: ISSUED FOR PERMIT  
ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G  
DRAWN BY:  
CHECKED BY:


Copyright (c) by Environetix, Inc. All Rights Reserved.

SHEET TITLE:  
**ELECTRICAL LIGHTING PLAN**

SHEET NUMBER:  
**E-201**





# ELECTRICAL RISER DIAGRAM



- 1 EXISTING DISTRIBUTION PANEL DP9 LOCATED IN EXISTING ELECTRICAL ROOM (X120). IT HAS BEEN VERIFIED THAT THIS MAIN DISTRIBUTION PANEL HAS ENOUGH ELECTRICAL CAPACITY TO HANDLE THE NEW ELECTRICAL LOADS IN THE NEW ELECTRICAL TENANT PANEL.
- 2 EXISTING 3P/110A WHICH FEEDS TENANT SPACE B-FB4, TO REMAIN AND BE PROTECTED DURING CONSTRUCTION.
- 3 EXISTING 3#2, 1#6G WIRES IN EXISTING 1-1/4" CONDUIT TO REMAIN AND BE PROTECTED DURING CONSTRUCTION.
- 4 NEW 4#4/0 1#2 WIRES IN EXISTING 2-1/2" CONDUIT TO TENANT SPACE.
- 5 NEW TIME CLOCK & 12 POLE SQUARE D LIGHTING CONTACTOR. REFER TO DETAILS. COORDINATE PROGRAMMING WITH TENANT.

| LEGEND: |   |
|---------|---|
|         | NEW EQUIPMENT, CONDUIT OR WIRE                    |
|         | EXISTING EQUIPMENT, CONDUIT OR WIRE TO REMAIN     |
|         | EXISTING EQUIPMENT, CONDUIT OR WIRE TO BE REMOVED |



**ENV**  
ARCHITECTURE + DESIGN  
180 SYLVAN AVENUE, SUITE 3  
ENGLEWOOD CLIFFS, NJ 07632  
TEL 201 | 894 | 1000  
ENV-team.com

ENVIRONETICS GROUP ARCHITECTS, P.C.  
COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED

CLIENT:  
**SSP AMERICA**  
20408 BASHAN DRIVE  
SUITE 300  
ASHBURN, VA 20147

PROJECT TEAM:  
ARCHITECT:  
ENVIRONETICS GROUP ARCHITECTS  
180 SYLVAN AVE.  
ENGLEWOOD CLIFFS, NJ 07632

MEP ENGINEER  
GUTH DECONZO CONSULTING  
ENGINEERS, P.C.  
520 8TH AVENUE, SUITE 2201  
NEW YORK, NY 10018  
CERTIFICATE OF AUTHORIZATION  
CA LIC. NO. 27747





John J. Guth, PE  
FL LIC# 60427

**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA



| REV  | DATE              | DESCRIPTION |
|--|-------------------|-------------|
| DESIGN DELIVERABLE:                                      | ISSUED FOR PERMIT |             |
| ISSUE DATE:  | 08/16/2024        |             |
| PROJECT NUMBER:  | 24017G            |             |
| DRAWN BY:  |                   |             |
| CHECKED BY:  |                   |             |
| Copyright (c) by Environetics, Inc. All Rights Reserved. |                   |             |

SHEET TITLE:  
**ELECTRICAL RISER DIAGRAM**

SHEET NUMBER:  
**E-301**



TYPICAL KITCHEN HOOD WIRING DIAGRAM / LAYOUT (VIA SHUNT-TRIP)




**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: 08/16/2024  
 ISSUED FOR PERMIT

PROJECT NUMBER: 24017G  
 DRAWN BY:  
 CHECKED BY:

SHEET TITLE:  
**ELECTRICAL DETAILS**  
 SHEET NUMBER:  
**E-401**



| PANEL DESIGNATION:<br><b>B-FB4</b><br>NEW      |        | LOCATION: AS INDICATED ON DRAWING     |     |        |        |      |     | REMARKS: 22 KAIC   |        |  |  |
|--|--------|---------------------------------------|-----|--------|--------|------|-----|--|--------|--|--|
|  |        | SERVICE: 120/208 VOLTS 3 PHASE 4 WIRE |     |        |        |      |     | NEUTRAL BUS:<br>GROUNDING: EQUIPMENT GROUND BUS:<br>ISOLATED GROUND BUS: |        |  |  |
|  |        | BUS: 225 AMP                          |     |        |        |      |     |  |        |  |  |
|  |        | MOUNTING TYPE: SURFACE                |     |        |        |      |     |  |        |  |  |
|  |        | MAIN CIRCUIT BREAKER: 225 AMP         |     |        |        |      |     |  |        |  |  |
|  |        | MAIN LUGS ONLY: NO                    |     |        |        |      |     |  |        |  |  |
| SERVICE TO:                                    | LOAD   | TRIP                                  | NO. | A      | B      | C    | NO. | TRIP   | LOAD   | SERVICE TO:                                    |  |
| B1: GLASSWASHER                                | 1728   | 20                                    | 1   | 2208   |        |      | 2   | 20   | 480    | B5: REACH IN UNDERCOUNTER FREEZER              |  |
| B6: REFRIGERATED BACKBAR CABINET               | 264    | 20                                    | 3   |        | 364    |      | 4   | 20   | 100    | EXT LIGHT                                      |  |
| B7: REFRIGERATED BACKBAR CABINET               | 264    | 20                                    | 5   |        |        | 984  | 6   | 20   | 720    | B10: POS                                       |  |
| B12: DRAFT BEER COOLER                         | 264    | 20                                    | 7   | 1664   |        |      | 8   | 20   | 1400   | K18: COFFEE/TEA BREWER<br>(3#12, 1#12G, 3/4"C) |  |
| RECIRCULATION PUMP                             | 120    | 20                                    | 9   |        | 1520   |      | 10  |  | 1400   |  |  |
| K7: FRYER BATTERY WITH SHUNT TRIP              | 672    | 20                                    | 11  |        |        | 1176 | 12  | 20   | 504    | K5: EQUIPMENT STAND WITH SHUNT TRIP            |  |
|  |        |                                       | 13  | 0      |        |      | 14  |  |        |  |  |
| K7: FRYER BATTERY WITH SHUNT TRIP              | 672    | 20                                    | 15  |        | 1687.2 |      | 16  | 20   | 1015.2 | K8: REACH IN FREEZER WITH SHUNT TRIP           |  |
|  |        |                                       | 17  |        |        | 0    | 18  |  |        |  |  |
| K11: REACH IN FREEZER                          | 1015.2 | 20                                    | 19  | 1975.2 |        |      | 20  | 20   | 960    | K12: REACH IN REFRIGERATOR                     |  |
| K14: MEGA TOP PREPA. REFRIGERATOR              | 732    | 20                                    | 21  |        | 2532   |      | 22  | 20   | 1800   | K16: TOASTER (Nema 5-15P)                      |  |
| K21: FRENCH FRY WARMER<br>(3#12, 1#12G, 3/4"C) | 1450   | 20                                    | 23  |        |        | 1810 | 24  | 20   | 360    | SELF ORDERING KIOSK                            |  |
|  | 1450   |                                       | 25  | 2890   |        |      | 26  | 20   | 1440   | K22: WARMING DRAWER                            |  |
| K36: DISHWASHER                                | 1920   | 20                                    | 27  |        | 1920   |      | 28  | 20   |        | SPARE  |  |
| K32: POS                                       | 720    | 20                                    | 29  |        |        | 720  | 30  | 20   |        | SPARE  |  |
| K34: SODA ICE & BEVERAGE DISPENSER             | 120    | 20                                    | 31  | 1320   |        |      | 32  | 20   | 1200   | K37: BAG N BOX                                 |  |
| K23.1: HEAT LAMP<br>(2#12, 1#12G, 3/4"C)       | 930    | 20                                    | 33  |        | 1830   |      | 34  | 20   | 900    | GENERAL RECEPTACLES                            |  |
|  | 930    |                                       | 35  |        |        | 2306 | 36  | 20   | 1376   | LIGHTING*                                      |  |
| TV   | 750    | 20                                    | 37  | 1250   |        |      | 38  | 20   | 500    | SIGNAGE  |  |
| DATA RACK                                      | 500    | 20                                    | 39  |        | 1250   |      | 40  | 20   | 750    | TV   |  |
| TIMECLOCK/CONTACTOR                            | 180    | 20                                    | 41  |        |        | 180  | 42  | 20   |        | SPARE  |  |
| K39: ICE MAKER<br>(2#12, 1#12G, 3/4"C)         | 998.4  | 20                                    | 43  | 1898.4 |        |      | 44  |  | 900    | EXHAUST FAN<br>(4#12, 1#12G, 3/4"C)            |  |
|  | 998.4  |                                       | 45  |        | 1898.4 |      | 46  | 20   | 900    |  |  |
| HOT GAS WATER HEATER                           | 100    | 20                                    | 47  |        |        | 1000 | 48  |  | 900    |  |  |
| GENERAL RECEPTACLES                            | 720    | 20                                    | 49  | 2676   |        |      | 50  |  | 1956   | FCU-BOH<br>(4#10, 1#10G, 1"C)                  |  |
| SPARE  |        | 20                                    | 51  |        | 1956   |      | 52  | 30   | 1956   |  |  |
| SPARE  |        | 20                                    | 53  |        |        | 1956 | 54  |  | 1956   |  |  |
| K1: EXHAUST HOOD WITH SHUNT TRIP               | 1200   | 20                                    | 57  |        | 3156   |      | 58  | 30   | 1956   | FCU-FOH<br>(4#10, 1#10G, 1"C)                  |  |
|  |        |                                       | 59  |        |        | 1956 | 60  |  | 1956   |  |  |

|                                 | SEC. 1  | TOTAL (VA) | DEMAND FACTORS            | DEMAND LOAD (VA) |
|---------------------------------|---------|------------|---------------------------|------------------|
| CONNECTED LIGHTING LOAD (VA):   | 1976    | 1976       | 125%                      | 2470             |
| CONNECTED RECEPTACLE LOAD (VA): | 2580    | 2580       | 1st 10kVA + 50% REMAINDER | 2580             |
| CONNECTED KITCHEN LOAD (VA):    | 28147.2 | 28147      | 70%                       | 19703.04         |
| CONNECTED MISC. LOAD (VA):      | 15336   | 15336      | 100%                      | 15336            |
| CONNECTED ELEC. HEAT LOAD (VA): | 0       | 0          | 100%                      | 0                |
| CONNECTED A/C LOAD (VA):        | 0       | 0          | 100%                      | 0                |
| PANEL TOTAL DEMAND LOAD (kVA):  |         |            |                           | <b>40.08904</b>  |
| PANEL TOTAL DEMAND LOAD (AMPS): |         |            |                           | <b>111</b>       |
| PERCENT SPARE :                 |         |            |                           | <b>25%</b>       |
| PANEL TOTAL AMPACITY (AMPS):    |         |            |                           | <b>139</b>       |

**DTS Timeclock**  
 Channel 1: Contactor 1 (Marked with \*)  
 Channel 2: Spare  
 Channel 3: Spare  
 Channel 4: Signage

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: ISSUED FOR PERMIT  
 ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G  
 DRAWN BY:  
 CHECKED BY:

COPYRIGHT (c) BY ENVIRONETICS, INC. ALL RIGHTS RESERVED.  
 SHEET TITLE:  
**ELECTRICAL SCHEDULES**

SHEET NUMBER:  
**E-501**



ELECTRICAL SPECIFICATIONS

2.10 CABLE SUPPORT

- A. CABLE SUPPORT SHALL BE J-HOOK SPACED 5' ON CENTER. J-HOOKS SHALL BE CADDY CAT21 AND CAT32 AS REQUIRED.
B. J-HOOKS SHALL BE FURNISHED COMPLETE WITH ALL PIECES REQUIRED TO ACHIEVE THE LAYOUT INDICATED. SUPPORTS SHALL BE SUPPORTED FROM BUILDING STEEL WITH SUPPORTS SPACED NO GREATER THAN 5' ON CENTER.

2.11 NOT USED

3.01 GROUNDING

- A. THE DISTRIBUTION SYSTEM SHALL BE COMPLETELY AND PROPERLY GROUNDED USING APPROVED FITTINGS. SEPARATE INSULATED GROUND CONDUCTORS SHALL BE RUN WITH ALL FEEDERS, RECEPTACLE BRANCH CIRCUITS AND FLEXIBLE CONNECTIONS TO LIGHTING FIXTURES AND EQUIPMENT.
B. METAL RACEWAYS, METAL ENCLOSURES OF ELECTRICAL DEVICES AND OTHER EQUIPMENT SHALL BE COMPLETELY GROUNDED IN AN APPROVED MANNER. PROPER HARDWARE REQUIRED FOR A COMPLETE GROUNDING SYSTEM SHALL BE INSTALLED BY THE CONTRACTOR.
C. WYE-CONNECTED TRANSFORMER SECONDARIES SHALL BE GROUNDED TO BUILDING STEEL, COLD WATER PIPING OR A DRIVEN GROUND ROD IN ACCORDANCE WITH CODE REQUIREMENTS FOR DERIVED SYSTEMS.
D. CONDUITS TERMINATING AT CABLE TRAYS SHALL BE BONDED TO THE TRAY WITH A #6 BARE COPPER JUMPER.
E. GROUND RODS SHALL BE 3/4 X 10'-0" COPPERWELD TYPE WITH EXOTHERMICALLY WELDED CONNECTIONS.
F. RAISED FLOORS SHALL BE GROUNDED WITH #6 AWG BARE COPPER CONDUCTORS BONDED TO EVERY SECOND PEDESTAL IN EVERY OTHER ROW OF PEDESTALS. TWO (2) DIAGONAL CORNER PEDESTALS OF THE FLOOR SYSTEM SHALL BE BONDED WITH AN APPROVED GROUNDING CLAMP AND #6 GROUNDING CABLE TO NEAREST BUILDING STEEL. EXOTHERMIC WELD CABLE TO FLANGE OF BUILDING STEEL. FLOOR GROUND CONDUCTOR LAYOUT SHALL NOT CREATE LOOPS.

3.02 SPLICES AND TERMINATIONS

- A. NO SPLICES OR JOINTS WILL BE PERMITTED IN EITHER FEEDER OR BRANCHES EXCEPT AT OUTLETS OR ACCESSIBLE TERMINAL, SPLICE OR JUNCTION BOXES.
B. ALL MATERIALS REQUIRED FOR MAKING SPLICES AND/OR TERMINATIONS SHALL BE SUPPLIED IN COMPLETE KITS NOT OLDER THAN 6 MONTHS. THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ENSURING THAT ALL MATERIALS FURNISHED WILL NOT ADVERSELY AFFECT THE PHYSICAL OR ELECTRICAL PROPERTIES OF OTHER MATERIALS FURNISHED OR OF THE WIRE OR CABLE ITSELF.
C. WHERE THE CONTRACTOR MAKES CONNECTIONS TO EXISTING WIRES, HE SHALL OPEN AND DISCONNECT THE EXISTING SPLICES FROM SUCH WIRES AND INSTALL NEW SPLICES TO INCLUDE THE EXISTING WIRES AS REQUIRED.
D. ALL SPLICES FOR WIRE SIZES #10 AWG AND SMALLER SHALL BE MADE WITH INSULATED SPRING CONNECTOR APPLIED TO TWISTED CONDUCTORS. TWO HALF LAPPED LAYERS OF VINYL TAPE EXTENDING A DISTANCE OF NOT LESS THAN ONE INCH FROM THE CONNECTOR SHALL BE APPLIED. SPLICES OTHER THAN THE AFOREMENTIONED WILL BE PERMITTED AT THE DISCRETION OF THE ENGINEER.
E. ALL SPLICES FOR WIRE SIZES #8 AND LARGER SHALL BE MADE WITH COMPRESSION TYPE CONNECTORS WITH PRE-MOLDED COVER OVER WHICH TWO HALF LAPPED LAYERS OF VINYL TAPE EXTENDING A DISTANCE OF NOT LESS THAN ONE INCH FROM THE CONNECTOR SHALL BE APPLIED.

3.03 REMOVALS

- A. NOTES AND GRAPHIC REPRESENTATIONS ON THE DRAWINGS SHALL NOT LIMIT THE EXTENT OF REMOVALS REQUIRED. THE CONTRACTOR SHALL VISIT THE SITE AND CAREFULLY EXAMINE EXISTING CONDITIONS AND SHALL PERFORM ALL WORK REQUIRED TO ACHIEVE THE FINAL DESIGN INTENT AS REQUIRED BY THE CONTRACT DOCUMENTS. THE EXTENT OF ALL REMOVAL WORK SHALL BE COORDINATED WITH THE ARCHITECT.
B. WHERE PORTIONS OF AN EXISTING BRANCH CIRCUIT ARE REMOVED, WIRING TO REMAIN DEVICES ON THE CIRCUIT SHALL BE RECONNECTED OR MODIFIED IN AN APPROVED MANNER AS REQUIRED TO MAINTAIN CONTINUITY OF THE AFFECTED BRANCH CIRCUIT AND OPERATION OF THE REMAINING DEVICES.
C. ALL WORK REQUIRED TO REMAIN IN SERVICE BUT INTERFERING WITH THE ALTERATION SHALL BE RELOCATED AND RECONNECTED USING MATERIALS AND STANDARDS OF THIS CONTRACT.
D. THE REMOVAL OF ALL TELEPHONE AND DATA DEVICES AND ASSOCIATED CABLE SHALL BE COORDINATED WITH THE APPROPRIATE BUILDING OPERATING PERSONNEL.
E. IN THE PROCESS OF REMOVING WIRING DEVICES, LIGHTING FIXTURES AND OTHER ELECTRICAL EQUIPMENT AND MATERIALS, THIS CONTRACTOR SHALL EXERCISE EXTREME CAUTION TO PREVENT DAMAGE TO ARCHITECTURAL SURFACES AND MATERIALS WHICH ARE TO REMAIN, INCLUDING WALLS, FLOORS, CEILINGS, WINDOWS, DOORS, MOLDINGS, STRUCTURAL MEMBERS, ETC. THE COST TO REPAIR OR REPLACE ANY MATERIAL DEEMED BY THE ARCHITECT TO HAVE BEEN UNDULY DAMAGED BY THIS CONTRACTOR DURING DEMOLITION OR CONSTRUCTION SHALL BE PAID BY THIS CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
F. ALL EXISTING UNUSED CONDUIT AND WIRING SHALL BE DROPPED TO THE FLOOR BY THE ELECTRICIAN FOR REMOVAL FROM THE BUILDING BY DEMOLITION OR GENERAL CONTRACTOR.

3.04 IDENTIFICATION OF WORK

- A. ALL PANELBOARDS, EQUIPMENT AND CABINETS SPECIFIED HEREIN SHALL BE CLEARLY IDENTIFIED WITH THE EQUIPMENT DESIGNATION, VOLTAGE AND AMPERE RATING, FUSE RATING, EQUIPMENT SERVED AND ORIGIN OF THE INCOMING FEED. IDENTIFICATION SHALL BE WHITE OR BLACK PLASTIC NAMEPLATE WITH 1/2" MINIMUM LETTERING ATTACHED BY SCREWS.
B. FACEPLATES OF SWITCHES FOR EQUIPMENT SUCH AS REMOTE FANS AND MOTORIZED SCREENS SHALL BE IDENTIFIED WITH THE NAME OF THE DEVICE CONTROLLED. IDENTIFICATION SHALL BE BY INDELEIBLE MARKER IN CONCEALED LOCATIONS AND ADHESIVE LABELS IN EXPOSED LOCATIONS. EMERGENCY DEVICES SHALL BE IDENTIFIED IN RED.
C. EMPTY CONDUITS SHALL BE IDENTIFIED WITH TAGS AT BOTH ENDS INDICATING THE LOCATION OF TERMINATION AT THE OPPOSITE END.
D. BALLAST COMPARTMENTS FOR FIXTURES OPERATING AT GREATER THAN 120 VOLTS SHALL BE IDENTIFIED WITH A BRIGHT ORANGE ADHESIVE WARNING LABEL.
E. ALL WIRES SHALL BE IDENTIFIED BY PANEL AND CIRCUIT NUMBER AT ALL TERMINATION AND SPLICE POINTS BY THE USE OF BRADY B-500 VINYL CLOTH TAPE OR EQUIVALENT METHOD.
F. ALL JUNCTION BOXES SHALL BE IDENTIFIED WITH PANEL AND CIRCUIT NUMBERS OF ALL CIRCUITS OR NAME OF COMMUNICATIONS SYSTEM CABLES CONTAINED WITHIN. JUNCTION BOXES IN EXPOSED LOCATIONS SHALL BE CLEARLY MARKED WITH LABELS. JUNCTION BOXES IN CONCEALED LOCATIONS SHALL BE MARKED WITH A BOLD, INDELEIBLE MARKING PEN. LETTERING SHALL BE NEATLY AND LEGIBLY PRINTED. JUNCTION BOXES ON EMERGENCY SERVICE SHALL BE PAINTED RED AND LABELED AS EMERGENCY.
G. CONDUIT RUNS FOR BRANCH CIRCUITING AND/OR COMMUNICATIONS CABLEING SHALL BE IDENTIFIED AT EVERY 50 FEET OF LENGTH, AND AT EACH OUTLET AND PULL BOX WITH CIRCUIT NUMBER OR SYSTEM NAME.
H. ALL OUTLETS AND SWITCHES SHALL BE LABELED WITH CIRCUIT AND PANEL INFORMATION USING P-TOUCH TYPE LABEL.

3.05 INSTALLATION OF LIGHTING FIXTURES

- A. LOCATIONS OF LIGHTING FIXTURES INDICATED ON THE DRAWINGS ARE APPROXIMATE. CONTRACTOR SHALL REFER TO ARCHITECTURAL REFLECTED CEILING PLANS FOR EXACT LOCATIONS OF ALL LIGHTING FIXTURES PRIOR TO INSTALLATION.
B. RECESSED FIXTURES SHALL BE FURNISHED COMPLETE WITH MOUNTING DEVICES AND ACCESSORIES.
C. FIXTURES SHALL BE ATTACHED TO CEILING SUPPORTING MEMBERS, AND SHALL NOT DEPEND UPON LATHING OR LASTER FOR ALIGNMENT OR SUPPORT. FIXTURES IN SUSPENDED CEILINGS SHALL BE SUPPORTED BY SADDLE HANGERS OR TIE-BARS ATTACHED TO RUNNERS OR BETWEEN CROSSBARS OF CEILING SYSTEMS. MOUNTING SPLINES OR OTHER POSITIVE MEANS OF MAINTAINING ALIGNMENT AND RIGIDITY SHALL BE PROVIDED. SUPPORTING MEMBERS SHALL BE SURFACE PASSIVATED AND SHALL BE PRIMED OR PAINT DIPPED TO RESIST CORROSION. FASTENING DEVICES SHALL BE OF A POSITIVE, LOCKING TYPE, AND SHALL NOT REQUIRE THE USE OF SPECIAL TOOLS TO REMOVE. TIE WIRES SHALL NOT BE USED IN PLACE OF FASTENING DEVICES.
D. HANGING OF LIGHTING FIXTURES IS TO BE DONE IN ACCORDANCE WITH THE FLORIDA ELECTRICAL CODE. LIGHTING FIXTURES WEIGHING UP TO AND INCLUDING 40 POUNDS MAY BE SUPPORTED FROM THE STEEL "Z" BARS. LIGHTING FIXTURES WEIGHING FROM 41 POUNDS UP TO AND INCLUDING 80 POUNDS MAY BE SUPPORTED FROM THE PURLINS. LIGHTING FIXTURES WEIGHING OVER 80 POUNDS SHALL BE SUPPORTED FROM THE BUILDING STRUCTURE AND NOT FROM THE CEILING SUSPENSION SYSTEM.
E. SPLICES SHALL NOT BE PERMITTED IN ANY RUN OF LIGHTING FIXTURE HOOKUP WIRE.
F. SEPARATELY MOUNTED OUTLET BOXES AND FLEXIBLE CONDUIT PIGTAIL CONNECTIONS (MAXIMUM LENGTH OF 6'-0") SHALL BE PROVIDED FOR LIGHTING FIXTURES RECESSED IN HUNG CEILINGS WITH ACCESSIBLE TILES. ONE (1) OUTLET BOX MAY SERVE UP TO A MAXIMUM OF FOUR (4) RECESSED LIGHTING FIXTURES.
G. ALL LIGHTING FIXTURES OPERATING AT 120V SHALL BE IDENTIFIED WITH AN ADHESIVE WARNING LABEL ATTACHED TO COVER A BALLAST COMPARTMENT.

3.06 CUTTING AND PATCHING

- A. ALL CUTTING AND PATCHING REQUIRED FOR EQUIPMENT INCLUDED IN THESE SPECIFICATIONS SHALL BE DONE BY THIS CONTRACTOR.
B. THIS CONTRACTOR SHALL NOT DO ANY CUTTING THAT MAY IMPAIR THE STRENGTH OF BUILDING CONSTRUCTION. NO HOLES ARE TO BE DRILLED INTO ANY STRUCTURAL MEMBERS. CLAMPS OR OTHER APPROVED HOLDING DEVICES ARE TO BE USED.
C. ALL CUTTING OF EXISTING FLOORS, CEILINGS AND WALLS SHALL BE PERFORMED IN A MANNER SO AS TO MINIMIZE DAMAGE TO ADJACENT MATERIALS. PATCHING OF ALL SURFACES SHALL BE PERFORMED IN A MANNER APPROVED BY THE ARCHITECT TO INSURE COMPLETE MATCHING WITH ADJACENT FINISHES AFTER FINAL TREATMENT OF SURFACES.

3.07 NOT USED

3.08 SEALING OF PENETRATIONS

- A. ALL PENETRATIONS OF WALLS, FLOORS OR CEILINGS MUST BE SEALED IN AN APPROVED MANNER USING AN OUTER CIRCUMFERENTIAL SLEEVE FILLED INSIDE AND OUT.
B. ALL PENETRATIONS OF FIRE RATED WALLS, FLOORS OR CEILINGS SHALL BE SEALED WITH APPROVED MATERIAL TO PROVIDE SAME RATING AS FLOOR, WALL OR CEILING ASSEMBLY. REFER TO ARCHITECTURAL DRAWINGS FOR LOCATIONS OF FIRE RATED PARTITIONS.

3.09 HANGERS AND SUPPORTS

- A. THREADED RODS SHALL BE FULLY GALVANIZED, MINIMUM 3/8" DIAMETER. MODULAR CHANNEL SUPPORTS SHALL BE GALVANIZED STEEL. SUPPORT CLIPS AND FASTENERS SHALL BE LISTED AND APPROVED FOR THE APPLICATION. STRAPS AND CLAMPS SHALL BE MALLEABLE IRON.
B. SUPPORTS SHALL BE SIZED TO ACCOMMODATE THE LOAD REQUIRED. ALL WORK SHALL BE SUPPORTED INDEPENDENTLY OF THE WORK OF OTHER TRADES, INCLUDING CEILING SYSTEM SUPPORTS.
C. PANELS AND EQUIPMENT LOCATED ON OTHER THAN MASONRY WALLS SHALL BE MOUNTED WITH MODULAR CHANNEL SUPPORTS SECURED TO THE BUILDING STRUCTURE.
D. APPROVED SEISMIC RESTRAINTS RATED TO RESIST 1/2G OF FORCE SHALL BE FURNISHED FOR ALL ELECTRICAL WORK WHERE REQUIRED BY LOCAL BUILDING CODES AND THE AUTHORITIES HAVING JURISDICTION.

3.10 POWER INTERRUPTION NOTE

- A. ELECTRICAL POWER MUST BE SHUT OFF PRIOR TO THE CONTRACTOR PERFORMING ANY WORK IN RACEWAYS WITH LIVE ELECTRICAL CIRCUITS OR ANY OTHER LIVE ELECTRICAL CIRCUITS OR EQUIPMENT. ANY POWER INTERRUPTION SHALL BE COORDINATED WITH THE OWNER AND BUILDING OPERATING PERSONNEL.
B. TAPS INTO LIVE RISERS ARE NOT PERMITTED.

3.11 TEMPORARY LIGHT AND POWER

- A. PROVIDE TEMPORARY LIGHT AND POWER SYSTEM (AS PART OF THE CONTRACT) ADEQUATE FOR THE REQUIREMENTS OF ALL TRADES DURING CONSTRUCTION. TEMPORARY SYSTEM SHALL BE DISCONNECTED AND REMOVED WHEN PERMANENT SERVICE IS IN OPERATION.

3.12 FINAL CLEANUP AND FIELD TESTS

- A. AFTER COMPLETION OF THE ENTIRE ELECTRICAL INSTALLATION:
1) THE CONTRACTOR, PRIOR TO FINAL ACCEPTANCE, SHALL CLEAN ALL SWITCHES, CABINETS, DEVICES PLATES, FIXTURES AND OTHER ITEMS FURNISHED UNDER THIS CONTRACT AND SHALL ENSURE THAT ALL PANELBOARD DIRECTORIES ARE IN PLACE AND COMPLETED OR REVISED AS REQUIRED BY THE WORK, AND THAT ALL IDENTIFICATION AND MARKING OF EQUIPMENT, CABLES, ALL JUNCTION BOXES AND OTHER ITEMS IS COMPLETED.
2) THE CONTRACTOR SHALL REPAIR OR REPLACE, AS DIRECTED BY THE ENGINEER, ANY ITEM DAMAGED DUE TO INSTALLATION OR RELOCATION OF EQUIPMENT OR DEVICES AT NOT ADDITIONAL COST TO THE OWNER.
B. IN ADDITION TO OTHER TESTS WHICH MAY BE REQUIRED BY OTHER DIVISIONS, PERFORM FIELD TESTS IN THE PRESENCE OF THE ENGINEER, TO DEMONSTRATE THE PROPER FUNCTIONING OF THE ELECTRICAL INSTALLATION. THE ENGINEER SHALL BE GIVEN A MINIMUM OF 48 HOURS ADVANCE NOTICE OF ALL TESTS. REQUIRED FIELD TESTS SHALL INCLUDE, BUT NOT BE LIMITED TO THE FOLLOWING:
1) OPERATION OF ALL ELECTRICAL EQUIPMENT FOR A PERIOD FOR A PERIOD OF 24 HOURS WITHOUT INTERRUPTION.
2) 1,000 VOLT MEGOHMMETER TEST FOR ALL WIRES AND CABLES FURNISHED CONTRACTOR SHALL FURNISH A TEST REPORT TO THE ENGINEER INDICATING TEST METHOD USED AND RESULTS.
C. ALL DEFECTIVE FIXTURES CABLES OR OTHER EQUIPMENT ENCOUNTERED DURING THE COURSE OF TESTING SHALL BE PROMPTLY REPLACED AND RE-TESTED TO THE SATISFACTION OF THE ENGINEER.
D. ELECTRIC WIRING FOR INSTALLATION AND RELOCATION OF FIRE ALARM DEVICES SHALL BE APPROVED BY THE FIRE DEPARTMENT. CONTRACTOR MUST FILE FORM AS REQUIRED WITH THE FIRE DEPARTMENT.

3.13 UNIT PRICE NOTES:

- A. CONTRACTOR IS TO SUBMIT UNIT PRICES FOR THE FOLLOWING LISTED ITEMS:
1) ALL CONDUITS REQUIRED FOR THIS JOB
2) ALL RECEPTACLES, WALL AND WORKSTATION MOUNTED
3) ALL LIGHT FIXTURES
4) ALL SWITCHES
5) TELEPHONE OUTLETS


3.14 PROJECT CLOSE OUT

- A. AFTER COMPLETION OF PROJECT AND PRIOR TO REQUESTING FINAL PAYMENT, THE CONTRACTOR SHALL GIVEN WRITTEN NOTICE THAT THE FOLLOWING ITEMS HAVE BEEN COMPLETED:
1) REQUIRED AGENCY APPROVALS.
2) FINAL CLEANING AND ADJUSTMENT OF LIGHTING FIXTURES AND EQUIPMENT.
3) RESOLUTION OF OUTSTANDING SUBMITTALS AND PUNCH LIST ITEMS.
4) AS-BUILT DRAWINGS
5) TURNOVER OF SPARE LAMPS, KEYS, AND ANY REQUIRED SPARE PARTS OR TOOLS.
6) SYSTEM STARTUP, TESTING AND ADJUSTMENT.
7) MANUFACTURER'S CERTIFICATIONS, WARRANTIES AND O&M MANUALS.
8) DEMONSTRATIONS AND OWNER INSTRUCTION.

ENV ARCHITECTURE + DESIGN 180 SYLVAN AVENUE, SUITE 3 ENGLEWOOD CLIFFS, NJ 07632 TEL 201 | 894 | 1000 ENV-team.com ENVIRONETICS GROUP ARCHITECTS, P.C. COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED

CLIENT: SSP AMERICA 20408 BASHAN DRIVE SUITE 300 ASHBURN, VA 20147

PROJECT TEAM: ARCHITECT: ENVIRONETICS GROUP ARCHITECTS 180 SYLVAN AVE. ENGLEWOOD CLIFFS, NJ 07632 MEP ENGINEER: GUTH DECONZO CONSULTING ENGINEERS, PC 520 8TH AVENUE, SUITE 2201 NEW YORK, NY 10018 CERTIFICATE OF AUTHORIZATION CA LIC. NO. 27747



B-FB4 - WAHLBURGERS SARASOTA BRADENTON INTERNATIONAL 6000 AIRPORT CIRCLE SARASOTA, FL 34243 CLIENT: SSP AMERICA

Table with columns for REV, DATE, and DESCRIPTION.


DESIGN DELIVERABLE: ISSUED FOR PERMIT 08/16/2024

PROJECT NUMBER: 24017G DRAWN BY: CHECKED BY:

Copyright (c) by Environetis, Inc. All Rights Reserved.

ELECTRICAL SPECIFICATIONS

SHEET NUMBER: E-602



John J. Guth, PE FL LIC# 60427

B-FB4 - WAHLBURGERS SARASOTA BRADENTON INTERNATIONAL 6000 AIRPORT CIRCLE SARASOTA, FL 34243 CLIENT: SSP AMERICA

PLUMBING SYMBOLS AND ABBREVIATIONS

Table with 2 columns: Symbol and Description. Includes Domestic Cold Water Piping, Domestic Hot Water Piping, Sanitary Piping, Grease Waste Piping, Indirect Waste Piping, Vent Piping, Gas Piping, Existing Piping to Remain, New Connection to Existing, Check Valve, Piping Up - Pierces Floor, Piping Drop - Piping Drops Within Story Height, Piping Rise - Piping Rises Within Story Height, Bottom of Pipe Take-Off, Shut-Off Valve, Cleanout, Floor Drain, Trap, Hose Bibb, Mixing Valve, Access Door, Balancing Valve Rig, Cold Water, Hot Water, Under Slab Sanitary Waste Piping, Existing Sanitary Waste Piping, Sanitary Piping, Clean Out, Vent Piping, Down, Floor Drain, Floor Sink, Filtered Cold Water, Funnel Wall Drain, Funnel Drain, Reduced Pressure Zone Assembly, Grease Interceptor, Gallons Per Minute, Thermostatic Mixing Valve, Vent Through Roof, Vacuum Breaker, Water Hammer Arrestor, Non Freeze Water Hydrant, Hose Bib.

NOTE: SYMBOL LIST AND ABBREVIATIONS PROVIDED FOR CONVENIENCE ONLY. NOT EVERY SYMBOL OR ABBREVIATION IS NECESSARILY USED.

FLORIDA PLUMBING CODE NOTES

- ALL PLUMBING WORK SHALL MEET THE REQUIREMENTS OF THE 2023 FLORIDA BUILDING CODE & 2023 FLORIDA PLUMBING CODE. 1. PROTECTION OF PIPING AS OUTLINED IN PC 305 SHALL BE PROVIDED AS REQUIRED. 2. TESTING AND INSPECTION OF PLUMBING WORK SHALL BE AS PER SECTION PC 312. 3. CONDENSATE DISPOSAL FROM HIGH EFFICIENCY FUEL BURNING APPLIANCES, EVAPORATORS AND COOLING COILS SHALL BE AS PER SECTION PC 314. 4. WATER HEATER INSTALLATION SHALL COMPLY WITH PC 502. 5. ALL PIPING AND MATERIALS SHALL BE AS DIRECTED IN PC 303. 6. PIPING JOINTS AND CONNECTIONS SHALL BE AS APPROVED IN PC 605, PC 705, PC 804 AND PC 1004. 7. CONSTRUCTION, QUANTITIES, DEVICES, FIXTURES, FAUCETS, VALVES AND FACILITIES FOR THE DISABLED SHALL BE AS OUTLINED IN PC 403. 8. TRAPS AND CLEANOUTS SHALL BE AS PER PC 1002. 9. CONSTRUCTION AND SPACING OF HANGERS AND SUPPORTS, AND SEISMIC SUPPORTS SHALL BE IN ACCORDANCE WITH SECTION PC 308 AND PC TABLE 308.5 10. WATER SUPPLY SYSTEM, VALVES, TESTS SHALL BE AS DIRECTED IN CHAPTER 6. 11. WATER SUB-METER SHALL CONFORM TO SECTION PC 606.7. 12. HOT WATER DISTRIBUTION AND RE-CIRCULATION SYSTEM SHALL BE AS PER SECTION PC 607. 13. SANITARY DRAINAGE PIPING, SIZING, GRADING AND OFFSETS SHALL BE AS OUTLINED SECTIONS PC 303 AND PC 702. 14. TRAPS SHALL BE AS PER SECTION PC 1002. 15. SIZING AND INSTALLATION OF DRAINAGE PIPING, FITTINGS AND OFFSETS SHALL BE AS PER CHAPTER 7 OF THE PLUMBING CODE. 16. VENT SIZING, GRADING, CONNECTIONS, LOCATIONS AND OFFSETS SHALL BE AS DIRECTED IN CHAPTER 9 OF THE PLUMBING CODE. 17. STORM DRAINAGE PIPING AND SIZING SHALL BE IN ACCORDANCE WITH CHAPTER 11. 18. SPECIAL AND MISCELLANEOUS PIPING SHALL BE AS DIRECTED IN PC 803. 19. INDIRECT WASTE PIPING SHALL BE AS DIRECTED IN CHAPTER 8 OF THE PLUMBING CODE. 20. GAS PIPING INSTALLATION, MATERIAL AND SIZES SHALL ADHERE TO CHAPTER 4 OF THE FUEL GAS CODE. 21. ALL PLUMBING DRAINAGE PIPING, INCLUDING AN EQUIPMENT CONNECTED THERETO, SHALL BE SEISMICALLY RESTRAINED AS PER SECTION BC 1613 AND ASCE 7-2010. 22. CLEAN OUTS FOR SANITARY DRAINAGE SHALL BE AS PER SECTION PC 708. 23. ALL SANITARY DRAINAGE PIPING SHALL BE PITCHED IN ACCORDANCE WITH SECTION PC 704.1. 24. ALL PLUMBING FIXTURES SHALL COMPLY WITH LOCAL LAW 29/89 - LOW FLOW FIXTURES. 25. THE OWNER SHALL ENGAGE THE SERVICES OF AN AGENCY APPROVED BY FLORIDA DEPARTMENT OF BUILDINGS TO PERFORM ALL REQUIRED SPECIAL INSPECTIONS (BC 1704) AND PROGRESS INSPECTIONS (BC 109), SPECIAL INSPECTION (CODE REFERENCES ARE TO THE DECEMBER 31, 2022 CODE). 26. ALL INSPECTIONS AND TESTS WILL BE MADE IN COMPLIANCE WITH BC 1704. 27. PROTECTION OF POTABLE WATER SYSTEM PER SECTION PC 608. 28. ALL PLUMBING WORK SHALL BE DONE BY OR UNDER THE DIRECT SUPERVISION OF A LICENSED MASTER PLUMBER AS PER FLORIDA ADMINISTRATIVE CODE.

BAR EQUIPMENT NOTES

- 1. PLUMBING ROUGHING FOR BAR EQUIPMENT AS DEDICATED ON THE DRAWINGS ARE APPROXIMATE, THIS CONTRACTOR SHALL REFER TO THE APPROVED BAR EQUIPMENT ROUGHING SHOP DRAWING FOR EXACT LOCATION OF CONNECTION TO EQUIPMENT. 2. THIS CONTRACTOR SHALL EXTEND AS REQUIRED, THE NECESSARY SUPPLIES (I.E. WATER, WASTE, INDIRECT WASTE, VENT, ETC.) FROM THE LOCATION ON THIS DRAWING TO FINAL CONNECTION OF ALL FLOOR DRAINS, ETC. 3. THIS CONTRACTOR SHALL COOPERATE AND COORDINATE WITH THE EQUIPMENT CONTRACTOR AND CONTRACTORS OF OTHER TRADES FOR THE EXACT LOCATION OF ALL FLOOR DRAINS, ETC. 4. WHERE POSSIBLE BRANCH PIPING TO EQUIPMENT CONNECTION SHALL BE INSTALLED CONCEALED FROM VIEW. ALL PIPING (WASTE, VENT, HOT & COLD WATER) EXPOSED TO VIEW IS TO BE CHROME PLATED. 5. PROVIDE NECESSARY SHOCK ABSORBERS, VACUUM BREAKERS, PRESSURE REDUCING VALVES, RELIEF VALVES, ETC... ON EACH BRANCH WATER LINE TO EQUIPMENT REQUIRING SAME, SEE SPECIFICATION. 6. THE ITEM NUMBERS INDICATED ON THESE DRAWINGS CORRESPOND TO THOSE ITEM NUMBERS SHOW ON THE EQUIPMENT ROUGHING DRAWINGS. 7. AT FINAL INSPECTION THE CONTRACTOR SHALL PROVIDE COPY OF WATER POTABILITY TEST RESULTS FROM A LICENSED LAB AFTER LINES HAVE BEEN CHLORINATED AS REQUIRED BY THE NATIONAL STANDARD PLUMBING CODE OR EQUIVALENT. 8. WATER TEMPERATURE FOR HANDWASHING SHALL BE SET AT 110 DEGREES F. WATER TEMPERATURE FOR SANITIZING SHALL BE SET AT 120 DEGREES F. 9. WATER POTABILITY MUST BE TESTED BY A LICENSED LAB AFTER LINES HAVE BEEN CHLORINATED. A COPY OF THE TEST RESULTS SHALL BE PROVIDED AT FINAL INSPECTION. 10. ALL FLOOR DRAINS/FLOOR SINKS SHALL BE EASILY ACCESSIBLE AND VISIBLE. 11. FLOOR DRAINS/FLOOR SINKS LOCATED WITHIN THE FOOTPRINT OF ANY CABINET SHALL BE BOXED OUT WITH A SURROUNDING COVE FOR ACCESSIBILITY/CLEANING. 12. ALL EXPOSED UTILITY SERVICE LINES AND PIPES SHALL BE INSTALLED IN A WAY THAT DOES NOT OBSTRUCT OR PREVENT THE CLEANING OF FLOORS (MIN 6" OFF FLOOR).

PLUMBING GENERAL NOTES

- ALL MATERIALS AND APPARATUS SHALL BE INSTALLED IN ACCORDANCE WITH ALL THE RULES AND REGULATIONS OF THE 2023 FLORIDA BUILDING CODE, 2023 FLORIDA PLUMBING CODE. 1. BEFORE SUBMITTING PROPOSAL, BIDDERS SHALL CAREFULLY EXAMINE EXISTING FIELD CONDITIONS AND CONTRACT DRAWINGS OF ALL TRADES. SUBMISSION OF PROPOSAL WILL BE CONSTRUCTED AS EVIDENCE THAT REQUIRED EXAMINATION HAS BEEN MADE. LATER CLAIMS FOR EXTRA LABOR, EQUIPMENT AND MATERIALS REQUIRED DUE TO EXISTING FIELD CONDITIONS, WHICH COULD HAVE BEEN FORESEEN, WILL NOT BE RECOGNIZED. 2. PROCUREMENT OF ALL PERMITS AND CERTIFICATES FOR THE INSTALLATION OF THESE SYSTEMS SHALL BE PERFORMED IN ACCORDANCE WITH ALL THE RULES AND REGULATIONS OF THE 2023 FLORIDA BUILDING CODES AND ALL OTHER AUTHORITIES HAVING JURISDICTION. 3. THE CONTRACTOR SHALL COORDINATE HIS WORK WITH ALL OTHER TRADES AT NO EXTRA COST AND PROVIDE REQUIRED OFF-SET COST FOR ANY ADDITIONAL PIPING AND FITTINGS REQUIRED PER SURVEYED FIELD CONDITIONS. CONTRACTOR MUST AVOID EXISTING/NEW STRUCTURAL, ARCHITECTURAL, MECHANICAL AND ELECTRICAL CONFLICTS BY PROPERLY PRICING BID. 4. ALL EXISTING PIPING IS SHOWN IN APPROXIMATE LOCATIONS. CONTRACTOR TO VERIFY IN FIELD ALL SIZES, LOCATIONS AND ELEVATIONS OF ALL NEW POINTS OF CONNECTION TO EXISTING PIPING. COORDINATE HIS WORK WITH ALL OTHER TRADES. 5. CONNECTION TO EXISTING SERVICES SHALL BE PERFORMED DURING OFF-WORK HOURS OR ON WEEKENDS IN PREMIUM TIME. CONNECTION PERFORMED OF NEW WORK TO EXISTING WORK SHALL BE APPROVED MANNER, RESTORING EXISTING WORK DISTURBED TO ORIGINAL CONDITION. 6. ALL NEW PIPING SHALL BE RUN CLOSE TO BEAMS, WALLS AND SLABS, SQUARE TO BUILDING CONSTRUCTION, CONCEALED ABOVE HUNG CEILING AND WITHIN FURRED SPACES. 7. ALL EXISTING PIPING, INDICATED AND/OR NOTED TO BE REMOVED, SHALL BE REMOVED BACK TO EXISTING STACKS, RISERS OR MAINS AND CAPPED/PLUGGED AT TERMINAL POINT UNLESS OTHERWISE DIRECTED BY OWNER OR ENGINEER. 8. THE CONTRACTOR SHALL NOT INTERRUPT ANY OF SERVICES OF THE EXISTING BUILDING WITHOUT THE EXPRESSED WRITTEN PERMISSION OF THE OWNER, AND SUCH INTERRUPTIONS SHALL BE AS BRIEF AS POSSIBLE, AND AT THE TIME AGREED TO WITH THE OWNER. 9. UNDER NO CIRCUMSTANCES WILL THIS CONTRACTOR, OR HIS WORKMEN BE PERMITTED TO USE ANY PART OF THE BUILDING AS A SHOP EXCEPT AREAS DESIGNATED BY OWNER. 10. EXISTING PIPING DAMAGED AS A RESULT OF PERFORMING THE WORK OF SHALL BE REPAIRED OR REPLACED AS REQUIRED WITH THIS CONTRACT EXISTING. MATERIAL AND FINISH TO MATCH. 11. ALL SHUT DOWNS AND TIE-INS SHALL BE COORDINATED WITH THE BUILDING MANAGEMENT PRIOR TO COMMENCEMENT. BUILDING MANAGEMENT SHALL DICTATE SCHEDULE OF TIE-INS AND SHUT DOWNS AS REQUIRED. 12. ALL PLUMBING WORK INDICATED OUTSIDE OF TENANT SPACES SHALL BE APPROVED BY BUILDING MANAGEMENT. 13. AT FINAL INSPECTION, PROVIDE A COPY OF THE WATER POTABILITY TEST RESULTS FROM A LICENSED LAB AFTER LINES HAVE BEEN CHLORINATED AS REQUIRED BY THE NATIONAL STANDARD PLUMBING CODE OR EQUIVALENT.

FLORIDA ENERGY COMPLIANCE:

TO THE BEST OF MY KNOWLEDGE, BELIEF AND PROFESSIONAL JUDGEMENT, THESE PLANS AND SPECIFICATIONS ARE IN COMPLIANCE WITH THE 2023 FLORIDA ECC.

BUILDING STANDARD CONTRACTOR NOTES:

- 1. THERE SHALL BE NO CUTTING OR CHANNELING INTO THE BUILDING STRUCTURAL FLOOR, CEILING, COLUMNS, OR BEAMS. 2. THERE SHALL BE NO INTERRUPTION OR RE-LOCATION OF BUILDING SERVICES, EXCEPT WITH THE CONSENT OF THE BUILDING MANAGER. 3. ALL EXISTING AND NEW VALVES MUST BE ACCESSIBLE, EITHER EXPOSED OR FROM ACCESS PANELS.

SAFETY NOTES

- 1. CONSTRUCTION WORK WILL BE CONFINED TO THE INTERIOR, AND WILL NOT CREATE DUST, DIRT, OR OTHER SUCH INCONVENIENCES TO OTHER TENANTS WITHIN THE BUILDING. 2. CONSTRUCTION OPERATION WILL NOT BLOCK HALLWAYS OR MEANS OF EGRESS FOR TENANTS OF THE BUILDING. 3. CONSTRUCTION OPERATIONS WILL NOT INVOLVE INTERRUPTION OF HEATING, WATER, OR ELECTRICAL SERVICES TO OTHER TENANTS OF THE BUILDING. 4. CONSTRUCTION OPERATIONS WILL BE CONFINED TO NORMAL WORKING HOURS, 8 AM TO 5 PM MONDAYS THROUGH FRIDAYS, EXCEPT LEGAL HOLIDAYS.

SPECIAL INSPECTIONS

Table with 4 columns: Y, N, INSPECTIONS, CODE SECTION. Includes Fire Resistant Penetrations & Joint (BC 1704.27) and Tenant Protection Plan Compliance (BC 1709.26).

LISTED INSPECTIONS ARE FOR THE PLUMBING SCOPE OF WORK ONLY. SEE ALL RELATED FILINGS FOR ADDITIONAL INSPECTIONS.

PLUMBING DRAWING LIST

Table with 2 columns: ID and Description. Includes P-001 PLUMBING NOTES, SYMBOLS AND DRAWING LIST, P-101 PLUMBING PLAN - LEVEL 1, P-102 PLUMBING PLAN - LEVEL 2, P-301 PLUMBING RISER, P-401 PLUMBING DETAILS, P-402 PLUMBING DETAILS, P-501 PLUMBING SCHEDULES, P-601 PLUMBING SPECIFICATIONS.

PLUMBING DEMOLITION & ALTERATION NOTES

- 1. ALL PLUMBING FIXTURES TO BE REMOVED SHALL BE TURNED OVER TO THE OWNER. THEY SHALL NOT BE REMOVED FROM THE PREMISES OR DISPOSED OF WITHOUT THE OWNER'S APPROVAL. 2. ALL PIPING TO BE REMOVED SHALL BE PROPERLY PLUGGED OR CAPPED SO THAT UPON COMPLETION OF ALL NEW WORK, ALL ABANDONED PIPING SHALL BE CONCEALED IN FINISHED AREAS. 3. NO DEAD ENDS SHALL BE LEFT ON ANY PIPING UPON COMPLETION OF THE PROJECT. 4. EXISTING EXPOSED PIPING NOT TO BE REUSED AND NOT SPECIFICALLY NOTED OR SHOWN ON DRAWINGS TO BE ABANDONED SHALL BE COMPLETELY REMOVED. 5. THE EXISTING SYSTEMS SHALL BE LEFT IN PERFECT WORKING ORDER UPON COMPLETION OF ALL NEW WORK. 6. LOCATIONS AND SIZES OF EXISTING PIPING ARE APPROXIMATE. EXACT SIZES AND LOCATIONS OF ALL EXISTING PIPING SHALL BE VERIFIED AT THE SITE. 7. NO REMOVED EXISTING PIPING, EQUIPMENT, ETC. SHALL BE REUSED. 8. ALL EXISTING EXPOSED, UNNECESSARY PIPING RELATED TO WORK BEING DONE SHALL BE COMPLETELY REMOVED. 9. THIS CONTRACTOR SHALL NOT INTERRUPT ANY OF THE SERVICES OF THE EXISTING FACILITY. NOR INTERFERE WITH THE SERVICES IN ANY WAY WITHOUT THE EXPRESS PERMISSION OF THE OWNER. SUCH INTERRUPTIONS AND INTERFERENCES SHALL BE MADE AS BRIEF AS POSSIBLE AND ONLY AT THE TIME STATED BY THE OWNER. 10. UNDER NO CIRCUMSTANCES SHALL THIS CONTRACTOR OR HIS WORKMEN BE PERMITTED TO USE ANY PART OF THE BUILDING AS A SHOP, EXCEPT PARTS DESIGNATED BY THE OWNER FOR SUCH PURPOSES. 11. REROUTE OR REMOVE ALL EXISTING PIPING WHERE NECESSARY TO AVOID NEW EQUIPMENT, STRUCTURAL, MASONRY OR CARPENTRY WORK AS REQUIRED BY THE PROPOSED ALTERATION.

PLUMBING FIELD EXAMINATION AND COORDINATION REQUIREMENTS


- 1. THESE DRAWINGS ARE DIAGRAMMATIC AND INDICATE THE GENERAL ARRANGEMENT OF SYSTEM AND WORK INDICATED UNDER THIS SECTION. THE CONTRACTOR SHALL CONSULT THE ARCHITECTURAL DRAWINGS & DETAILS FOR EXACT LOCATIONS OF FIXTURES, AND EQUIPMENT. 2. THE CONTRACTOR SHALL FOLLOW THE DRAWINGS IN LAYING OUT WORK AND CHECK DRAWINGS OF OTHER TRADES TO VERIFY SPACES IN WHICH WORK WILL BE INSTALLED AND MAINTAIN MAXIMUM HEADROOM AND SPACE CONDITIONS AT ALL POINTS. WHERE HEADROOM OR SPACE CONDITIONS APPEAR INADEQUATE, THE ARCHITECT SHALL BE NOTIFIED IN WRITING. THE INSTALLATION SHALL NOT PROCEED BEFORE RECEIVING THE ARCHITECT'S WRITTEN INSTRUCTIONS. 3. IF DIRECTED BY THE ARCHITECT, THE CONTRACTOR SHALL, WITHOUT EXTRA CHARGE, MAKE REASONABLE MODIFICATIONS IN THE APPROVED LAYOUT AS NEEDED TO PREVENT CONFLICT WITH WORK OF OTHER TRADES. MAINTAIN REQUIRED HEADROOM AND SPACE CONDITIONS, OR FOR PROPER EXECUTION OF THE WORK. 4. WHERE THE PLUMBING WORK WILL BE INSTALLED IN CLOSE PROXIMITY TO THE WORK OF OTHER TRADES, OR WHERE THERE IS EVIDENCE THAT THE WORK OF THE CONTRACTOR WILL INTERFERE WITH THE WORK OF OTHER TRADES, HE SHALL ASSIST IN WORKING OUT SPACE CONDITIONS TO MAKE A SATISFACTORY ADJUSTMENT. IF THE CONTRACTOR INSTALLS THE WORK BEFORE COORDINATION WITH OTHER TRADES OR SO AS TO CAUSE INTERFERENCE WITH WORK OF OTHER TRADES, HE SHALL MAKE NECESSARY CHANGES IN HIS WORK TO CORRECT THE CONDITION WITHOUT EXTRA CHARGE. 5. STUDY THE DRAWINGS AND SPECIFICATIONS IN ORDER TO INSURE COMPLETENESS OF THE WORK REQUIRED UNDER THIS SECTION. INCIDENTAL WORK ITEMS NORMAL AND NECESSARY TO COMPLETE THE WORK, THOUGH NOT SHOWN OR SPECIFIED SHALL BE INCLUDED. 6. VERIFY ALL MEASUREMENTS AND CONDITIONS IN THE FIELD BEFORE STARTING WORK. INFORMATION REGARDING THE EXISTING FIRE PROTECTION SPRINKLER SYSTEM SHOWN ON THE PLANS HAVE BEEN TAKEN FROM PREVIOUS BUILDING SHOP DRAWINGS. ANY DEVIATIONS FOUND IN THE FIELD SHOULD BE REPORTED TO THE ARCHITECT. 7. THIS CONTRACTOR SHALL SUBMIT LAYOUT DRAWINGS FOR APPROVAL BEFORE BEGINNING WORK. THESE DRAWINGS SHALL DEPICT ACTUAL FIELD CONDITIONS VERIFIED UNDER THIS CONTRACT. THEY MUST ALSO INDICATE ALL NEW AND EXISTING PIPING, FIXTURES, ETC. DRAWINGS SHALL BE TO SCALE (1/4"=1'-0") AND INDICATE ALL PERTINENT DIMENSIONS, AND PIPE SIZES. THIS CONTRACTOR SHALL SUBMIT PRINTS OF THE LAYOUT AND ALL CALCULATIONS TO THE ARCHITECT. QUANTITIES SHALL BE AS DIRECTED BY THE ARCHITECT.

ANY EXTRAS AND DEVIATIONS RESULTED FROM THE SUBSTITUTION OF THE ORIGINALLY DESIGNED CONCEPTS OR UTILIZED EQUIPMENT, WILL HAVE TO BE THE RESPONSIBILITY OF THIS CONTRACTOR AND DONE AT NO ADDITIONAL COST TO THE CLIENT.


Table with 3 columns: REV, DATE, DESCRIPTION. Includes Design Deliverable Issue Date 08/16/2024.

PROJECT NUMBER: 24017G DRAWN BY: CHECKED BY: Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE: PLUMBING NOTES, SYMBOLS AND DRAWING LIST SHEET NUMBER: P-001



**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA



**PLUMBING PLAN-LEVEL 1**  
SCALE: 1/4" = 1'-0"  
0 2 4 8 FEET

**NEW WORK NOTES**

1. ALL NEW ALTERATIONS SHALL SUBMIT PLUMBING SHOP DRAWINGS. SHOP DRAWINGS SHALL BE COORDINATED WITH FIELD CONDITIONS AND WITH AOR/EOR PRIOR TO INSTALLATION.
2. EXACT LOCATION OF BASE BUILDING PIPE STUBS, FIXTURES, PIPE SIZES TO BE FIELD VERIFIED. NOTIFY THE AOR/EOR PRIOR TO INSTALLATION.
3. CONTRACTOR SHALL PITCH NEW GREASE & SANITARY PIPING AS PER THE REQUIREMENTS OF THE FLORIDA PLUMBING CODE. THE MINIMUM PITCH SHALL BE OF 1/8" PER FOOT FOR SIZE 3" AND ABOVE. ALL PIPING SHALL BE TESTED PER THE REQUIREMENTS OF THE FLORIDA PLUMBING CODE.
4. CONTRACTOR TO NOTIFY ARCHITECT/ENGINEER OF ANY OBJECTIONS THAT MAY INTERFERE WITH PROPOSED WORK PRIOR TO THE START OF CONSTRUCTION.
5. CONTRACTOR SHALL VERIFY UNDER SLAB PIPING. IF BEAM PENETRATIONS ARE REQUIRED, PENETRATION TO BE PROVIDED WITH SIGNED AND SEALED STRUCTURAL CALCULATIONS BY STRUCTURAL ENGINEER. PLUMBING CONTRACTOR TO COORDINATE WITH STRUCTURAL ENGINEER FOR EXACT LOCATION OF PENETRATION.

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: ISSUED FOR PERMIT  
ISSUE DATE: 08/16/2024


PROJECT NUMBER: 24017G  
DRAWN BY:  
CHECKED BY:

Copyright (c) by Environetics, Inc. All Rights Reserved.  
SHEET TITLE:  
**PLUMBING PLAN-LEVEL 1**


SHEET NUMBER:  
**P-101**

CLIENT:  
**SSP AMERICA**  
 20408 BASHAN DRIVE  
 SUITE 300  
 ASHBURN, VA 20147


PROJECT TEAM:  
 ARCHITECT:  
 ENVIRONETICS GROUP ARCHITECTS  
 180 SYLVAN AVE.  
 ENGLEWOOD CLIFFS, NJ 07632  
 MEP ENGINEER  
 GUTH DECONZO CONSULTING  
 ENGINEERS, PC  
 520 8TH AVENUE, SUITE 2201  
 NEW YORK, NY 10018  
 CERTIFICATE OF AUTHORIZATION  
 CA LIC. NO. 27747



**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA



**PLUMBING SANITARY PLAN**  
 SCALE: 1/4" = 1'-0"  
 0' 2' 4' 8' FEET



**PLUMBING DOMESTIC WATER & GAS PLAN**  
 SCALE: 1/4" = 1'-0"  
 0' 2' 4' 8' FEET

- NEW WORK NOTES**
- REFER TO DRAWING P301 & P501 FOR ITEM DESIGNATION, CONNECTIONS, AND ADDITIONAL NOTES AND PIPE SIZING.
  - ALL NEW ALTERATIONS SHALL SUBMIT PLUMBING SHOP DRAWINGS. SHOP DRAWINGS SHALL BE COORDINATED WITH FIELD CONDITIONS AND WITH AOR/EOR PRIOR TO INSTALLATION.
  - EXACT LOCATION OF BASE BUILDING PIPE STUBS, FIXTURES, PIPE SIZES TO BE FIELD VERIFIED. NOTIFY THE AOR/EOR PRIOR TO INSTALLATION.
  - CONTRACTOR SHALL PITCH NEW GREASE & SANITARY PIPING AS PER THE REQUIREMENTS OF THE FLORIDA PLUMBING CODE. THE MINIMUM PITCH SHALL BE OF 1/8" PER FOOT FOR SIZE 3" AND ABOVE. ALL PIPING SHALL BE TESTED PER THE REQUIREMENTS OF FLORIDA PLUMBING CODE.
  - INSTALL ALL LISTED FIXTURES ON PLAN AS SHOWN. PROVIDE ALL NECESSARY ACCESSORIES FOR FIXTURE TO PERFORM AS PER MANUFACTURER'S REQUIREMENTS. BASE BUILDING SUPPLY WATER PIPE, LOCATION, AND SIZES TO BE VERIFIED IN FIELD.
  - CONTRACTOR TO NOTIFY ARCHITECT/ENGINEER OF ANY OBJECTIONS THAT MAY INTERFERE WITH PROPOSED WORK PRIOR TO THE START OF CONSTRUCTION.
  - CONTRACTOR TO PROVIDE TRAP PRIMER FOR ALL FLOOR DRAINS. SEE P402 FOR DETAIL.
  - CONTRACTOR SHALL FURNISH AND INSTALL IW PIPE TO NOTED FIXTURES AS SHOWN ON THE PLANS

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: ISSUED FOR PERMIT  
 ISSUE DATE: 08/16/2024


PROJECT NUMBER: 24017G  
 DRAWN BY:  
 CHECKED BY:

Copyright (c) by Environetix, Inc. All Rights Reserved.

SHEET TITLE:  
**PLUMBING PLAN-LEVEL 2**

SHEET NUMBER:  
**P-102**





| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

|                     |                   |
|---------------------|-------------------|
| DESIGN DELIVERABLE: | ISSUED FOR PERMIT |
| ISSUE DATE:         | 08/16/2024        |

PROJECT NUMBER: 24017G

DRAWN BY:





CHECKED BY:

Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE:


# PLUMBING RISER

## P-301






**System No. W-L-2078**  
**F Ratings — 1 and 2 Hr (See Item 1)**  
**T Ratings — 0, 1 and 2 Hr (See Items 2 and 3)**  
**L Rating At Ambient — 3 CFM/sq ft**  
**L Rating At 400 F — Less Than 1 CFM/sq ft**



1. Wall Assembly — The fire-rated gypsum board/stud wall assembly shall be constructed of the materials and in the manner specified in the individual U300, U400, V400 or W400 Series Wall and Partition Designs in the UL fire Resistance Directory and shall include the construction features noted below:  
 A. Studs — Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm) lumber spaced max 16 in. (406 mm) OC. Steel studs to be min 2-1/2 in. (64 mm) wide and spaced max 24 in. (610 mm) OC.  
 B. Gypsum Board\* — Nom 5/8 in. (16 mm) thick gypsum board, as specified in the individual Wall and Partition Design. Max diam of opening is 11-1/2 in. (292 mm).  
 The hourly F Rating of the firestop system is equal to the hourly fire rating of the wall assembly in which it is installed.  
 2. Through-Penetrants — One nonmetallic pipe, conduit or tubing to be installed within the firestop system. The annular space between pipe and periphery of opening shall be min 0 in. (point contact) to max 1/2 in. (13 mm). Pipe or conduit to be rigidly supported on both sides of the wall assembly. The following types and sizes of nonmetallic pipes may be used:  
 A. Polyvinyl Chloride (PVC) Pipe — Nom 10 in. (254 mm) diam (or smaller) Schedule 40 solid-core or cellular core PVC pipe for use in closed (process or supply) or vented (drain, waste or vent) piping system.  
 B. Chlorinated Polyvinyl Chloride (CPVC) Pipe — Nom 10 in. (254 mm) diam (or smaller) SDR13.5 CPVC pipe for use in closed (process or supply) piping systems.  
 C. Acrylonitrile Butadiene Styrene (ABS) Pipe — Nom 6 in. (152 mm) diam (or smaller) Schedule 40 solid-core or cellular core ABS pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems.  
 D. Flame Retardant Polypropylene (FRPP) Pipe — Nom 6 in. (152 mm) diam (or smaller) Schedule 40 FRPP pipe for use in closed (process or supply) or vented (drain, waste or vent) piping system.  
 E. Polyvinylidene Fluoride (PVDF) Pipe — Nom 4 in. (102 mm) diam (or smaller) PVDF pipe for use in closed (process or supply) or vented (drain, waste or vent) piping system.  
 When max 6 in. diam pipe is used, T Rating is equal to the hourly fire rating of the wall. When nom 8 in. or 10 in. (203 or 254 mm) diam pipe is used, T Rating is 0 hr.  
 3. Firestop Device\* — Firestop Collar — Firestop collar shall be installed in accordance with the accompanying installation instructions. Collar to be installed and latched around the pipe and secured to both sides of the wall using the anchor hooks provided with the collar. (Minimum two anchor hooks for 1-1/2 and 2 in. (38 and 51 mm) diam pipes, three anchor hooks for 3 and 4 in. (76 and 102 mm) diam pipes, four anchor hooks for 6 in. (152 mm) diam pipes, ten anchor hooks for 8 in. (203 mm) diam pipes and twelve anchor hooks for 10 in. (254 mm) diam pipes. The anchor hooks are to be secured to the surface of wall with 3/16 in. (4.8 mm) diam by 2-1/2 in. (64 mm) long steel toggle bolts along with washers. As an alternate for pipe sizes of nom 4 in. diam or less, min No. 10 by 1-1/2 in. (254 by 38 mm) long drywall or laminate screws with min 3/4 in. (19 mm) steel washers may be used. When the drywall or laminate screw is used, T Rating shall not exceed 1 hr.  
 HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP 643 50/1.5"N, CP 643 63/2"N, CP 643 90/3"N, CP 643 110/4"N, CP 643 160/6"N, CP 644 200/8" and CP 644 250/10" Firestop Collars  
 4. Fill, Void or Cavity Material\* — Sealant - (Not Shown) — Min 1/2 in. (13 mm) thickness of sealant applied within the annular space for nom 8 in. and 10 in. (203 and 254 mm) diam pipes, flush with each side of wall. Sealant in annular space is optional for max 6 in. (152 mm) diam pipes. A min 1/4 in. (6 mm) thickness of sealant is required within the annular space, flush with each side of wall, to attain the L Ratings for max 6 in. (152 mm) diam pipes.  
 HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-One Sealant or FS-ONE MAX Intumescent Sealant  
 \* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.




**FIRE STOPPING DETAIL**  
NTS



| WITHOUT INCOMPRESSIBLE INSULATING BLOCK AT HANGER |               |                       |
|---|---------------|-----------------------|
| PIPE DIAMETER                                     | SHIELD LENGTH | SHIELD THICKNESS USGG |
| UP TO 3"  | 12"           | 18                    |
| 4"  | 15"           | 16                    |
| 5"  | 18"           | 16                    |
| 6"  | 21"           | 16                    |
| 8" & LARGER                                       | 24"           | 14                    |



NOTE: HANGER, ROD & INSERT SHALL BE DIPPED IN ZINC CHROMATE PRIMER PRIOR TO INSTALLATION

**TYPICAL INSULATED PIPE SUPPORT DETAIL**




NOTES:  
 1. PROVIDE REMOTE TYPE THERMOMETERS IF MOUNTED HIGHER THAN 8FT. ABOVE FLOOR  
 2. INSTALL THERMOMETERS IN OVERSIZED TEES.


**TYPICAL HANGING ELECTRIC WATER HEATER DETAIL**  
NTS




**PIPE SLEEVES THRU WALL DETAIL**  
NTS



**NO-HUB PIPE BRACING FOR HORIZONTAL PIPING (6" & LARGER) DETAIL**  
NTS




**INSTALLATION DETAIL OF PRESSURE GAUGE**  
NTS



**SSP AMERICA**  
 20408 BASHAN DRIVE  
 SUITE 300  
 ASHBURN, VA 20147

PROJECT TEAM:  
 ARCHITECT:  
 ENVIRONETICS GROUP ARCHITECTS  
 180 SYLVAN AVE.  
 ENGLEWOOD CLIFFS, NJ 07632  
 MEP ENGINEER  
 GUTH DECONZO CONSULTING  
 ENGINEERS, PC  
 520 8TH AVENUE, SUITE 2201  
 NEW YORK, NY 10018  
 CERTIFICATE OF AUTHORIZATION  
 CA LIC. NO. 27747




**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA

DESIGN DELIVERABLE: PERMIT  
 ISSUE DATE: 08/16/2024


PROJECT NUMBER: 24017G  
 DRAWN BY:  
 CHECKED BY:

**PLUMBING DETAILS**


**P-401**




**FLOOR SINK DETAIL**  
NTS




**FLOOR DRAIN TRAP SEAL PROTECTION DETAIL**




**TYPICAL FLOOR DRAIN FOR INDIRECT WASTE DETAIL**  
NTS




**HUBLESS PIPE BRACING FOR VERTICAL PIPING DETAIL**  
NTS



**HUBLESS PIPE BRACING LOCATION FOR HORIZONTAL PIPING DETAIL**  
NTS



**INSULATION OF PIPING, VALVES AND FITTINGS FOR EXPOSED AND CONCEALED LOCATIONS DETAIL**  
NTS




| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: ISSUED FOR PERMIT  
ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G  
DRAWN BY:  
CHECKED BY:

Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE:  
**PLUMBING DETAILS**



John J. Guth, PE FL LIC# 60427

PLUMBING FIXTURE SCHEDULE (KITCHEN)

Table with columns: ITEM #, QTY, EQUIPMENT CATEGORY, COLD WATER SIZE (IN), FILTERED COLD WATER SIZE (IN), HOT WATER 110" SIZE (IN), HOT WATER 120" SIZE (IN), HOT WATER 140" SIZE (IN), DIRECT WASTE SIZE (IN), INDIRECT WASTE SIZE (IN), GAS SIZE, NATURAL GAS (BTU), REMARKS. Includes items like GRIDDLE, FRYER BATTERY, HAND SINK, WORK TABLE, COFFEE/TEA BREWER, WATER FILTER, PRE-RINSE FAUCET, 3-COMP. SINK, WORK TABLE/ PREP SINK, MOP SINK, SODA ICE & BEVERAGE DISPENSER, DISHWASHER, BAG-N-BOX/CO2 TANK, ICE MAKER, ICE BIN, STORAGE CABINET, GLASSWASHER, ICE BIN WITH SINK COMBO UNIT, BOTTLE STORAGE, SPEED RAIL, UNDERBAR DUMP SINK UNITS, GLASS RINSER, DIPPER WELL, DRAINBOARD, DRAFT BEER COOLER, WATER FILTER.

DOMESTIC LOAD VALUES WSFU

Table with columns: ITEM#, DESCRIPTION, QTY, WSFU, TOTAL WSFU. Includes items like HAND SINK, WORK TABLE W/HAND SINK, COFFEE/TEA BREWER, PRE-RINSE FAUCET, WORK TABLE/ PREP SINK, MOP SINK, SODA ICE & BEVERAGE DISPENSER, DISHWASHER, BAG-N-BOX/CO2 TANK, ICE MAKER, STORAGE CABINET W/HAND SINK, GLASSWASHER, HAND SINK, UNDERBAR DUMP SINK UNITS, GLASS RINSER, DIPPER WELL, DRAFT BEER COOLER, GRAND TOTAL.

TOTAL WSFU C.W.+H.W. = 32 W.S.F.U. =32.5 GPM MINIMUM REQUIRED PIPE SIZE: 1 1/4" AT 32.5 GPM FOR TYPE L COPPER TUBE

DOMESTIC HOT WATER STORAGE HEATER CALCULATIONS

Table with columns: ITEM #, EQUIPMENT CATEGORY, QTY, TYPE OF EQUIPMENT, GPH, TOTAL GPH. Includes items like HAND SINK, WORK TABLE W/HAND SINK, PRE-RINSE FAUCET, WORK TABLE/ PREP SINK, MOP SINK, DISHWASHER, GLASSWASHER, HAND SINK, STORAGE CABINET W/HAND SINK, UNDERBAR DUMP SINK UNITS. Summary rows for POSSIBLE TOTAL DEMAND, DEMAND FACTOR, STORAGE CAPACITY FACTOR, HEATER STORAGE CAPACITY, WATER HEATER 1 HR SUPPLY.

GAS WATER HEATER SCHEDULE

Table with columns: ITEM#, MANUFACTURER, QTY, MODEL #, STORAGE CAPACITY (GAL), DOMESTIC HW TEMP. OUT, INPUT RATING BTU/HR, MAX WORKING PRESSURE (PSI), REMARKS. Includes item GWH-1 by A.O. SMITH.

PLUMBING FLOOR DRAIN & SINK CONNECTION SCHEDULE

Table with columns: ITEM#, DESCRIPTION, VENT SIZE (IN), WASTE SIZE (IN), MODEL & MANUFACTURER. Includes items FD-X (FLOOR DRAIN) and FS-X (FLOOR SINK).

HOT WATER RECIRCULATION PUMP SCHEDULE

Table with columns: DESIGNATION, TAG, QTY REQUIRED, G.P.M., T.D.H., FT., MANUFACTURE MODEL NO. (BASED ON), MECH. SEAL, STAGES, VERT. CLOSE-COUPLED, MAX WORKING PRESS., WATTS, R.P.M., VOLTS, PHASE, CYCLE, REMARKS. Includes item HWRP-1.

GAS EQUIPMENT

Table with columns: DESIGNATION, TAG, QTY, MANUFACTURER, MODEL #, TOTAL BTU/HR NATURAL, GAS SIZE, REMARKS. Includes items GRIDDLE, FRYER BATTERY, GAS WATER HEATER, TOTAL.

Table with columns: REV, DATE, DESCRIPTION. Includes a row for DESIGN DELIVERABLE: PERMIT ISSUE DATE: 08/16/2024.

PROJECT NUMBER: 24017G DRAWN BY: CHECKED BY:

Copyright (c) by Environetics, Inc. All Rights Reserved. SHEET TITLE:

PLUMBING SCHEDULES SHEET NUMBER: P-501



FIRE PROTECTION SYMBOLS

Table with 2 columns: Symbol and Description. Includes symbols for new concealed sprinkler head, remove existing piping, existing piping, new piping, connections, floor control valve, fire department connection, and sprinkler node.

SPRINKLER ABBREVIATIONS

Table with 2 columns: Abbreviation and Full Name. Lists abbreviations for floor levels, valves, pipes, and other fire protection components.

SPRINKLER NOTES

- 1. THE INSTALLATION, COMPONENTS, SIZING, SPACING, LOCATION, CLEARANCES, POSITION AND TYPE OF SYSTEMS SHALL CONFORM TO 2023 FLORIDA BUILDING CODE, NFPA 13 (2022) AND FLORIDA FIRE CODE 2021, FIRE PROTECTION DOCUMENTATION TO BE PROVIDED PER FLORIDA STATUTE 61-G15.
2. ONLY APPROVED MATERIALS SHALL BE USED AS PER CHAPTER 6 OF NFPA 13.
...
40. PER THE FLORIDA 61-G15 LESS THAN 50 SPRINKLER HEADS ARE BEING ADDED/MODIFIED. THEREFORE, A FULL DELEGATE FIRE SPRINKLER DESIGN IS NOT REQUIRED.

SPRINKLER HEAD LEGEND

Table with 7 columns: SYMBOL, RESPONSE TYPE, K-FACTOR, MANUFACTURER MODEL NO. & STYLE, SIN, TEMPERATURE RATING, ESCUTCHEON TYPE/FINISH. Lists specific head models like RA3415 and RA3614.

TEMPORARY FIRE SAFETY AND PROTECTION MEASURES

- 1. FULL COMPLIANCE WITH RULES OF THE 2023 FLORIDA BUILDING CODE.
2. FULL COMPLIANCE WITH 2023 FLORIDA BUILDING CODE CHAPTER 33, SAFEGUARDS DURING CONSTRUCTION AND DEMOLITION.
...
22. ANY AND ALL OTHER AUTHORITY OF FLORIDA RULES, REGULATIONS, LAWS ETC. RELATING TO CONSTRUCTION OPERATIONS AND SITE SAFETY SHALL BE COMPLIED WITH.

DRAWING LIST

Table with 2 columns: DRAWING NO. and DRAWING TITLE. Lists drawings SP-001 through SP-601.

CONSTRUCTION GENERAL NOTES

- 1. THE SPRINKLER CONTRACTOR WILL BE HELD RESPONSIBLE TO HAVE VISITED AND EXAMINED THE PREMISES BEFORE SUBMITTING HIS PROPOSAL, IN ORDER TO UNDERSTAND THE CONDITIONS RELATED TO HIS WORK.
2. ALL MATERIALS AND APPARATUS SHALL BE INSTALLED IN ACCORDANCE WITH ALL THE RULES AND REGULATIONS OF THE FLORIDA 2023 BUILDING CODES AND ALL OTHER AUTHORITIES HAVING JURISDICTION & NFPA.
...
14. CONTRACTOR SHALL SUBMIT ALL FINAL COORDINATED DRAWINGS IN AUTOCAD FORMAT.


SPRINKLER DESIGN CRITERIA

- 1. SPRINKLER SYSTEM LAYOUT AND CALCULATIONS SHALL COMPLY WITH NFPA-13 (2022), LOCAL BUILDING CODE FLORIDA STATE CONSTRUCTION CODE 2023, LOCAL FIRE DEPARTMENT OWNERS INSURANCE UNDERWRITERS AND ALL OTHER AUTHORITIES HAVING JURISDICTIONS.
2. DESIGN CRITERIA FOR CEILING PROTECTION PLAN: PIPE SIZES SHALL BE REQUIRED BY THE AUTHORITIES HAVING JURISDICTION AND SHALL BE CALCULATED AS FOLLOWS:
...
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RECEIVING FLOW TEST INFORMATION TO PREPARE HYDRAULIC CALCULATIONS AND OBTAIN APPROVAL FROM ALL AUTHORITIES HAVING JURISDICTION OVER THE SPRINKLER WORK...

ENV ARCHITECTURE + DESIGN
180 SYLVAN AVENUE, SUITE 3
ENGLEWOOD CLIFFS, NJ 07632
TEL 201 | 894 | 1000
ENV-team.com

SSP AMERICA
20408 BASHAN DRIVE
SUITE 300
ASHBURN, VA 20147

PROJECT TEAM:
ARCHITECT: ENVIRONETICS GROUP ARCHITECTS
180 SYLVAN AVE.
ENGLEWOOD CLIFFS, NJ 07632
MEP ENGINEER: GUTH DECONZO CONSULTING ENGINEERS, PC
520 8TH AVENUE, SUITE 2201
NEW YORK, NY 10018
CERTIFICATE OF AUTHORIZATION CA LIC. NO. 27747



John J. Guth, PE
FL LIC# 60427

B-FB4 - WAHLBURGERS
SARASOTA BRADENTON INTERNATIONAL
6000 AIRPORT CIRCLE
SARASOTA, FL 34243
CLIENT: SSP AMERICA

Table with 2 columns: REV and DESCRIPTION. Shows revision history.

DESIGN DELIVERABLE: ISSUED FOR PERMIT
ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G
DRAWN BY: LR/DR
CHECKED BY: SB


Copyright (c) by Environetix, Inc. All Rights Reserved.

SHEET TITLE:
SPRINKLER NOTES, SYMBOLS AND DRAWING LIST


SHEET NUMBER: SP-001

CLIENT:  
**SSP AMERICA**  
 20408 BASHAN DRIVE  
 SUITE 300  
 ASHBURN, VA 20147

PROJECT TEAM:  
 ARCHITECT:  
 ENVIRONETICS GROUP ARCHITECTS  
 180 SYLVAN AVE.  
 ENGLEWOOD CLIFFS, NJ 07632  
 MEP ENGINEER  
 GUTH DECONZO CONSULTING  
 ENGINEERS, P.C.  
 520 8TH AVENUE, SUITE 2201  
 NEW YORK, NY 10018  
 CERTIFICATE OF AUTHORIZATION  
 CA LIC. NO. 27747




**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA



NOTES:

|   |    |
|---|----|
| 1. NEW SPRINKLER HEADS:                     | 9  |
| 2. SPRINKLER HEADS TO BE CAPPED             | 2  |
| 3. EXISTING SPRINKLER HEADS TO BE RELOCATED | 11 |
| TOTAL:                                      | 20 |

**SPRINKLER PLAN**  
 SCALE: 1/4" = 1'-0"



|  |  |
|--|--|
|  |  |
|  |  |
|  |  |
|  |  |
|  |  |
|  |  |
|  |  |
|  |  |

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |


|                     |                   |
|---------------------|-------------------|
| DESIGN DELIVERABLE: | ISSUED FOR PERMIT |
| ISSUE DATE:         | 08/16/2024        |

|                 |        |
|-----------------|--------|
| PROJECT NUMBER: | 24017G |
| DRAWN BY:       | LR/DR  |
| CHECKED BY:     | SB     |

Copyright (c) by Environetix, Inc. All Rights Reserved.

SHEET TITLE:  
**SPRINKLER PLAN**

SHEET NUMBER:  
**SP-101**



Downloaded by:  
  
 John J. Guth, PE  
 FL LIC# 60427

**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA

**HILTI KB-TZ SS 304 INSTALL SEQUENCE**

- MARK HOLE WITH CENTER PUNCH
- DRILL OUT HOLE AT 90 DEG (PARTICULAR TO MEDIUM) TO REQUIRED LENGTH PER MANUFACTURE SPECIFICATIONS
- BLOW OUT DRILLED HOLE WITH AIR TO REMOVED DUST AND DEBRIS
- INSERT CONCRETE ANCHOR INTO PRE-DRILLED HOLE AND SEAT PROPERLY TO ENSURE THE ANCHOR IS INSERTED ALL THE WAY TO THE BOTTOM. (USE SEATING TOOL)
- PROVIDE RETRAINING WASHER AND TOQUE DOWN NUT TO MANUFACTURE SPECIFICATIONS
- PROVIDE ADDITIONAL NUT TO ENSURE ANTI-BACKLASH.

| GRAVITY HANGER HORIZONTAL SPACING |  |                               |                               |
|-----------------------------------|--|-------------------------------|-------------------------------|
| NOM. PIPE SIZE (INCHES)           | STEEL PIPE SCH40 NOT LIGHT WALL MAX. SPAN (FEET) | DUCTILE-IRON MAX. SPAN (FEET) | MINIMUM ROD DIAMETER (INCHES) |
| 1                                 | 12   | NA                            | 3/8                           |
| 1 1/4                             |  |                               |                               |
| 1 1/2                             |  |                               |                               |
| 2                                 |  |                               |                               |
| 2 1/2                             | 15   | 15                            | 3/8                           |
| 3                                 |  | NA                            |                               |
| 3 1/2                             |  | 15                            |                               |
| 4                                 |  | 15                            |                               |

- THERE SHALL BE NOT LESS THAN ONE HANGER FOR EACH SECTION OF PIPE.
- WHERE SPRINKLERS ARE SPACED LESS THAN 6 FT APART, HANGERS SPACED UP TO A MAXIMUM OF 12 FT SHALL BE PERMITTED
- A BRANCH LINE ABOVE A CEILING SUPPLIES SPRINKLERS IN A PENDENT POSITION BELOW THE CEILING, THE CUMULATIVE HORIZONTAL LENGTH OF AN UNSUPPORTED ARM OVER TO A SPRINKLER OR SPRINKLER DROP SHALL NOT EXCEED 12 IN.
- THE HANGER CLOSEST TO THE SPRINKLER SHALL BE OF A TYPE THAT PREVENTS UPWARD MOVEMENT OF THE PIPE.



**NOTES:**

- THREADED STUD BOLT SIZES, LONGITUDINAL & LATERAL BRACES AND CONNECTIONS TO STRUCTURAL SUPPORTING MEMBERS SHALL BE IN ACCORDANCE WITH IBC 2021 FLORIDA ED. AND NFPA-13 [2022] CH 9 REQUIREMENTS.
- INSTALLATION DETAILS ARE FOR REFERENCE PURPOSES ONLY. CONTRACTOR SHALL SUBMIT SIGN AND SEALED BRACING CALCULATIONS BY AN LICENCE STRUCTURAL ENGINEER FOR APPROVAL IN THE SUBMITTAL PACKAGE, BASED ON INSTALLED FIELD CONDITIONS.
- EQUIPMENT SHALL BE INSTALLED PER MANUFACTURE INSTRUCTIONS.
- HANGARS AND ANCHORS SHALL COMPLY WITH THE REQUIREMENTS OF SHEET S07.041 (DETAIL 2 FOR SLAB ON METAL DECK, DETAIL 3 FOR UNTOPPED METAL DECK) IN THE BASE BUILDING CONTRACT DOCUMENTS AND THE PORT AUTHORITY TENANT CONSTRUCTION REVIEW MANUAL (TCRM).

**GRAVITY HANGING DETAIL FOR SPRINKLER PIPE**  
NOT TO SCALE

**TYPICAL CONCEALED SPRINKLER CONNECTIONS**  
NOT TO SCALE

**SCHEMATIC OF PIPING PENETRATION THRU FIRE RATED WALL**  
NOT TO SCALE



| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |


DESIGN DELIVERABLE: PERMIT  
 ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G  
 DRAWN BY: LR/DR  
 CHECKED BY: SB


COPYRIGHT (c) BY ENVIRONETICS, INC. ALL RIGHTS RESERVED.  
 SHEET TITLE:  
**SPRINKLER DETAILS**

SHEET NUMBER:  
**SP-401**





**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA



MINIMUM DISTANCE BETWEEN HANGERS - STEEL PIPE

| NOMINAL PIPE SIZE (in.)              | 1/2"   | 3/4"   | 1"     | 1 1/4" | 1 1/2" | 2"     | 2 1/2" | 3"     | 3 1/2" | 4"     | 6"     | 8"     |
|--------------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| STEEL PIPE EXCEPT THREADED LIGHTWALL | 12'-0" | 12'-0" | 13'-0" | 13'-0" | 13'-0" | 13'-0" | 13'-0" | 13'-0" | 13'-0" | 13'-0" | 13'-0" | 13'-0" |

MAX ARMORER W/O HANGER WHEN SYSTEM PRESSURE OVER 100 PSI = 1'-0"

NOTES:  
1. HANGARS AND ANCHORS SHALL COMPLY WITH THE REQUIREMENTS OF SHEET S07.041 (DETAIL 2 FOR SLAB ON METAL DECK, DETAIL 3 FOR UNTOPPED METAL DECK) IN THE BASE BUILDING CONTRACT DOCUMENTS AND THE PORT AUTHORITY TENANT CONSTRUCTION REVIEW MANUAL (TCRM).

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: DESIGN PERMIT  
ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G  
DRAWN BY:  
CHECKED BY:

Copyright (c) by Environetics, Inc. All Rights Reserved.

SHEET TITLE:  
**SPRINKLER DETAILS**

SHEET NUMBER:  
**SP-402**

# SPRINKLER SPECIFICATIONS

**1. GENERAL**

A. THE SPRINKLER CONTRACTOR SHALL BE A LICENSED, AUTHORIZED INSTALLER OF SPRINKLER SYSTEMS AND SHALL HAVE HAD A MINIMUM OF FIVE YEARS EXPERIENCE IN THE INSTALLATION OF SPRINKLER SYSTEMS.

B. BEFORE SUBMITTING HIS BID, THE SPRINKLER CONTRACTOR SHALL VISIT THE SITE AND SHALL FULLY FAMILIARIZE HIMSELF WITH THE STRUCTURAL LAYOUT OF THE EXISTING BEAMS IN RELATIONSHIP TO THE NEW HVAC DUCT LAYOUT AND NEW LIGHTING FIXTURES AND HUNG CEILING HEIGHTS AND BECOME FAMILIAR WITH THE DIFFICULTIES THAT WILL ATTEND THE EXECUTION OF THIS WORK. CONTRACTOR SHALL PERFORM THIS PRIOR TO SUBMITTING HIS BID. SUBMISSION OF A BID WILL BE CONSTRUED AS EVIDENCE THAT SUCH AN EXAMINATION HAS BEEN MADE, AND LATER CLAIMS WILL NOT BE RECOGNIZED FOR EXTRA LABOR, EQUIPMENT OR MATERIALS REQUIRED BECAUSE OF DIFFICULTIES ENCOUNTERED WHICH COULD HAVE BEEN FORESEEN HAD SUCH AN EXAMINATION BEEN MADE.

C. UPON REVIEW OF SPRINKLER DRAWINGS PRIOR TO SUBMITTING HIS PROPOSAL, THE SPRINKLER CONTRACTOR SHALL INFORM ARCHITECT AND/OR ENGINEER OF ANY DISCREPANCIES OR REQUEST CLARIFICATION IN WRITING, IF NECESSARY, CONCERNING THE INTENT OF THE PLANS AND SPECIFICATIONS TO PROVIDE A COMPLETE SPRINKLER INSTALLATION. LATER CLAIMS WILL NOT BE RECOGNIZED FOR EXTRA LABOR, EQUIPMENT OR MATERIALS SHOULD SUCH PROCEDURE NOT BE FOLLOWED.

D. THE SCHEDULING OF THE SPRINKLER WORK SHALL BE COORDINATED WITH THE BUILDING OWNER, WITH OTHER CONTRACTORS AND WITH CLIENT.

E. NECESSARY SHUT-DOWNS OF BASE BUILDING SPRINKLER SYSTEM MUST BE COORDINATED WITH THE BUILDING OWNER AND CLIENT. SHUT-DOWNS OF BASE BUILDING SYSTEMS SHALL TAKE PLACE AFTER OR BEFORE NORMAL BUSINESS HOURS AND SHALL BE CONSIDERED OVERTIME WORK.

F. THE SPRINKLER SYSTEM SHALL BE COMPLETE WITH ALL PIPE, FITTING, VALVES DRAINAGE SYSTEM AND VALVES, SPRINKLER HEADS, HANGERS AND SUPPORTS, ALSO MISCELLANEOUS WORK ITEMS, SUCH AS, SIGNS AS REQUIRED, VALVE TAGS, ETC., AND ALL OTHER RELATED EQUIPMENT, APPARATUS, AND MATERIAL ITEMS NECESSARY FOR COMPLETE, SATISFACTORY OPERATING AND APPROVED TYPE SYSTEM.

G. ALL PIPE FITTINGS, HANGERS, SUPPORTS, SPRINKLER HEADS, ETC., SHALL CONFORM TO THE FLORIDA 2023 BUILDING CODE AND NATIONAL FIRE PROTECTION ASSOCIATION'S REQUIREMENTS AS TO TYPES OF MATERIALS, ARRANGEMENT, SIZES, AND INSTALLATION EXCEPT THAT NO FACE OR FLUSH BUSHING SHALL BE USED. REDUCING FITTINGS SHALL BE PROVIDED IN LIEU OF BUSHINGS.

**2. WORK INCLUDED**

A. WORK SHALL INCLUDE ALL SPRINKLER WORK FURNISHED AND INSTALLED FOR THE CLIENT.

1) ALL WORK SHALL COMPLY WITH REQUIREMENTS OF THE FLORIDA 2023 BUILDING CODE.

2) WORK SHALL ALSO INCLUDE THE REMOVAL OF EXISTING SPRINKLER PIPING, HEADS, AND SUPPORTS AS NOTED.

3) WORK SHALL ALSO INCLUDE FURNISHING AND INSTALLING A COMPLETE WET SPRINKLER SYSTEM AS INDICATED ON THE PLANS. CONTRACTOR'S ELECTRICIAN SHALL BE FULLY FAMILIAR WITH THE OPERATION OF THE WET SYSTEM AND ITS INTERCONNECTIONS.

B. SPRINKLER SYSTEM SHALL BE:

1) A HYDRAULICALLY DESIGNED SYSTEM IN ACCORDANCE WITH THE STANDARDS OF THE NATIONAL FIRE PROTECTION ASSOCIATION, THE BUILDING CODE OF FLORIDA.

2) DESIGN SYSTEM TO CONFORM WITH BUILDING STRUCTURAL, MECHANICAL AND ELECTRICAL SYSTEMS, EITHER EXISTING OR PROPOSED.

C. THESE DRAWINGS ARE DIAGRAMMATIC AND INDICATE THE GENERAL LOCATION OF WORK SCALED DIMENSIONS SHALL NOT BE USED. ANY DIMENSIONS NOT SHOWN SHALL BE OBTAINED FROM THE ARCHITECTURAL DRAWINGS, FOR EXACT LOCATIONS, MOUNTING HEIGHTS, ETC., REFER TO ARCHITECTURAL DRAWINGS AND DETAILS. ALL DIMENSIONS, ETC., SHALL BE VERIFIED BY FIELD CHECK.

**3. SHOP DRAWINGS AND DATA**

A. THE CONTRACTOR SHALL SUBMIT, FOR APPROVAL, FULLY COORDINATED SHOP DRAWINGS, CAPACITY DATA, HYDRAULIC CALCULATIONS AND CATALOG CUTS OF THE FOLLOWING:

1) PIPE AND FITTINGS  
 2) SPRINKLER HEADS  
 3) HANGERS AND SUPPORTS  
 4) SPRINKLER AND PIPING LAYOUT  
 5) HYDRAULIC CALCULATIONS  
 6) VALVES, O.S.&Y. FLOOR CONTROL VALVE, PRESSURE REDUCING VALVE AND PRESSURE RELIEF VALVE  
 7) TAMPER SWITCH

**4. BUILDING DEPARTMENT FILING, PERMITS, AND CERTIFICATES**

A. THE SPRINKLER CONTRACTOR SHALL FILE ALL REQUIRED DRAWINGS AND SPECIFICATIONS WITH THE PORT AUTHORITY AND BE RESPONSIBLE FOR OBTAINING FINAL APPROVAL. THIS CONTRACTOR SHALL SUBMIT THE REQUIRED WITH THE FIRE DEPARTMENT AND OBTAIN ALL FINAL APPROVALS. IN ADDITION THIS CONTRACTOR IS TO SUBMIT TO THE FIRE DEPARTMENT FOR THEIR APPROVAL, A SHOP DRAWING INDICATING ALL OF THE SYSTEMS COMPONENTS. THIS DRAWING SHALL INCLUDE ALL OF THE NECESSARY SYMBOLS, NOTES AND WIRING DIAGRAMS AS REQUIRED FOR APPROVAL. THIS DRAWING IS TO BE SIGNED AND SEALED BY THE CONTRACTOR'S LICENSED ENGINEER AS REQUIRED FOR THE FINAL BUILDING AND FINAL FIRE DEPARTMENT APPROVALS.

**5. INSPECTION AND TESTING**

A. THE SPRINKLER SYSTEM SHALL BE INSPECTED AND TESTED IN ACCORDANCE WITH THE REQUIREMENTS OF THE FLORIDA BUILDING CODE.

B. THE SPRINKLER SYSTEM SHALL BE SUBJECTED TO A HYDROSTATIC PRESSURE FOR A PERIOD OF ONE HOUR AT A PRESSURE OF AT LEAST 200 PSIG OR 50 PSI IN EXCESS OF THE MAXIMUM PRESSURE TO BE MAINTAINED WHEN THE MAXIMUM PRESSURE IN THE SYSTEM IS IN EXCESS OF 150 PSI AS PER NFPA 2022.

C. BEFORE SPRINKLER SYSTEM IS CONCEALED, THE BUILDING DEPARTMENT SHALL BE NOTIFIED THAT THE SYSTEM IS READY FOR INSPECTION AND TESTING. THE BUILDING DEPARTMENT INSPECTOR SHALL WITNESS THE TEST. FINAL APPROVAL OF THE SPRINKLER SYSTEM SHALL BE OBTAINED FROM BUILDING DEPARTMENT.

**6. FLUSHING**

A. ALL FIRE PROTECTION PIPING SHALL BE FLUSHED OUT IN ACCORDANCE WITH REQUIREMENT OF THE NATIONAL FIRE PROTECTION ASSOCIATION PAMPHLET NO. 13 AND 14, LATEST EDITION.

**7. SPRINKLER PIPING**

A. ALL SPRINKLER PIPING 2" AND LESS SHALL BE SCHEDULE 40 BLACK STEEL PIPE. SPRINKLER PIPE SIZES 2 1/2" AND UP SHALL BE SCHEDULE 40 BLACK STEEL. ALL FITTINGS AND FLANGES SHALL BE AMERICAN STANDARD BLACK CAST IRON SPRINKLER FITTINGS, FLANGED OR SCREWED AS REQUIRED, DESIGNED AND MANUFACTURED FOR A WATER WORKING PRESSURE OF 175 POUNDS. VICTAULIC TYPE GROOVED FITTINGS ARE ACCEPTED TO BE INSTALLED AS PER THE MANUFACTURER'S INSTRUCTIONS.

B. SCHEDULE 10 & SCHEDULE 30 BLACK STEEL PIPE IS NOT ACCEPTABLE.

**8. TAMPER SWITCHES**

A. WHERE INDICATED ON THE DRAWINGS, FURNISH AND INSTALL VALVE TAMPER SWITCHES FOR SUPERVISION OF O.S & Y. SHUT OFF VALVES. TAMPER SWITCHES SHALL BE ADT, ITT GRINNELL CORP., AUTO-CALL OR APPROVED EQUAL. COORDINATE TAMPER SWITCHES WITH BASE BUILDING FIRE ALARM SIEMENS

**9. CUTTING AND PATCHING**

A. DO ALL CUTTING NECESSARY FOR THE INSTALLATION OF SPRINKLER WORK. ACCURATELY LAYOUT WORK FOR WHICH CUTTING IS REQUIRED, SO AS TO AVOID UNNECESSARY LARGE OPENINGS, CUTTING OF BEAMS, JOISTS, FLOORS OR WALLS OF THE BUILDING WILL NOT BE PERMITTED EXCEPT AFTER RECEIVING APPROVAL OF THE BUILDING MANAGER.

B. ROUGH PATCHING WILL BE DONE BY THIS CONTRACTOR IN A MANNER TO ACCOMMODATE FINISHED PATCHING WORK. FINISHED PATCHING WILL BE DONE UNDER ANOTHER SECTION OF THE SPECIFICATIONS.

**10. INSERTS, HANGERS, ETC.**

A. ALL SPRINKLER PIPING SHALL BE SUBSTANTIALLY SUPPORTED AND SHALL COMPLY WITH THE STANDARDS OF THE NATIONAL FIRE PROTECTION ASSOCIATION FOR THE INSTALLATION OF SPRINKLER SYSTEMS AND AS REQUIRED BY THE FLORIDA BUILDING CODE AND FACTORY MUTUAL.

B. HANGERS AND THEIR COMPONENTS SHALL BE FERROUS. HANGERS SHALL BE ADJUSTABLE, FLAT IRON TYPE OR CLEVIS TYPE.

C. SPRINKLER PIPING OR HANGERS SHALL NOT BE USED TO SUPPORT NON-SYSTEM COMPONENTS.

D. SPRINKLER PIPING SHALL BE SUBSTANTIALLY SUPPORTED FROM THE BUILDING STRUCTURE WHICH MUST SUPPORT THE ADDED LOAD OF THE WATER-FILLED PIPE PLUS A MINIMUM OF 250 LBS. APPLIED AT THE POINT OF HANGING.

E. SPRINKLER PIPING SHALL BE SUPPORTED INDEPENDENTLY OF THE CEILING SHEATHING.

F. WHEN SPRINKLER PIPING IS INSTALLED BELOW DUCTWORK, PIPING SHALL BE SUBSTANTIALLY SUPPORTED FROM THE BUILDING STRUCTURE, NOT FROM THE DUCTWORK.

G. MAXIMUM DISTANCE BETWEEN HANGERS SHALL NOT EXCEED 6 FT. FOR 1 AND 1-1/4 IN. SIZES OR 10 FT. FOR SIZES

H. EXPANSION SHIELDS FOR SUPPORTING PIPES UNDER CONCRETE CONSTRUCTION MAY BE USED IN A HORIZONTAL POSITION IN THE SIDES OF BEAMS. IN CONCRETE HAVING GRAVEL OR CRUSHED STONE AGGREGATE, EXPANSION SHIELDS MAY BE USED IN THE VERTICAL POSITION TO SUPPORT PIPES 4 IN. OR LESS IN DIAMETER.

**11. SPRINKLER HEADS**

A. ALL SPRINKLER HEADS TO BE CONSISTENT WITH BUILDING STANDARDS. MATCH EXISTING BUILDING SPRINKLERS.

B. RECESSED PENDENT SPRINKLER HEADS-RELIABLE MODEL 'F' FR58, FM APPROVED AND UL LISTED, ADJUSTABLE TYPE MAY BE USED. HEADS SHALL BE 1/2" ORIFICE, K5.6, 155 DEG. TEMPERATURE RATING, QUICK RESPONSE, SIN RA1414.

**12. ESCUTCHEONS**

A. PROVIDE ESCUTCHEONS ON ALL EXPOSED PIPING PASSING THROUGH WALLS, PARTITIONS, FLOORS AND CEILINGS. ESCUTCHEON SHALL BE HELD IN PLACE BY INTERNAL TENSION OR SET SCREW.

**13. SYSTEM SUPERVISION**

A. ALL VALVES IN SUPPLY PIPES TO SPRINKLER SYSTEMS SHALL BE SUPERVISED BY:

1) CENTRAL STATION, PROPRIETARY, OR REMOTE STATION SIGNALING SERVICE. OR,  
 2) LOCAL SIGNALING SERVICE THAT WILL CAUSE THE SOUNDING OF AN AUDIBLE SIGNAL AT A CONSTANTLY ATTENDED POINT. OR,  
 3) VALVES LOCKED IN THE CORRECT POSITION. OR,  
 4) VALVES LOCATED WITHIN FENCED ENCLOSURES UNDER THE CONTROL OF THE OWNER, SEALED IN THE OPEN POSITION, AND INSPECTED WEEKLY AS PART OF AN APPROVED PROCEDURE.

**14. FIRE WATCH**

A. FIRE SYSTEM INTERRUPTIONS: FIRE WATCH REQUIREMENTS FOR FIRE SYSTEM OUTAGES SHALL BE DETERMINED BASED ON EXTEND OF THE INTERRUPTION AND EXPECTED OUTAGE TIME OF THE INTERRUPTION. HOWEVER, IN GENERAL, A FIRE WATCH IS TO FULFILL THE INTENT OF NFPA-72 AS FOLLOWS:

1) FIRE WATCH PERSONNEL ARE TO BE FAMILIAR WITH FACILITIES AND PROCEDURES FOR SOUNDING AN ALARM IN THE EVENT OF A FIRE.

2) FIRE WATCH PERSONNEL ARE TO HAVE FIRE EXTINGUISHING EQUIPMENT READILY AVAILABLE AND BE TRAINED IN ITS USE, INCLUDING PRACTICE ON TEST FIRES.

3) NOTIFY OCCUPANTS TO EVACUATE WHEN THERE IS A FIRE IN THE BUILDING.

4) NOTIFY THE CENTRAL MONITORING STATION TO INITIATE EMERGENCY PERSONNEL RESPONSE.

5) ACTIVATE FIRE PROTECTION SYSTEMS, E.G., IN ORDER TO RELEASE DOOR HOLDERS, CLOSE SMOKE DAMPERS AND SHUT DOWN FANS.

6) THE PERSONS PERFORMING THIS TYPE OF FIRE WATCH ARE NOT TO BE PERMITTED TO PERFORM ANY OTHER DUTIES.

**15. GUARANTEE**

A. THE CONTRACTOR SHALL GUARANTEE FOR A PERIOD OF ONE (1) YEAR FROM THE DATE OF ACCEPTANCE BY THE ARCHITECT/ENGINEER, ALL MATERIALS, APPERATUS AND WORKMANSHIP WHETHER FURNISHED BY HIMSELF OR BY HIS SUBCONTRACTORS AND HE SHALL REPLACE OR REPAIR IN A MANNER APPROVED BY THE ARCHITECTS, WITHOUT COST TO THE TENANT, ANY PART OR PARTS OF THE WORK WHICH MAY PROVE DEFECTIVE OR UNSATISFACTORY WITHIN THE PERIOD OF THE GUARANTEE.

**16. SYSTEM DESIGN CRITERIA**

A. SPRINKLER SYSTEM SHALL BE DESIGNED AND INSTALLED IN ACCORDANCE WITH FLORIDA BUILDING CODE 2023 AND NFPA-13-2022.

**17. AS-BUILT DRAWINGS**

A. PREPARE AND SUBMIT "AS-BUILT" DRAWINGS AT THE COMPLETION OF THE PROJECT.

**18. INSTALLATION**

A. ALL EQUIPMENT AND MATERIALS SUITABLE AND RATED FOR SYSTEM WATER WORKING PRESSURE.

B. SPRINKLER SYSTEM SHALL BE HYDRAULICALLY CALCULATED TO DETERMINE THE SPRINKLER SYSTEM DEMAND AND REQUIRED PRESSURE.

C. THE DRAWINGS AND INFORMATION INCLUDED IN THIS SPECIFICATION ARE GIVEN AS A GUIDE ONLY AND THEY THEREFORE DO NOT RELIEVE THIS CONTRACTOR FROM PROVIDING ALL WORK AND EQUIPMENT NECESSARY TO COMPLETE THE INSTALLATION ACCORDING TO THE REQUIREMENTS, THE NUMBER AND SPACING OF SPRINKLER HEADS, HYDRAULIC CALCULATIONS, METHOD OF DRAINING LINES, ALARM VALVES, AND ALL OTHER DETAILS AND WORK SHALL BE REQUIRED BY THE LOCAL BUILDING CODE, OWNERS UNDERWRITERS, N.F.P.A. AND ALL OTHER GOVERNING AUTHORITIES.

D. THE SPRINKLER HEADS IN ALL AREAS ARE TO BE INSTALLED IN THE CENTER OF THE TILE OR CENTERED WITH LIGHTS, DIFFUSERS OR SIMILAR ELEMENTS AS INDICATED ON THE ARCHITECTURAL REFLECTED CEILING DRAWINGS. SPRINKLER HEADS MUST ALSO BE INSTALLED ON A TRUE AXIS LINE IN BOTH DIRECTIONS WITH A MAXIMUM DEVIATION FROM THE AXIS LINE OF 1/4" PLUS OR MINUS. AT THE COMPLETION OF THE INSTALLATION, IF ANY HEADS ARE FOUND TO EXCEED THE ABOVE MENTIONED TOLERANCE, SAME SHALL BE REMOVED AND REINSTALLED BY THIS CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.

E. NO PIPES, VALVES OR OTHER APPARATUS SHALL BE INSTALLED SO AS TO INTERFERE IN ANY WAY WITH THE FULL SWING OF THE DOORS.

F. THE ARRANGEMENT, POSITIONS AND CONNECTIONS OF PIPES, DRAINS, VALVES, ETC., SHOWN ON THE DRAWINGS SHALL BE TAKEN AS A CLOSE APPROXIMATION AND WHILE THEY SHALL BE FOLLOWED AS CLOSELY AS POSSIBLE. THE RIGHT IS RESERVED BY THE ARCHITECT AND/OR DESIGN ENGINEER TO CHANGE THE LOCATIONS, TO ACCOMMODATE ANY CONDITIONS WHICH MAY ARISE DURING THE PROGRESS OF THE WORK WITHOUT ADDITIONAL COMPENSATION TO THIS CONTRACTOR FOR SUCH CHANGES. PROVIDED THAT THE CHANGES ARE REQUESTED PRIOR TO THE INSTALLATION OF THIS CONTRACTOR'S WORK. THE RESPONSIBILITY FOR ACCURATELY LAYING OUT THE WORK RESTS WITH THIS CONTRACTOR. SHOULD IT BE FOUND OUT THAT ANY OF HIS WORK IS SO LAID OUT THAT INTERFERENCES WILL OCCUR, HE SHALL ALSO REPORT THAT TO THE ARCHITECT BEFORE INSTALLATION.

G. WHERE SO SHOWN, OR REQUIRED, PIPING SHALL BE INSTALLED CONCEALED IN BUILDING CONSTRUCTION.

H. ALL SCREWED PIPE THROUGHOUT THE JOB SHALL BE REAMED SMOOTH BEFORE BEING INSTALLED. PIPE SHALL NOT BE SPLIT, BENT, FLATTENED NOR OTHERWISE INJURED EITHER BEFORE OR DURING THE INSTALLATION. PROVIDE ALL SPRINKLER HEADS AND WORK IN STRICT CONFORMANCE WITH APPROVED SHOP DRAWINGS. THE ARCHITECT AND/OR DESIGN ENGINEER RESERVES THE RIGHT TO REJECT ANY AND ALL WORK NOT IN ACCORDANCE WITH THE APPROVED SHOP DRAWING.

I. WHETHER OR NOT THE SYSTEM SHOWN ON THE CONTRACT DRAWINGS MEETS THE REQUIREMENTS OF THE NATIONAL FIRE PROTECTION ASSOCIATION, THESE SPECIFICATIONS REQUIRE THE FURNISHING AND INSTALLATION OF SPRINKLER SYSTEMS COMPLETE IN ALL DETAILS AND IN ACCORDANCE WITH THE STANDARDS OF THE NATIONAL FIRE PROTECTION ASSOCIATION.

J. PERFORM THE FOLLOWING IN AREAS WHERE PAINTING OCCURS OR WHEN SPRINKLER PIPING IS PAINTED, AS SOON AS SPRINKLER HEADS ARE IN PLACE AND THE CONTRACTOR SHALL COVER EACH HEAD WITH A SMALL BAG OF AN UNDERWRITER'S APPROVED TYPE, WHICH SHALL BE REMOVED ONLY AFTER ALL PAINTING IS COMPLETE. AFTER THE BAG IS REMOVED, ALL HEADS SHALL BE CLEANED AND POLISHED.

K. PIPING MAY BE HUNG FROM STRUCTURAL STEEL BY MEANS OF BEAM ATTACHMENTS. ALL AUXILIARY STEEL REQUIRED FOR SUPPORT SHALL BE PROVIDED BY THIS TRADE. DO NOT HANG PIPING FROM DUCTWORK, EXCEPT A 1" DROP BRANCH TO A MAXIMUM OF TWO HEADS.

L. THE CONTRACTOR MAY COORDINATE WITH OTHER CONTRACTORS TO USE COMMON MEANS OF SUPPORT. SUBMIT FOR APPROVAL ALL PERTINENT DESIGN DATA RELATING TO THE SUPPORT AS WELL AS VERIFICATION OF THE RESPONSIBILITY FOR THE SUPPORT.

**19. STOCK OF SPARE SPRINKLER HEADS**

A. SUPPLY AT LEAST SIX SPARE SPRINKLERS (NEVER FEWER THAN SIX) SHALL BE MAINTAINED ON THE PREMISES SO THAT ANY SPRINKLERS THAT HAVE OPERATED OR BEEN DAMAGED IN ANY WAY CAN BE PROMPTLY REPLACED.

B. THE SPRINKLERS SHALL CORRESPOND TO THE TYPES AND TEMPERATURE RATINGS OF THE SPRINKLERS IN THE PROPERTY.

C. THE SPRINKLERS SHALL BE KEPT IN A CABINET LOCATED WHERE THE TEMPERATURE TO WHICH THEY ARE SUBJECTED WILL AT NO TIME EXCEED 100° F.

D. ONE SPRINKLER WRENCH AS SPECIFIED BY THE SPRINKLER MANUFACTURER SHALL BE PROVIDED IN THE CABINET FOR EACH TYPE OF SPRINKLER INSTALLED TO BE USED FOR THE REMOVAL AND INSTALLATION OF SPRINKLERS IN THE SYSTEM.

E. A LIST OF THE SPRINKLERS INSTALLED IN THE PROPERTY SHALL BE POSTED IN THE SPRINKLER CABINET.

F. THE LIST SHALL INCLUDE THE FOLLOWING:

1. SPRINKLER IDENTIFICATION NUMBER (S/N) IF EQUIPPED; OR THE MANUFACTURER, MODEL, ORIFICE, DEFLECTOR TYPE, THERMAL SENSITIVITY AND PRESSURE RATING.

2. GENERAL DESCRIPTION

3. QUANTITY OF EACH TYPE TO BE CONTAINED IN THE CABINET

4. ISSUE OR REVISION DATE OF THE LIST

**SPRINKLER FIELD EXAMINATION AND COORDINATION REQUIREMENTS**

1. THESE DRAWINGS ARE DIAGRAMMATIC AND INDICATE THE GENERAL ARRANGEMENT OF SYSTEMS AND WORK INDICATED UNDER THIS SECTION. THE CONTRACTOR SHALL CONSULT THE ARCHITECTURAL DRAWINGS AND DETAILS FOR EXACT LOCATIONS OF FIXTURES, AND EQUIPMENT.

2. THE CONTRACTOR SHALL FOLLOW THE DRAWINGS IN LAYING OUT WORK AND CHECK DRAWINGS OF OTHER TRADES TO VERIFY SPACES IN WHICH WORK WILL BE INSTALLED AND MAINTAIN MAXIMUM HEADROOM AND SPACE CONDITIONS AT ALL POINTS. WHERE HEADROOM OR SPACE CONDITIONS APPEAR INADEQUATE, THE ENGINEER SHALL BE NOTIFIED IN WRITING. THE INSTALLATION SHALL NOT PROCEED BEFORE RECEIVING THE ENGINEER'S WRITTEN INSTRUCTIONS.

3. IF DIRECTED BY THE ENGINEER, THE CONTRACTOR SHALL, WITHOUT EXTRA CHARGE, MAKE REASONABLE MODIFICATIONS IN THE APPROVED LAYOUT AS NEEDED TO PREVENT CONFLICT WITH WORK OF OTHER TRADES, MAINTAIN REQUIRED HEADROOM AND SPACE CONDITIONS, OR FOR PROPER EXECUTION OF THE WORK.

4. WHERE THE FIRE PROTECTION WORK WILL BE INSTALLED IN CLOSE PROXIMITY TO THE WORK OF OTHER TRADES, OR WHERE THERE IS EVIDENCE THAT THE WORK OF THE CONTRACTOR WILL INTERFERE WITH THE WORK OF OTHER TRADES, HE SHALL ASSIST IN WORKING OUT SPACES CONDITIONS TO MAKE A SATISFACTORY ADJUSTMENT. IF THE CONTRACTOR INSTALLS HIS WORK BEFORE COORDINATION WITH OTHER TRADES OR SO AS TO CAUSE INTERFERENCE WITH WORK OF OTHER TRADES, HE SHALL MAKE NECESSARY CHANGES IN HIS WORK TO CORRECT THE CONDITION WITHOUT EXTRA CHARGE.

5. STUDY THE DRAWINGS AND SPECIFICATIONS IN ORDER TO INSURE COMPLETENESS OF THE WORK REQUIRED UNDER THIS SECTION. INCIDENTAL WORK ITEMS NORMAL AND NECESSARY TO COMPLETE THE WORK, THOUGH NOT SHOWN OR SPECIFIED SHALL BE INCLUDED.

6. VERIFY ALL MEASUREMENTS AND CONDITIONS IN THE FIELD BEFORE STARTING WORK. INFORMATION REGARDING THE EXISTING FIRE PROTECTION SPRINKLER SYSTEM SHOWN ON THE PLANS HAVE BEEN TAKEN FROM PREVIOUS BUILDING SHOP DRAWINGS. ANY DEVIATIONS FOUND IN THE FIELD SHOULD BE REPORTED TO THE ENGINEER.

7. THIS CONTRACTOR SHALL SUBMIT LAYOUT DRAWINGS FOR APPROVAL BEFORE BEGINNING WORK. THESE DRAWINGS SHALL DEPICT ACTUAL FIELD CONDITIONS VERIFIED UNDER THIS CONTRACT. THEY MUST ALSO INDICATE ALL NEW AND EXISTING PIPING, SPRINKLER HEADS, ETC. DRAWINGS SHALL BE TO SCALE (1/4"=1'-0") AND INDICATE ALL PERTINENT DIMENSIONS, AND PIPE SIZES. THIS CONTRACTOR SHALL SUBMIT SEPIAS AND PRINTS OF THIS LAYOUT PLAN AND ALL CALCULATIONS TO THE ARCHITECT. QUANTITIES SHALL BE AS DIRECTED BY THE ENGINEER.

8. THIS CONTRACTOR SHALL SUBMIT DRAWINGS AND HYDRAULIC CALCULATIONS SIGNED AND SEALED BY A REGISTERED PROFESSIONAL ENGINEER FOR APPROVAL TO THE PORT AUTHORITY AND OBTAIN APPROVALS PRIOR TO THE INSTALLATION OF WORK. CONTRACTOR SHALL OBTAIN REQUIRED FIRE PROTECTION PLANS AND RISER DIAGRAMS FROM THE BUILDING OWNER. THIS CONTRACTOR SHALL VERIFY WITH BUILDING MANAGEMENT IF THE EXISTING BUILDING FIRE RESERVE CAPACITY IS ADEQUATE.




180 SYLVAN AVENUE, SUITE 3  
 ENGLEWOOD CLIFFS, NJ 07632  
 TEL 201 | 894 | 1000

**ENV-team.com**  
 ENVIRONETICS GROUP ARCHITECTS, P.C.  
 COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED.

**CLIENT:**  
**SSP AMERICA**  
 20408 BASHAN DRIVE  
 SUITE 300  
 ASHBURN, VA 20147

**PROJECT TEAM:**  
 ARCHITECT:  
 ENVIRONETICS GROUP ARCHITECTS  
 180 SYLVAN AVE.  
 ENGLEWOOD CLIFFS, NJ 07632

MEP ENGINEER  
 GUTH DECONZO CONSULTING ENGINEERS, PC  
 520 8TH AVENUE, SUITE 2201  
 NEW YORK, NY 10018  
 CERTIFICATE OF AUTHORIZATION  
 CA LIC. NO. 27747



John J. Guth, PE  
 FL LIC# 60427

**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: ISSUED FOR PERMIT  
 ISSUE DATE: 08/16/2024

**PROJECT NUMBER:** 24017G  
**DRAWN BY:** LR/DR  
**CHECKED BY:** SB


Copyright (c) by Envionetics, Inc. All Rights Reserved.

SHEET TITLE:

**SPRINKLER SPECIFICATIONS**

SHEET NUMBER:  
**SP-601**

# FIRE ALARM RISER DIAGRAM



**LEGEND:**

- NEW EQUIPMENT, CONDUIT OR WIRE
- - - EXISTING EQUIPMENT, CONDUIT OR WIRE TO REMAIN
- \*-X-X\* EXISTING EQUIPMENT, CONDUIT OR WIRE DISCONNECTED AND REMOVED

FIRE ALARM SYSTEM: CLASS B SYSTEM

\* CIRCUITS ARE CLASS B

EC SHALL PROVIDE NEW RELAY MODULE FOR MUSIC OVERRIDE. EC SHALL PROVIDE CAT6 CABLE FROM RELAY MODULE TO MUSIC SYSTEM AS REQUIRED.

THE CONTRACTOR TO VERIFY THAT THERE IS CAPACITY ON THE EXISTING LOOP TO ACCOMMODATE NEW FIRE ALARM DEVICES. IF THE EXISTING LOOP CANNOT ACCOMMODATE THE NEW FIRE ALARM DEVICES, CONTRACTOR SHALL FURNISH AND INSTALL A NEW FIRE ALARM BOOSTER PANEL

## FIRE ALARM (FA) NOTES

- DASHED LINES INDICATE EXISTING EQUIPMENT TO REMAIN. SOLID LINES INDICATE NEW.
- COMPLETE INSTALLATION OF THE FIRE ALARM SYSTEM SHALL BE COORDINATED WITH THE BUILDING'S FIRE ALARM SYSTEM MAINTENANCE CONTRACTOR.
- THE ELECTRICAL CONTRACTOR MUST CONTACT THE BUILDING'S FA MAINTENANCE CONTRACTOR PRIOR TO BID TO CONFIRM FINAL CONNECTION POINTS AND EQUIPMENT REQUIREMENTS. ALL MODIFICATIONS ARE TO BE APPROVED BY PAIRPORT.
- THE ELECTRICAL CONTRACTOR MUST SUBMIT WIRING DIAGRAMS (PRODUCED BY THE BASE BUILDING FA CONTRACTOR) TO THE ENGINEER FOR ANY MODIFICATIONS TO THE FIRE ALARM SYSTEM. THE ELECTRICAL CONTRACTORS BID SHALL INCLUDE TESTING BY THE BASE BUILDING FA CONTRACTOR.
- FINAL CONNECTION OF WIRING AT THE EXISTING TERMINAL BOX OR CONTROL PANEL SHALL BE MADE BY ELLENCO. ALL RELAYS, CIRCUIT EXTENDER PANELS, SUB-PANELS ETC. REQUIRED FOR A COMPLETE INSTALLATION AND AS DIRECTED BY THE BUILDING'S FIRE ALARM SYSTEM MAINTENANCE CONTRACTOR SHALL BE FURNISHED AND INSTALLED BY THE ELECTRICAL CONTRACTOR.
- ANY RELATED CONNECTION CHARGES AND PROGRAMMING CHARGES SHALL BE INCLUDED IN THE ELECTRICAL CONTRACTOR'S BID.
- ALL 120V REQUIREMENTS FOR ADDITIONAL EQUIPMENT REQUIRED BY THE BUILDING'S FA CONTRACTOR SHALL BE INCLUDED IN THE ELECTRICAL CONTRACTOR'S BID.
- WALL MOUNTED STROBES SHALL BE MOUNTED 80 INCHES ABOVE THE FLOOR OR 6" BELOW THE CEILING WHICHEVER IS LOWER.
- INSTALL FIRE ALARM EQUIPMENT, FIRE ALARM HORN AND STROBE LIGHTS (ADA TYPE, 75 CANDELA) UNITS AT LOCATION INDICATED ON THE PLAN. COORDINATE WITH ARCHITECT PRIOR TO INSTALLATION.
- FIRE ALARM SYSTEM TERMINAL AND JUNCTION LOCATIONS SHALL BE IDENTIFIED IN ACCORDANCE WITH NFPA STANDARD 70. TERMINAL BOXES SHALL BE PAINTED RED AND STENCILED IN WHITE LETTERS "FIRE ALARM".
- ELECTRICAL CONDUITS SHALL ENTER ONLY AT THE SIDES OR BOTTOM OF THE FIRE ALARM TERMINAL BOXES, CONTROL PANELS ETC, UNLESS DESIGNED AND APPROVED FOR ENTRY ON THE TOP.
- EXPOSED CONDUITS IN FINISHED AREAS ARE NOT ALLOWED. WHERE REQUIRED CHOP WALL AND PATCH TO CONCEAL CONDUIT AND RECESS DEVICE.
- ALL WIRING TYPES SHALL BE COORDINATED WITH THE BUILDING'S FA MAINTENANCE CONTRACTOR, SHALL BE APPROVED BY THE LOCAL FIRE DEPARTMENT AND ALL AUTHORITIES HAVING JURISDICTION.
- ALL BATTERY INSTALLATIONS SHALL BE DATED.
- ALL NEW FIRE DETECTION, NOTIFICATION, & ACTIVATION DEVICES MUST BE FLORIDA FIRE DEPARTMENT APPROVED. PROVIDE UL NUMBERS.
- ALL FIRE ALARM DEVICES SHALL BE BARCODED AND LABELED ON THE OUTSIDE OF THE DEVICE.
- FIRE ALARM SYSTEM MANUFACTURER IS ELLENCO.
- EC SHALL PROVIDE NEW PROGRAMMING AS NEEDED SO THAT ALL NEW & EXISTING DEVICES ACTIVATE TERMINAL MAIN FACP AND SCARESDALE CENTRAL MONITORING STATION AS ADDRESSABLE DEVICES.
- ALL NEW AND/OR RELOCATED FIRE DETECTION AND SUPPRESSION DEVICES SHALL BE INSTALLED, TESTED, AND ACCEPTED PRIOR OCCUPANCY. THIS ALSO APPLIES TO WIRING TO EXISTING DEVICES, WHICH ARE CUT AND RECONNECTED DURING THE PROPOSED WORK.
- EACH ALARM POINT MUST SEND THE CENTRAL STATION A RESTORE CODE FOR EACH POINT
- EC MUST PROVIDE A CONTINUOUS FIRE WATCH IF THERE IS A FIRE ALARM SYSTEM IMPAIRMENT IN THE SPACE DURING CONSTRUCTION.
- PAINT ALL FIRE ALARM CONDUIT JUNCTION BOXES & CONDOLETS RED.
- ALL PULL STATIONS MUST BE DOUBLE ACTION ACTIVATED. PAINT WHITE STRIPE FROM TOP LEFT TO BOTTOM RIGHT ON ALL PULL STATIONS.
- ALL FIRE ALARM DETECTION AND SUPPRESSION DEVICES SHALL TRANSMIT SIGNALS TO THE FIRE ALARM PANEL AND THE CENTRAL MONITORING STATION AS ADDRESSABLE DEVICES AND ALL ALARM POINTS MUST BE TRANSMITTED TO THE CENTRAL STATION
- WHERE RGS CONDUIT IS USED TO HOUSE WIRING, ALL ENDS SHALL BE CONNECTED USING COMPRESSION TYPE FITTINGS.
- LABEL ALL DEVICES CONTAINING END OF LINE RESISTORS (EOL)
- THE FIRE ALARM SYSTEM CONSISTS OF A FULLY ADDRESSABLE SYSTEM WITH AN INTELLIGENT FIRE ALARM NETWORK. FA SYSTEM SHALL BE MAINTAINED TO THE STANDARDS OF FLORIDA FIRE PREVENTION CODE AND THE UNIFORM STATEWIDE BUILDING CODE UNDER THE PROVISIONS APPLICABLE TO EXISTING BUILDINGS. TENANT FA DESIGN WILL BE SUBJECT TO REVIEW AND APPROVAL BY PAIRPORT PRIOR TO INSTALLATION.
- IN EXISTING FACILITIES, INSTALLATION OF NEW, AND/OR MODIFICATION OF FIRE ALARM SYSTEMS OR SPECIAL EXTINGUISHING SYSTEMS SHALL NOT BE UNDERTAKEN UNLESS WRITTEN PERMISSION IS OBTAINED FROM THE AIRPORT BUILDING CODES, ENGINEERING & MAINTENANCE DEPARTMENT AND THE AUTHORITY FIRE MARSHAL.
- THE FIRE ALARM SYSTEM SHALL BE DESIGNED, INSTALLED, CONFIGURED, PROGRAMMED, COMMISSIONED AND TESTED IN ACCORDANCE WITH THE EDITION OF NFPA 72, AS SPECIFIED IN THE FLORIDA FIRE CODE AND NFPA 72-2022, AIRPORT INSURANCE CARRIER GUIDELINES, AND IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS AND INSTRUCTIONS.
- THE FACP SHALL PROVIDE POWER, ANNUNCIATION, SUPERVISION, AND CONTROL FOR THE COMPLETE DETECTION, ALARM, AND MONITORING SYSTEM.
- FACP OPERATES FROM A 3 WIRE 120 VOLT SUPPLY FROM AN EMERGENCY SOURCE IF AVAILABLE AND BE PROVIDED WITH INTERNAL 24 VOLT UNINTERRUPTIBLE POWER SUPPLY (UPS) AND BACK-UP BATTERY.
- INITIATING AND INDICATING CIRCUITS SHALL NOT UTILIZE THE SAME RACEWAY UNLESS THE INITIATING CIRCUIT IS SHIELDED. NO WIRING OTHER THAN THAT DIRECTLY ASSOCIATED WITH FIRE ALARM SYSTEM SHALL BE PERMITTED IN FIRE ALARM RACEWAYS. ALL FIRE ALARM SYSTEM INITIATING DEVICES SHALL BE MARKED WITH A DEVICE ADDRESS ON BOTH BASE AND DEVICE. ALL FIRE ALARM JUNCTION AND PULL BOXES SHALL BE PAINTED RED; ALL BOX COVERS SHALL BE MARKED WITH THE CIRCUIT NUMBERS. ALL FIRE ALARM SYSTEM CONDUITS SHALL BE IDENTIFIED WITH RED MARKING EVERY 20'.
- THE ROOM NUMBERS AND BUILDING NUMBERS MUST BE INCLUDED ON THE FIRE ALARM SHOP DRAWINGS.
- FIRE ALARM OUTAGES REQUIRE 72 HOURS ADVANCE NOTICE TO FACILITIES ENGINEERING DIVISION.
- FIRE ALARM SHOP DRAWING PLANS ARE REQUIRED IF THERE ARE ANY DEVICES ADDED OR REMOVED WITH THE PROJECT.
- THE BUILDING FIRE ALARM SYSTEM SHALL TRANSMIT ALL ADDRESSABLE POINTS TO THE BUILDING'S FIRE ALARM SYSTEM IN ORDER TO PROVIDE THE COMPLETE STATUS OF ALL ALARMS, SUPERVISORY AND TROUBLE SIGNALS. THE AUDIBLE AND VISUAL DEVICES IN THE BUILDING SHALL BE FULLY INTEGRATED WITH THE BUILDING SYSTEM AND WORK IN CONJUNCTION WITH BUILDING AUDIBLE AND VISUAL DEVICES SO THAT ALL DEVICES IN A FIRE ZONE ARE ACTIVATED SIMULTANEOUSLY. EC SHALL FOLLOW ALL FLORIDA BUILDING CODE REQUIREMENTS.
- IN THE EVENT OF AN IMPAIRMENT TO THE FIRE PROTECTION SYSTEM IN THE AREA OF THE PROPOSED WORK DURING CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE FACILITIES MANGER WHOM SHALL COMPLETE AN IMPAIRMENT NOTIFICATION FORM AND FORWARD IT TO THE PERSONS INDICATED ON THAT FORM, AND MUST PROVIDE A CONTINUOUS FIRE WATCH.
- GC MUST HIRE BASE BUILDING FA CONTRACTOR FOR THEIR WORK. FINAL CONNECTIONS BY FLORIDA LICENSED FIRE PROTECTION COMPANY.
- CONNECTIONS ARE TO EXISTING BASE BUILDING CIRCUITS (INITIATING CIRCUITS AND ANNUNCIATION CIRCUITS), SIEMENS TO CONFIRM PANEL DESIGNATION AND LOCATION.
- FIRE ALARM OUTAGES REQUIRE 72 HOURS ADVANCE NOTICE TO FACILITIES ENGINEERING DIVISION.
- CONTRACTOR TO PROVIDE RE-PROGRAMMING OF ALL FIRE ALARM DEVICE PROGRAMMING IS ACCOMPLISHED BY SIEMENS BUILDING TECHNOLOGIES, 301-837-2852 FOR FURTHER INFO AND COORDINATION.
- CONTRACTOR TO PROVIDE FIRE ALARM SHOP DRAWING TO ENGINEER DURING CONSTRUCTION FOR REVIEW AND APPROVAL.
- COORDINATE WITH SIEMENS FOR ANY MODIFICATION TO THE EMS CONNECTION.
- CONTRACTOR WILL NEED TO FILE A SEPARATE FIRE ALARM PERMIT FOR THIS PROJECT AND PROVIDE IT FOR INSPECTIONS.
- ALL FIRE ALARM WIRING TO BE WITHIN RACEWAY.

### FIRE ALARM DRAWING LIST

|        |  |
|--------|--|
| FA-001 | FIRE ALARM NOTES, SYMBOLS AND DRAWING LIST |
| FA-101 | FIRE ALARM PLAN                            |

## FIRE ALARM SYMBOLS LIST

|         |   |
|---------|---|
|         | COMBINATION WALL MOUNTED BUILDING STANDARD HORN STROBE FIRE ALARM DEVICE WITH A MIN OF 75 CANDELA). COVERPLATE SHALL BE RED WITH WHITE LETTERS. MAXIMUM 80 INCHES ABOVE FINISHED FLOOR OR 6 INCHES BELOW CEILING WHICHEVER IS LOWER. 'CD'- CANDELA RATING |
|         | DUCT DETECTOR   |
|         | CEILING MOUNTED AREA SMOKE DETECTOR   |
|         | CEILING MOUNTED AREA HEAT DETECTOR  |
|         | TAMPER SWITCH   |
|         | FIRE ALARM PULL STATION   |
|         | MUSIC SHUTDOWN RELAY  |
|         | MONITORING MODULE   |
| N       | NEW   |
| ETR, EX | EXISTING TO REMAIN  |
| ER      | EXISTING RELOCATED  |
| ERR     | EXISTING TO BE REMOVED AND RELOCATED  |
| R       | EXISTING TO BE DISCONNECT AND REMOVED   |
| NAC     | NOTIFICATION APPLIANCE CIRCUIT  |
| SLC     | SIGNAL LINE CIRCUIT   |
| MFACP   | MAIN FIRE ALARM CONTROL PANEL   |

ALL FIRE ALARM DEVICES SHALL BE NEW U.O.N.

## FIRE ALARM WIRING

- ALL FIRE ALARM WIRING MUST BE HOUSED IN A MINIMUM OF 3/4" C. RGS. ALL CABLES SHALL MATCH BASE-BUILDING FA SYSTEM. COORDINATE WITH BASE BUILDING FIRE ALARM VENDOR FOR THE CABLE TYPE.
- WIRE AND CABLE: STROBE CIRCUITS - 14AWG TWISTED/SHIELDED PAIR TEFLON CABLE MINIMUM 150 DEG C INITIATING DEVICES - 16AWG TWISTED/SHIELDED PAIR TEFLON CABLE MINIMUM 150 DEG C
- POSITIVE WIRES SHALL BE COLOR CODED: RED  
NEGATIVE WIRES SHALL BE COLOR CODED: BLACK

**ENV**  
ARCHITECTURE + DESIGN  
180 SYLVAN AVENUE, SUITE 3  
ENGLEWOOD CLIFFS, NJ 07632  
TEL 201 | 894 | 1000  
ENV-team.com  
ENVIRONETICS GROUP ARCHITECTS, P.C.  
COPYRIGHT © BY ENVIRONETICS. ALL RIGHTS RESERVED

CLIENT:  
**SSP AMERICA**  
20408 BASHAN DRIVE  
SUITE 300  
ASHBURN, VA 20147

PROJECT TEAM:  
ARCHITECT:  
ENVIRONETICS GROUP ARCHITECTS  
180 SYLVAN AVE.  
ENGLEWOOD CLIFFS, NJ 07632  
MEP ENGINEER  
GUTH DECONZO CONSULTING  
ENGINEERS, PC  
520 8TH AVENUE, SUITE 2201  
NEW YORK, NY 10018  
CERTIFICATE OF AUTHORIZATION  
CA LIC. NO. 27747

John J. Guth, PE  
FL LIC# 60427

**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
6000 AIRPORT CIRCLE  
SARASOTA, FL 34243  
CLIENT: SSP AMERICA

| REV                 | DATE              | DESCRIPTION |
|---------------------|-------------------|-------------|
| DESIGN DELIVERABLE: | ISSUED FOR PERMIT |             |
| ISSUE DATE:         | 08/16/2024        |             |

PROJECT NUMBER: 24017G  
DRAWN BY:  
CHECKED BY:  
Copyright (c) by Environetics, Inc. All Rights Reserved.


SHEET TITLE:  
**FIRE ALARM RISER, NOTES, AND SYMBOL LIST**

SHEET NUMBER:  
**FA-001**

**ENV**  
**ARCHITECTURE + DESIGN**  
 180 SYLVAN AVENUE, SUITE 3  
 ENGLEWOOD CLIFFS, NJ 07632  
 TEL 201 | 894 | 1000  
 ENV-team.com  
 ENVIRONMENTALS GROUP ARCHITECTS, P.C.  
 COPYRIGHT © BY ENVIRONMENTALS. ALL RIGHTS  
 RESERVED


CLIENT:  
**SSP AMERICA**  
 20408 BASHAN DRIVE  
 SUITE 300  
 ASHBURN, VA 20147

PROJECT TEAM:  
 ARCHITECT:  
 ENVIRONMENTALS GROUP ARCHITECTS  
 180 SYLVAN AVE.  
 ENGLEWOOD CLIFFS, NJ 07632  
 MEP ENGINEER  
 GUTH DECONZO CONSULTING  
 ENGINEERS, P.C.  
 520 8TH AVENUE, SUITE 2201  
 NEW YORK, NY 10018  
 CERTIFICATE OF AUTHORIZATION  
 CA LIC. NO. 27747




John J. Guth, PE  
 FL LIC# 60427

**B-FB4 - WAHLBURGERS**  
**SARASOTA BRADENTON INTERNATIONAL**  
 6000 AIRPORT CIRCLE  
 SARASOTA, FL 34243  
 CLIENT: SSP AMERICA



**FIRE ALARM DEMOLITION PLAN**  
 SCALE: 1/4" = 1'-0"



| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |


DESIGN DELIVERABLE: ISSUED FOR PERMIT  
 ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G  
 DRAWN BY:  
 CHECKED BY:


Copyright (c) by Environmentals, Inc. All Rights Reserved.

SHEET TITLE:  
**FIRE ALARM DEMOLITION PLAN**

SHEET NUMBER:  
**FA-011**




John J. Guth, PE  
FL LIC# 60427



**PS**  
ETR  
EXISTING PULL STATION IS LOCATED  
WITHIN +/- 50 FEET AWAY FROM THE  
SPACE AND FULLY ACCESSIBLE TO  
THE PUBLIC.

**FIRE ALARM PLAN**  
SCALE: 1/4" = 1'-0"



A SMOKE ALARM SHOULD NOT BE INSTALLED WITHIN 3'  
HORIZONTALLY OF A SUPPLY REGISTER AND OUTSIDE  
THE DIRECT AIR FLOW FROM THE REGISTER. SMOKE  
DETECTOR IS PLACED AT MINIMUM 36" AWAY FROM THE  
SUPPLY DIFFUSER.

PROVIDE ADDITIONAL FA RELAY TO SHUT DOWN ALL  
SPEAKERS IN THE CASE OF FIRE ALARM EMERGENCY.

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |
|     |      |             |

DESIGN DELIVERABLE: ISSUED FOR PERMIT  
ISSUE DATE: 08/16/2024

PROJECT NUMBER: 24017G  
DRAWN BY:  
CHECKED BY:

Copyright (c) by Environetix, Inc. All Rights Reserved.

SHEET TITLE:  
**FIRE ALARM PLAN**

SHEET NUMBER:  
**FA-101**